

## Scarab-shaped seals, by Percy E. Newberry.

Newberry, Percy E. (Percy Edward), 1869-1949.

London, A. Constable and co., ltd., 1907.

<http://hdl.handle.net/2027/mdp.39015013775245>

# HathiTrust




[www.hathitrust.org](http://www.hathitrust.org)

**Public Domain in the United States,  
Google-digitized**

[http://www.hathitrust.org/access\\_use#pd-us-google](http://www.hathitrust.org/access_use#pd-us-google)

We have determined this work to be in the public domain in the United States of America. It may not be in the public domain in other countries. Copies are provided as a preservation service. Particularly outside of the United States, persons receiving copies should make appropriate efforts to determine the copyright status of the work in their country and use the work accordingly. It is possible that current copyright holders, heirs or the estate of the authors of individual portions of the work, such as illustrations or photographs, assert copyrights over these portions. Depending on the nature of subsequent use that is made, additional rights may need to be obtained independently of anything we can address. The digital images and OCR of this work were produced by Google, Inc. (indicated by a watermark on each page in the PageTurner). Google requests that the images and OCR not be re-hosted, redistributed or used commercially. The images are provided for educational, scholarly, non-commercial purposes.

**PAGE NOT  
AVAILABLE**








0-11,900

3 9015 01377 5245  
Digitized by Google



Original from  
UNIVERSITY OF MICHIGAN

THE UNIVERSITY OF MICHIGAN

DATE DUE

~~JUL 24 1989~~

AUG 09 1989

~~NOV 17 1989~~

~~JAN 08 1995~~



CATALOGUE GÉNÉRAL  
DES  
ANTIQUITÉS ÉGYPTIENNES  
DU MUSÉE DU CAIRE.  
—  
SCARAB-SHAPED SEALS.





SERVICE DES ANTIQUITÉS DE L'ÉGYPTE

*Cairo. Musée des antiquités égyptiennes.*

# CATALOGUE GÉNÉRAL

DES

# ANTIQUITÉS ÉGYPTIENNES

DU MUSÉE DU CAIRE.

N<sup>OS</sup>. 36001-37521.

NOTE TO THE READER

The paper in this volume is brittle or the inner margins are extremely narrow.

We have bound or rebound the volume utilizing the best means possible.

PLEASE HANDLE WITH CARE

FLAPED SEALS,

E. NEWBERRY.



LONDON:

ARCHIBALD CONSTABLE AND CO., LTD.

1907.

DT  
57  
C136c  
V.32

LONDON :  
HARRISON AND SONS, PRINTERS IN ORDINARY TO HIS MAJESTY,  
ST. MARTIN'S LANE, W.C.

2-28-25  
11040

## INTRODUCTION.

THE present Volume of the *Catalogue Général* contains drawings and descriptions of all the scarab-shaped seals, and scarabs bearing historical inscriptions, in the Museum; the amuletic and heart scarabs will be described in the volumes on amulets by Dr. Reisner.

The collection, numbering over 1500 specimens, is a representative one, and contains examples of all periods from the end of the Sixth Dynasty to the time of the last native Egyptian ruler, Nectanebo. In Twelfth Dynasty specimens it is especially rich, those from Dahchour being the finest examples of the period to be found in any museum in the world.

The collection was begun by M. Mariette in 1858, and it appears to have been much richer formerly than at present. A number of interesting specimens, described in the *Journal d'entrée du musée* and in Mariette's *Monuments Divers*, are not to be found now. Writing in 1889, Professor Flinders Petrie says that "the Scarabs [figured] in the *Monuments Divers* were all in the Boulak Museum, but most were stolen in 1878<sup>1</sup> . . . . I hear that they were mainly sold to General Cesnola for New York."<sup>2</sup> Some examples fortunately have been recovered by purchase (Nos. 36054, 36061, 36067, &c.), a few stray ones can be traced in private hands, but the greater number of those stolen have disappeared.

In describing the specimens I have carefully noted the length, width and height, and given a description of the inscription or device on the base,

<sup>1</sup> Professor Maspero tells me that, on account of the great inundation of 1878, the smaller monuments were packed up in boxes. There were three cases containing scarabs, and of these one box, containing nearly all the historical series, was stolen.

<sup>2</sup> Petrie, *Historical Scarabs*, p. 14.

together with remarks on the glaze, technique and preservation. The material is always noted, and the date, wherever it has been possible to fix it from a study of dated examples in other museums, has been given. Each specimen has been drawn and is figured in the plates. I also made drawings of the backs, and then sorted them into a series of six principal types, specimens of which will be found on Plates XIX–XXII. The types are :—

- (1) Scarabs without prothorax or elytra marked. (Plate XIX.)
- (2) Scarabs with prothorax slightly indicated but no elytra marked. (Plates XIX, XX.)
- (3) Scarabs with prothorax marked but no elytra shown. (Plate XX.)
- (4) Scarabs with prothorax and elytra marked. (Plate XXI.)
- (5) Scarabs with rounded prothorax and elytra marked. (Plate XXI.)
- (6) Scarabs with prothorax and elytra marked, with a V-shaped marking on either wing-case. (Plate XXII.)
- (7) Miscellaneous examples. (Plate XX.)

Only about a dozen specimens had numbers attached to them when I began their study, but the *Journal d'entrée du musée* has been carefully searched and a number have been identified ; these references to the *Journal d'entrée* and other publications have always been given. It was not possible to identify them all, for entries such as “Nos. 5453–5733 Gurneh, Juin, 1859, 280 scarabées avec légendes diverses,” or “Collection de 51 scarabées (pas royaux),” are frequent.

PERCY E. NEWBERRY.

INSTITUTE OF ARCHEOLOGY,  
UNIVERSITY OF LIVERPOOL.

CATALOGUE GÉNÉRAL  
DES  
ANTIQUITÉS ÉGYPTIENNES  
DU MUSÉE DU CAIRE.

SCARAB-SHAPED SEALS.

**36001. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '008.—Plate I.—Sheikh abd el Kurneh.

DESCRIPTION: Inscribed with the name of Khuf[u]. *Back*, rounded prothorax and elytra marked, as on No. 36293 (Plate V).

DATE: Twenty-fourth Dynasty.

GLAZE: rich deep blue, of very fine quality.

TECHNIQUE: moulded back, fine cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25716. Found in a tomb at Sheikh abd el Kurneh, together with Nos. 36002, 36293, 36296 and 36596. PETRIE, *Hist. Scarabs*, No. 1837.

**36002. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate I.—Sheikh abd el Kurneh.

DESCRIPTION: Inscribed with the name of Nefer-ka-Ra. *Back*, rounded prothorax and elytra marked, as on No. 36293 (Plate V).

DATE: Twenty-fourth Dynasty.

GLAZE: rich deep blue, very fine quality.

TECHNIQUE: moulded back, very fine cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25718. Found in a tomb at Sheikh abd el Kurneh, together with Nos. 36001, 36293 and 36596. PETRIE, *Hist. Scarabs*, No. 1838.

*Catal. du Musée*, n. 36001.

1

**36003. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m. '004.—Plate I.

DESCRIPTION: Inscribed with the name of Men-ka-Ra. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty or later.

GLAZE: light blue.

TECHNIQUE: poor.

PRESERVATION: perfect.

BIBL.: *Journal d'entré du Musée*, No. 2522. Provenance unknown. MASPERO, *Slip Cat.*, No. 3642. PETRIE, *Hist. Scarabs*, No. 35.

**36004. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '033. Width, 0 m '022. Height, 0 m '014. Plate I.

DESCRIPTION: Inscribed with the name and titles of Men-ka-Ra. Above the cartouche is a human-headed sphinx, wearing the double feathers upon his head. Below is a *neb*-sign. *Back*, prothorax and elytra marked, with curved lines on prothorax and elytra.

DATE: Twenty-fifth Dynasty (?).

GLAZE: green (turned yellowish).

TECHNIQUE: coarse.

PRESERVATION: worn round edges.

BIBL.: MASPERO, *Slip Cat.*, No. 3643. PETRIE, *Hist. Scarabs*, No. 938.

**36005. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '032. Width, 0 m '022. Height, 0 m '012.—Plate I.

DESCRIPTION: Inscribed with the name of Men-ka-Ra. On either side of the name are uraei and *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-fifth Dynasty (?).

GLAZE: green (turned light brown).

TECHNIQUE: good, with bold deep cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3649. PETRIE, *Hist. Scarabs*, No. 937.

**36006. Scarab-shaped Seal.**—Faience, glazed.—Length, 0 m '009. Width, 0 m '01. Height, 0 m '006.—Plate I.

DESCRIPTION: Inscribed with the name of Unas. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: finely cut.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3645. PETRIE, *Hist. Scarabs*, No. 55.

- 36007. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .008. Width, 0 m .006. Height, 0 m .003.—Plate I.

DESCRIPTION: Inscribed with the name of Unas. *Back*, prothorax slightly indicated but no elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: roughly cut.

PRESERVATION: head of beetle chipped, otherwise perfect.

- 36008. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .018. Width, 0 m .012. Height, 0 m .008.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-kheper-Ra; hieroglyphic signs in the field. *Back*, rounded prothorax and elytra marked.

DATE: Twelfth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: finely cut.

PRESERVATION: perfect.

BIBL: NEWBERRY, *Scarabs*, Plate IX, 19.

- 36009. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .006.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-ka-Ra in a cartouche; hieroglyphic signs in the field. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty.

GLAZE: green.

TECHNIQUE: finely cut.

PRESERVATION: worn slightly on back, otherwise perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3659. PETRIE, *Hist. Scarabs*, No. 248.

- 36010. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .006.—Plate I.—Kurneh.

DESCRIPTION: Inscribed with the name of Senusret. *Back*, prothorax and elytra marked with a  $\nabla$  on either wing-case.

DATE: Eighteenth Dynasty (?).

GLAZE: green, of poor quality and turned brown.

TECHNIQUE: good cutting.

PRESERVATION: fair.

BIBL: *Journal d'entrée du Musée*, No. 20422. MASPERO, *Slip Cat.*, No. 3653.

PETRIE, *Hist. Scarabs*, No. 202.

*Catal. du Musée*, n. 36001.

1.



- 36011. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '018. Height, 0 m '012.—Plate I.—Abydos.

DESCRIPTION: Inscribed with the name of Sekhem-se-uaz-taui-Ra Sebek-hetep *ar ne neter âtef* Mentu-hetep. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: green, crackled and turned light green.

TECHNIQUE: medium cutting.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3665, Abydos, No. 1383. PETRIE, *Hist. Scarabs*, No. 292. NEWBERRY, *Scarabs*, Plate X, 2.

- 36012. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '009.—Plate I.

DESCRIPTION: Inscribed with the name of Sekhem-se-uaz-taui-Ra Sebekhetep *mes ne met seten* Auhet-abu. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: green, turned brown and mostly worn off.

TECHNIQUE: good cutting.

PRESERVATION: badly worn and chipped in places.

BIBL.: *Journal d'entrée du Musée*, No. 5038 (Coll. Huber). MASPERO, *Slip Cat.*, No. 3664 (No. 521). PETRIE, *Hist. Scarabs*, No. 290.

- 36013. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '01.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-sesher-Ra *ar ne âtef neter* Ha-ankh-ef. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: blue, turned greyish.

TECHNIQUE: medium cutting.

PRESERVATION: back slightly worn, otherwise perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3667, Abydos, No. 1383. PETRIE, *Hist. Scarabs*, No. 293.

- 36014. Scarab-shaped Seal.**—Steatite, glazed. Length, 0 m '013. Width, 0 m '008. Height, 0 m '004.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-nefer-Ra. *Back*, rounded prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29966, Upper Egypt.

- 36015. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·012.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-nefer-Ra, Sebek-hetep. *Back*, prothorax and elytra marked (see Plate XX).

DATE: Thirteenth Dynasty.

GLAZE: green, crackled and turned a brownish-grey.

TECHNIQUE: medium cutting.

PRESERVATION: slightly chipped.

BIBL.: *Journal d'entrée du Musée*, No. 34034. Bought.

- 36016. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-nefer-Ra Sebek-hetep. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Thirteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: medium cutting.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du musée*, No. 27005. (Bought 1885.)

- 36017. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·025. Width, 0 m ·018. Height, 0 m ·011.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-nefer-Ra *ir ne átef neter* Ha-ankh-ef. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: green, slightly crackled.

TECHNIQUE: rough but bold cutting.

PRESERVATION: good, but slightly worn on top of back.

BIBL.: NEWBERRY, *Scarabs*, Plate X, 8.

- 36018. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·014. Height, 0 m ·008.—Plate I.—Licht.

DESCRIPTION: Inscribed with a similar inscription to No. 36017. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: a bright blue, of fine quality.

TECHNIQUE: medium cutting.

PRESERVATION: back partly broken away and edges chipped.

BIBL.: *Journal d'entrée du Musée*, No. 31373.

- 36019. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '010.—Plate I.

DESCRIPTION: Inscribed with the name of Sebek-hetep *nes ne met seten Kemá*.  
*Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: grey-green, of medium quality.

TECHNIQUE: good cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 28361. Bought. PETRIE, *Hist. Scarabs*, No. 309.

- 36020. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '008.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-hetep-Ra Sebek-hetep. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: green, thin and slightly cracked.

TECHNIQUE: fair cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 2524. Provenance unknown. MASPERO, *Slip Cat.*, No. 3666. MAR., *M.D.*, Plate 48 p. PETRIE, *Hist. Scarabs*, No. 322. NEWBERRY, *Scarabs*, Pl. X, 16.

- 36021. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '010.—Plate I.

DESCRIPTION: Inscribed with the name of Mer-nefer-Ra Ay. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: grey-brown.

TECHNIQUE: fair, with deep cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 5020 (Coll. Huber). MASPERO, No. 3668. MAR., *M.D.*, Plate 48 o. PETRIE, *Hist. Scarabs*, No. 325. NEWBERRY, *Scarabs*, Plate X, 19.

- 36022. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '007.—Plate I.—Tell Basta (1901).

DESCRIPTION: Inscribed with the name of Mer-nefer-Ra. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: grey-brown.

TECHNIQUE: good, sharp cutting.

PRESERVATION: slightly chipped on under surface and on back.

BIBL.: *Journal d'entrée du Musée*, No. 35094.

- 36023. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate I.—Licht.

DESCRIPTION: Similar to No. 36022. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: light blue, of fair quality.

TECHNIQUE: fine deep cutting.

PRESERVATION: chipped round edges and on back.

BIBL.: *Journal d'entr e du Mus e*, No. 31375.

- 36024. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate I.—Licht.

DESCRIPTION: Similar to No. 36022. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: blue, and of very fine quality.

TECHNIQUE: fine deep cutting.

PRESERVATION: excellent.

BIBL.: *Journal d'entr e du Mus e*, No. 31374.

- 36025. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·009.—Plate I.—Memphis.

DESCRIPTION: Inscribed with the name of Kha-ka-Ra and a rope pattern border. *Back*, prothorax indicated as No. 37179.

DATE: Thirteenth Dynasty.

GLAZE: green, crackled and gone brown in places.

TECHNIQUE: fine deep cutting.

PRESERVATION: good, but slightly chipped at edges.

BIBL.: MASPERO, *Slip Cat.*, No. 3661. PETRIE, *Hist. Scarabs*, No. 236.

- 36026. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate I.

DESCRIPTION: Inscribed with the name of the Sa seten Sa-Hather. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: light blue, of very fine quality.

TECHNIQUE: cutting very fine.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3796, Abydos, No. 1394. PETRIE, *Hist. Scarabs*, No. 299. NEWBERRY, *Scarabs*, Plate XII, 3. MAR., *Cat. Ab.*, 539.

**36027. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '20. Width, 0 m '14. Height, 0 m '01.—Plate I.

DESCRIPTION: Inscribed with the name of the Heq Khaskhet Khfan: in the field divided from the name by vertical lines are hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, thin in parts.

TECHNIQUE: fine deep cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 30458. Bought.

**36028. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '21. Width, 0 m '14. Height, 0 m '01.—Plate I.—Hou.

DESCRIPTION: Inscribed with the name of Yabek-her; in the field on either side of the name is a loop pattern, disconnected above. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, thin in places.

TECHNIQUE: deep and good cutting.

PRESERVATION: chipped round edges.

BIBL.: *Journal d'entrée du Musée*, No. 33995. MACE in PETRIE'S *Diospolis Parva*, Plate XLI, No. 12 and p. 53. NEWBERRY, *Scarabs*, Plate XXIII, 3.

**36029. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '21. Width, 0 m '15. Height, 0 m '012.—Plate I.

DESCRIPTION: Inscribed with the name of Uazed: in the field is a loop pattern disconnected above. *Back*, prothorax slightly indicated, but no elytra marked.

DATE: Hyksos Period.

GLAZE: blue, turned whitish.

TECHNIQUE: cutting of hieroglyphs deep and bold.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3674. PETRIE, *Hist. Scarabs*, No. 349. NEWBERRY, *Scarabs*, Plate XXIII, 9.

**36030. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '20. Width, 0 m '014. Height, 0 m '009.—Plate I.

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field is a loop pattern, disconnected above and below. Pierced longitudinally with three holes. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, thin in places.

TECHNIQUE: good cutting.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 31039. MASPERO, *Slip Cat.*, No. 3672, Abydos, No. 1391.

- 36031. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate I.

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field is a loop pattern disconnected above and below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, thin.

TECHNIQUE: good deep cutting.

PRESERVATION: good.

BIBL: MASPERO, *Slip Cat.*, No. 3671, Abydos, No. 1391.

- 36032. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate I.

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field a loop pattern disconnected above and below. *Back*, prothorax indicated as No. 36364.

DATE: Hyksos Period.

GLAZE: green, turned yellowish.

TECHNIQUE: fine, with delicately cut back.

PRESERVATION: back and edges slightly chipped.

BIBL: MASPERO, *Slip Cat.*, No. 3672. PETRIE, *Hist. Scarabs*, No. 120.

- 36033. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate I.

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field a loop pattern disconnected above and below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, thin and gone white in parts.

TECHNIQUE: delicately cut.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3671, Abydos, No. 1391.

- 36034. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '010.—Plate I.—Kurneh (1860).

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field a loop pattern disconnected above and below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turned a dull reddish-brown.

TECHNIQUE: cutting good.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 13001. MASPERO, *Slip Cat.*, No. 3669.

PETRIE, *Hist. Scarabs*, No. 121.

*Catal. du Musée*, n. 36001.

- 36035. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·010.—Plate I.

DESCRIPTION: Inscribed with the name of Maa-ab-Ra: in the field a loop pattern, disconnected above and below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, crackled and rather thin on back.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3670, Abydos, No. 1391. PETRIE, *Hist. Scarabs*, No. 119.

- 36036. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate I.

DESCRIPTION: Inscribed with the name of Shesha: in the field, divided from the name by vertical lines, are hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, turned a grey-green.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3646. PETRIE, *Hist. Scarabs*, No. 71.

- 36037. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·016. Height, 0 m ·01.—Plate I.

DESCRIPTION: Inscribed with the name of Shesha surrounded by a rope-pattern border. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, turned a greyish-brown.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 30675.

- 36038. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·015. Height, 0 m ·01.—Plate I.—Sheikh es Selam (1899).

DESCRIPTION: Inscribed with the name of Shesha; in the field, divided from the name by vertical lines, are hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 34008.

- 36039. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '008.—Plate I.

DESCRIPTION: Inscribed with the name of Shesha: in the field, divided from the name by vertical lines, are hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, thin in parts.

TECHNIQUE: medium cutting.

PRESERVATION: slightly broken on back.

BIBL: MASPERO, *Slip Cat.*, No. 3646.

- 36040. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '009.—Plate I.—Abydos (1874).

DESCRIPTION: Inscribed with the name of Aa-mu: in the field, divided from the name by vertical lines, are hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green, unequally distributed.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL: *Journal d'entré du Musée*, No. 22157. MASPERO, *Slip Cat.*, No. 3687. PETRIE, *Hist. Scarabs*, No. 130.

- 36041. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-user-Ra; in the field, divided from the name by vertical lines, are  $\cong$  lines. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turned brown.

TECHNIQUE: poor cutting.

PRESERVATION: good.

- 36042. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate I.

DESCRIPTION: Inscribed with the name of Kha-mu (?); in the field, divided from the name by vertical lines, are vertical and horizontal bands. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: greeny-blue.

TECHNIQUE: coarse cutting.

PRESERVATION: back flaked, otherwise perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3673, Abydos, No. 1391. PETRIE, *Hist. Scarabs*, No. 142.



- 36043. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate I.

DESCRIPTION : Inscribed with the name of Qar (?); hieroglyphs in the field. *Back*, Shesha type.

DATE : Hyksos Period.

GLAZE : green, unequally distributed and gone brown in parts.

TECHNIQUE : coarse cutting.

PRESERVATION : good.

BIBL : MASPERO, *Slip Cat.*, No. 1683.

- 36044. Scarab-shaped Seal.**—Mother of Emerald.—Length, 0 m '024. Width, 0 m '016. Height, 0 m '012.—Plate I.

DESCRIPTION : Inscribed with the name and titles of a Royal Seal-bearer named Khensu : a double line runs around the name. *Back*, prothorax and elytra marked.

DATE : Thirteenth—Seventeenth Dynasty.

TECHNIQUE : medium, cutting not deep.

PRESERVATION : good.

- 36045. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '012.—Plate I.

DESCRIPTION : Inscribed with the name and titles of a Messenger of the Oasis named Uas-hetep : a rope pattern runs around the name. *Back*, prothorax and elytra marked (see Plate XXI.)

DATE : Thirteenth—Seventeenth Dynasty.

GLAZE : dark blue, gone whity-yellow in parts.

TECHNIQUE : good cutting.

PRESERVATION : good.

BIBL : MASPERO, *Slip Cat.*, No. 1686. MAR., *M.D.*, Pl. 52 *h*. PETRIE, *Hist. Scarabs*, No. 387. NEWBERRY, *Scarabs*, Plate XVII, 22.

- 36046. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '00(?).—Plate I.—Mitraheny.

DESCRIPTION : Inscribed with the name and titles of an officer named Se-hetep-ab ; a continuous loop-pattern surrounds the name. Remains of a bronze pin in hole. *Back*, cut away.

DATE : Thirteenth—Seventeenth Dynasty.

GLAZE : green, turned brown.

TECHNIQUE : very good cutting.

PRESERVATION : back broken away and edges chipped.

BIBL. : on label :—Found at Mitraheny.

- 36047. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·027. Width, 0 m ·019. Height, 0 m ·012.—Plate I.

DESCRIPTION: Inscribed with the name and titles of a Scribe of the Army named Nehy, born of the Lady Kesen. *Back*, see Plate XXI.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, unequally distributed and crackled; turned brown in thin parts.

TECHNIQUE: cutting deep and very good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 30456. (Bought.) NEWBERRY, *Scarabs*, Plate XLIII, 5.

- 36048. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·01.—Plate I.

DESCRIPTION: Inscribed with the name and titles of an official named Sebek-hetep, son of Mentu-hetep. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: rich blue, crackled.

TECHNIQUE: very good cutting and back finely detailed.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 2523, provenance unknown. MASPERO, *Slip Cat.*, No. 3795, Abydos, No. 1397. PETRIE, *Hist. Scarabs*, No. 390. MAR., *Mon. Div.*, Plate 48 n. MAR., *Cat. Ab.*, p. 541. Cf. NEWBERRY, *Scarabs*, p. 127–128.

- 36049. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·025. Width, 0 m ·017. Height, 0 m ·012.—Plate I.

DESCRIPTION: Inscribed with the name and titles of an official named User: a double line runs around the name. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green, of a fine colour and quality.

TECHNIQUE: deep and bold cutting; modelling of back good.

PRESERVATION: worn slightly on back.

BIBL.: *Journal d'entrée du Musée*, No. 30457. (Bought.) NEWBERRY, *Scarabs*, Plate XLIII, 32.

- 36050. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate I.

DESCRIPTION: Inscribed with the name and titles of an official named Ankef. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, gone whitly-grey.

TECHNIQUE: medium cutting.

PRESERVATION: chipped round edges.

BIBL.: PETRIE, *Hist. Scarabs*, No. 441. NEWBERRY, *Scarabs*, Plate XIII, 27.

**36051. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '026. Width, 0 m '019. Height, 0 m '012.—Plate I.

DESCRIPTION: Inscribed with the name of an official. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: fine green, of excellent quality.

TECHNIQUE: very fine; cutting bold and modelling of beetle exquisite.

PRESERVATION: good, but slightly chipped on edge.

BIBL: MASPERO, *Slip Cat.*, No. 1687. PETRIE, *Hist. Scarabs*, No. 472.

**36052. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '009.—Plate I.—Mitrahény (1900).

DESCRIPTION: Inscribed with the name and titles of a priest named Amen<sup>y</sup>: a double line runs around the name. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: light blue, turning white.

TECHNIQUE: fine and delicate cutting.

PRESERVATION: slightly chipped on edge.

BIBL: *Journal d'entrée du Musée*, No. 34083.

**36053. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate I.—Kurneh (1858).

DESCRIPTION: Inscribed with the name and titles of an official named Neb-pu; a continuous loop-pattern runs around the name. *Back*, rounded prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: good cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 3349. MASPERO, *Slip Cat.*, No. 3793.

PETRIE, *Hist. Scarabs*, No. 418. NEWBERRY, *Scarabs*, Plate XVI, 22.

**36054. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate I.—Abydos.

DESCRIPTION: Inscribed with the name of an official: a continuous loop-pattern runs around the name. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green.

TECHNIQUE: medium cutting.

PRESERVATION: back and edges chipped.

BIBL: MASPERO, *Slip Cat.* No. 3042, Abydos, No. 1396. Stolen in 1878 and rebought in 1882. MAR., *Cat. Ab.*, p. 540. PETRIE, *Hist. Scarabs*, No. 417.

NEWBERRY, *Scarabs*, Plate XVI, 17.

- 36055. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·03. Width, 0 m ·021. Height, 0 m ·012.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official with a continuous loop pattern around it. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: boldly cut.

PRESERVATION: back flaked away.

BIBL.: MASPERO, *Slip Cat.*, No. 3794. PETRIE, *Hist. Scarabs*, No. 437. NEWBERRY, *Scarabs*, Plate XV, 4.

- 36056. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m ·024. Width, 0 m ·016. Height, 0 m ·009.—Plate II.—Abydos.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: perfect.

BIBL.: *Journal d'entré du Musée*, No. 25037. MASPERO, *Slip Cat.*, No. 3792. PETRIE, *Hist. Scarabs*, No. 330.

- 36057. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·015. Height, 0 m ·01.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, gone a whitish-grey.

TECHNIQUE: medium cutting.

PRESERVATION: chipped on edges.

BIBL.: MASPERO, *Slip Cat.*, No. 1691. PETRIE, *Hist. Scarabs*, No. 468. NEWBERRY, *Scarabs*, XLIII, 7.

- 36058. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·025. Width, 0 m ·016. Height, 0 m ·01.—Plate II.

DESCRIPTION: Inscribed with the name of an official. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, of very fine quality.

TECHNIQUE: bold but rather coarse cutting.

PRESERVATION: slightly worn on back.

BIBL.: MASPERO, *Slip Cat.*, No. 1689. PETRIE, *Hist. Scarabs*, No. 471.

**36059. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '027. Width, 0 m '019. Height, 0 m '013.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official with a loop pattern around it. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: very good and deep cutting.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 30455. Bought. NEWBERRY, *Scarabs*, XLIII, 30.

**36060. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '01.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty.

GLAZE: blue, of a medium colour but very fine.

TECHNIQUE: cutting of back and hieroglyphs very delicate.

PRESERVATION: back slightly chipped.

BIBL: NEWBERRY, *Scarabs*, p. 126.

**36061. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '01. Plate II.

DESCRIPTION: Inscribed with the name of an official with a coil pattern and hieroglyphs around it. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: fine blue, thick on back.

TECHNIQUE: very delicate and beautiful work.

PRESERVATION: chipped on back.

BIBL: MASPERO, *Slip Cat.*, No. 3043, Abydos, No. 1396. Stolen in 1878 and bought again in 1882. NEWBERRY, *Scarabs*, XIV, 21.

**36062. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '011.—Plate II.—Abydos.

DESCRIPTION: Inscribed with the name and titles of an official: a rope pattern around the inscription. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: light blue, of very fine quality.

TECHNIQUE: exquisitely cut.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 22014. MASPERO, *Slip Cat.*, No. 1690. PETRIE, *Hist. Scarabs*, No. 378. NEWBERRY, *Scarabs*, Plate XVII, 26.

- 36063. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate II.—Kurneh.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax and elytra marked.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green, gone grey in places.

TECHNIQUE: coarse cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 20429. MASPERO, *Slip Cat.*, No. 1685, Abydos, 1397. PETRIE, *Hist. Scarabs*, No. 173. NEWBERRY, *Scarabs*, Plate XI, 13.

- 36064. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '01.—Plate II.—Dahchour.

DESCRIPTION: Inscribed with the name of a private person. *Back*, modelled in the form of a hedgehog (see Plate II).

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, gone yellowish-white.

TECHNIQUE: good cutting.

PRESERVATION: good.

BIBL: DE MORGAN, *Dahchour*, I, p. 52, fig. 113.

- 36065. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '026. Width, 0 m '018. Height, 0 m '012.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. A loop pattern runs around the inscription. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Thirteenth—Seventeenth Dynasty.

TECHNIQUE: cutting of hieroglyphs poor, modelling of back good.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 1688. PETRIE, *Hist. Scarabs*, No. 407. NEWBERRY, *Scarabs*, Plate XIII, 34.

- 36066. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '016. Height, 0 m '011.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. A continuous loop pattern runs around the inscription. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: very good modelling and cutting.

PRESERVATION: perfect.

BIBL: NEWBERRY, *Scarabs*, Plate XLIII, 29.

*Catal. du Musée*, n. 36001.

3

**36067. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '025. Width, 0 m '017. Height, 0 m '01.—Plate II.—Kurneh.

DESCRIPTION: Inscribed with the name and titles of an official. A continuous loop pattern runs around the inscription. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: good cutting and modelling.

PRESERVATION: edges and back chipped.

BIBL.: *Journal d'entrée du Musée*, No. 20428. MASPERO, *Slip Cat.*, No. 3041, Abydos, 1396. Stolen and rebought in 1882. PETRIE, *Hist. Scarabs*, No. 436. NEWBERRY, *Scarabs*, Plate XVI, 3.

**36068. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate II.—Tell el Yahûdiyeh.

DESCRIPTION: Inscribed with the name and titles of an official. A double rope pattern runs around the inscription. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, turned white in places.

TECHNIQUE: cutting of hieroglyphs bold and good: modelling of back excellent.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 27712. NEWBERRY, *Scarabs*, Plate XLIII, 33.

**36069. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '010.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax indicated as No. 36364.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, of medium colour, very finely laid on.

TECHNIQUE: cutting of hieroglyphs and modelling of back very good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3799, Abydos, 1394. PETRIE, *Hist. Scarabs*, No. 406. NEWBERRY, *Scarabs*, Plate XII, 16.

**36070. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '09.—Plate II.

DESCRIPTION: Inscribed with the name and titles of an official. A double rope pattern runs around the inscription. *Back*, rounded prothorax and elytra.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: very fine.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3688. NEWBERRY, *Scarabs*, Plate XLIII, 24.

- 36071. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Aahmes I. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: bright green, of fine quality.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: excellent.

BIBL.: *Journal d'entrée du Musée*, No. 25188. Given by M. Carey, 1882. MASPERO, *Slip Cat.*, No. 3097. PETRIE, *Hist. Scarabs*, No. 763. NEWBERRY, *Scarabs*, Plate XXVI, 8.

- 36072. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '01.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Aahmes I. *Back*, broken away.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of exquisite quality.

TECHNIQUE: good.

PRESERVATION: back flaked away.

BIBL.: MASPERO, *Slip Cat.*, No. 3684.

- 36073. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate II.—Abydos (1881).

DESCRIPTION: Inscribed with the name of Aahmes-nefret-ari. *Back*, prothorax indicated as No. 37132.

DATE: Early Eighteenth Dynasty.

GLAZE: green, slightly crackled.

TECHNIQUE: medium cutting.

PRESERVATION: worn on back and edges chipped.

BIBL.: *Journal d'entrée du Musée*, No. 25089. MASPERO, *Slip Cat.*, No. 3685. PETRIE, *Hist. Scarabs*, No. 781.

- 36074. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the name and titles of Nefret-ari. *Back*, round prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of exquisite quality, but gone white in places.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3686. PETRIE, *Hist. Scarabs*, No. 784.



**36075. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '016. Width 0 m '012. Height, 0 m '001.—Plate II.—Kurneh (1859).

DESCRIPTION: Inscribed with the name of Aahmes-nefret-ari and mounted in a gold fundu. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: finely cut.

PRESERVATION: broken in three places: the lower part wanting.

BIBL.: *Journal d'entrée du Musée*, No. 3370. MASPERO, *Slip Cat.*, No. 3694. PETRIE, *Hist. Scarabs*, No. 785.

**36076. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '006.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Amenhetep I. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3689. PETRIE, *Hist. Scarabs*, No. 806.

**36077. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '001.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Amenhetep I. *Back*, broken away.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: coarse cutting.

PRESERVATION: back broken away.

BIBL.: MASPERO, *Slip Cat.*, No. 3692. PETRIE, *Hist. Scarabs*, No. 307.

**36078. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate II.—Kurneh (1858).

DESCRIPTION: Inscribed with the prenomen of Amenhetep I: hieroglyphs in the field. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, uneven and slightly crackled.

TECHNIQUE: medium modelling and cutting.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 2539. MASPERO, *Slip Cat.*, No. 3688. PETRIE, *Hist. Scarabs*, No. 810.

- 36079. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '01.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Amenhetep I within an oval. In the field, a hawk with outspread wings and a *neb*-sign below. *Back*, rounded prothorax and elytra marked.


DATE: Early Eighteenth Dynasty.

TECHNIQUE: very good cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entr e du Mus e*, No. 5040 (Coll. Huber). MASPERO, *Slip Cat.*, No. 3691. PETRIE, *Hist. Scarabs*, No. 823.

- 36080. Scarab-shaped Seal.**—Red carnelian.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Amenhetep I within an oval. In the field on either side are two hawks with outspread wings facing . *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: very finely cut.

PRESERVATION: perfect, save for a chip on the edge.

- 36081. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '03. Width, 0 m '021. Height, 0 m '014.—Plate II.—Ekhm m.

DESCRIPTION: Inscribed with the name of Amenhetep written within a  $\square$ . Above is the title Sa Ra, and at the sides and beneath are hieroglyphic signs; the whole being surrounded by a double rope pattern. The back is very delicately cut and the thorax dotted. (See Plate II.)

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine quality but not very even.

TECHNIQUE: exquisitely cut.

PRESERVATION: perfect.

BIBL: *Journal d'entr e du Mus e*, No. 27681.

- 36082. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the name of Amenhetep. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, unevenly laid on.

TECHNIQUE: coarse and lumpy.

PRESERVATION: fair.

**36083. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate II.

DESCRIPTION: Inscribed on the base with the name of Amenhetep. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: poorish.

PRESERVATION: worn on back.

**36084. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·008.—Plate II.

DESCRIPTION: Inscribed with the name of Amenhetep. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green, uneven.

TECHNIQUE: rough.

PRESERVATION: good.

**36085. Scarab-shaped Seal.**—Black steatite.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate II.

DESCRIPTION: Inscribed with the prenomem of Amenhetep I within a cartouche; hieroglyphic signs in the field. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: fair modelling and cutting.

PRESERVATION: much worn.

**36086. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate II.

DESCRIPTION: Inscribed with the prenomem of Thothmes I within a cartouche: a double line around the margin. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine colour and evenness.

TECHNIQUE: very finely cut.

PRESERVATION: excellent.

BIBL.: PETRIE, *Hist. Scarabs*, No. 861 (?).

- 36087. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes I. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone yellowy-brown in places.

TECHNIQUE: very good.

PRESERVATION: excellent.

- 36088. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes I; on either side are hawks with wings outspread and facing  $\rightarrow \leftarrow$ . *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, thin but of good quality.

TECHNIQUE: very finely cut.

PRESERVATION: good.

BIBL.: *Journal d'entr e du Mus e*, No. 31975.

- 36089. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes I. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Early Eighteenth Dynasty.

GLAZE: green, of very fine quality.

TECHNIQUE: exquisite cutting and fine detail.

PRESERVATION: perfect.

BIBL.: *Journal d'entr e du Mus e*, No. 31293. Bought.

- 36090. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate II.—Kurneh (1858).

DESCRIPTION: Inscribed with the prenomen of Thothmes I within a cartouche. On either side of it are two standing figures with arms upraised, and above is a winged disc. *Back*, without prothorax or elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green (discoloured by grease).

TECHNIQUE: medium work.

PRESERVATION: back worn.

BIBL.: *Journal d'entr e du Mus e*, No. 3348.

- 36091. Scarab-shaped Seal.**—Glass, light opaque blue.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes I. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: exquisitely carved and engraved.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 30790.

- 36092. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes I within a cartouche. Titles in the field. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine quality but thin.

TECHNIQUE: finely cut.

PRESERVATION: perfect.

- 36093. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate II.—Sheikh es Selam (1899).

DESCRIPTION: Inscribed with the prenomen of Thothmes I. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: excellent cutting.

PRESERVATION: slightly chipped on back.

BIBL: *Journal d'entrée du Musée*, No. 34012.

- 36094. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes II. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: medium cutting.

PRESERVATION: fair.

BIBL: *Journal d'entrée du Musée*, No. 29954. Bought in Upper Egypt.

- 36095. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Hatshepsut within a cartouche: short inscription below. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case (see Plate XXII).

DATE: Early Eighteenth Dynasty.

GLAZE: green, thin and turning brown.

TECHNIQUE: fair cutting.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 31293. Bought.

- 36096. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '011.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Hatshepsut within a cartouche: on either side a hanging uraeus, and below, a necklace with hawk-headed ends. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, of poor quality.

TECHNIQUE: medium work.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 30789.

- 36097. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Hatshepsut within a cartouche. To the left, a figure of the queen seated and wearing the double crown of Egypt: above is the winged disc, and below, a *nub*-sign. *Back*, see Plate XXII. The scarab is set in a plain bronze signet-ring.

DATE: Early Eighteenth Dynasty.

GLAZE: light greeny-blue.

TECHNIQUE: very fine back, but cutting of seal medium.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 30737.

- 36098. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '008. Height, 0 m '005.—Plate II.

DESCRIPTION: A double scarab with single piercing: prenomen of Thothmes III repeated twice below. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case (see Plate II).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: roughly cut,

PRESERVATION: fair.

*Catal. du Musée*, n. 36001.

- 36099. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III, with disc above, from which two uræi are suspended: beneath, a *ded*-sign and two *ankhs*. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: grey-green.

TECHNIQUE: good.

PRESERVATION: head broken off and back flaked.

- 36100. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '004.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: very fine green.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: excellent.

BIBL.: MASPERO, *Slip Cat.*, No. 3733.

- 36101. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche. On either side are uræi, while above are the titles of the king and below, a *nub*-sign. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: good cutting.

PRESERVATION: chipped on edge.

- 36102. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. Above is a hornet and below a *neb*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: coarsely cut and modelled.

PRESERVATION: fair.

- 36103. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; a legend below. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality, but turning yellowish.

TECHNIQUE: good cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25730. Bought. PETRIE, *Hist. Scarabs*, No. 1067. NEWBERRY, *Scarabs*, Plate XXVIII, 25.

- 36104. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; to the left the legend *men mennu*. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: finely cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31356.

- 36105. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '005.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax slightly indicated, but no elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: delicately cut and modelled.

PRESERVATION: perfect.

- 36106. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: coarse cutting.

PRESERVATION: fair.



- 36107. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: delicately cut and modelled.

PRESERVATION: head of beetle chipped, and chipped on edge.

- 36108. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: on either side, feathers with uræi springing from them and below, a *ded*-sign with uræi on either side. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: well cut.

PRESERVATION: chipped on edge.

BIBL.: MASPERO, *Slip Cat.*, No. 3719.

- 36109. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '03. Width, 0 m '021. Height, 0 m '014.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; to the right of the name a uræus; above, a papyrus ornament and below, a *neb*-sign. *Back*, see Plate II.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone a brownish white.

TECHNIQUE: cutting, deep and good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3704. PETRIE, *Hist. Scarabs*, No. 974.

- 36110. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '032. Width, 0 m '023. Height, 0 m '012.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; on either side of it are obelisks, and below is a large *sam*-sign with uræi on either side. On the back is a Hathor head with uræi on either side of it (see Plate II).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: coarse.

PRESERVATION: chipped on edge.

- 36111. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '029. Width, 0 m '022. Height, 0 m '011.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. To the left is a Set-headed figure with a crocodile below. *Back*, see Plate II.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36112. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '028. Width, 0 m '02. Height, 0 m '012.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. To the left a seated figure. Above, a design of uncertain meaning. Around the whole a rope pattern. *Back*, see Plate II.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown and yellow in thinner parts.

TECHNIQUE: medium.

PRESERVATION: Chipped on one edge.

BIBL.: MASPERO, *Slip Cat.*, No. 3705. PETRIE, *Hist. Scarabs*, No. 983.

- 36113. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '031. Width, 0 m '021. Height, 0 m '013.—Plate II.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. Around the whole is a rope pattern with a series of disconnected coils on the inside. *Back*, see Plate II.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green, going brown.

TECHNIQUE: coarse cutting, back very well modelled.

PRESERVATION: perfect.

- 36114. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue-green, turning brown.

TECHNIQUE: coarse.

PRESERVATION: back flaked at top.

BIBL.: MASPERO, *Slip Cat.*, No. 3721.

- 36115. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '016. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. To the left is a cynocephalus seated, and below, a *nub*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

- 36116. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '009. Height, 0 m '01.—Plate III.—Abydos (1881).

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: in the field on either side are hawks with wings outspread. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, going white in places.

TECHNIQUE: modelling of back good, cutting fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25088. MASPERO, *Slip Cat.*, No. 3720.

- 36117. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen and nomen of Thothmes III within a cartouche, with titles above and a *nub*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark greeny-blue of fine quality.

TECHNIQUE: delicate detail cutting and legs deeply sunk.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36118. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '013. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: on either side two feathers, with, below, a man kneeling with arms upraised and holding in each hand a palm-branch. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: exquisite light green of very fine quality.

TECHNIQUE: very delicately cut and modelling exquisite.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882. MASPERO, *Slip Cat.*, No. 3097. PETRIE, *Hist. Scarabs*, No. 1012. NEWBERRY, *Scarabs*, Plate, XXVIII, 24.

- 36119. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval before a recumbent sphinx. Below is a man standing holding up a *pet*-sign, and in the field are hieroglyphic signs.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown in parts.

TECHNIQUE: coarsely cut and modelled.

PRESERVATION: back partly flaked away.

- 36120. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '016. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: incised lines at the sides. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: coarsely cut and modelled.

PRESERVATION: edges chipped and back worn.

- 36121. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche. Below, hieroglyphic signs and urai. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brownish-white and crackled.

TECHNIQUE: back finely modelled; inscription coarsely cut.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36122. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche. To the left are hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, of poor quality.

TECHNIQUE: legs deeply sunk: cutting of back and inscription coarse.

PRESERVATION: broken on one side.

- 36123. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·014. Height, 0 m ·01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval; below a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white in parts.

TECHNIQUE: cutting good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 1698.

- 36124. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·00(?)—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: to the right a crocodile. *Back*, flaked away.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: back flaked away.

- 36125. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·017. Height, 0 m ·011.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: to the left a crocodile. *Back*, see Pl. III.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: edges worn.

- 36126. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate III.—Abydos (Amelineau).

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: below is a beetle with wings outspread. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going white in places.

TECHNIQUE: cutting and modelling of back good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31356.

- 36127. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left are hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue, of poorish quality.

TECHNIQUE: cutting coarse.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 3724.

- 36128. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: urai on either side and below. *Back*, plain as No. 36676, Plate XIX.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green, going white.

TECHNIQUE: coarse.

PRESERVATION: chipped at edges.

- 36129. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: to the left a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going white in places.

TECHNIQUE: cutting, good.

PRESERVATION: perfect.

BIBL.: *Journal d'entré du Musée*, No. 5037 (Coll. Huber). MASPERO, *Slip Cat.*, No. 3097.

- 36130. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate III.

DESCRIPTION: Similar to No. 36129.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brownish-yellow.

TECHNIQUE: good cutting.

PRESERVATION: good.

*Catal. du Musée*, n. 36001.

5

**36131. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·016. Height, 0 m ·009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: on either side are hawks with outspread wings. *Back*, prothorax indicated as No. 36707.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fair quality, going white in places.

TECHNIQUE: coarse.

PRESERVATION: chipped around edges.

**36132. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·032. Width, 0 m ·025. Height, 0 m ·014.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: above are the titles of the king, and to the right a hieroglyphic legend. Surrounding the whole is a rope pattern. On the back is (1) a Hathor with uræi on either side, and (2) a lotus flower with outspread petals (see Plate III).

DATE: Middle Eighteenth Dynasty.

GLAZE: brownish-white.

TECHNIQUE: boldly cut, but rather coarse.

PRESERVATION: chipped around edges.

BIBL.: *Journal d'entrée du Musée*, No. 27500. Bought.

**36133. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·026. Width, 0 m ·02. Height, 0 m ·012.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: on either side are uræi. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning grey, of very poor quality and nearly worn off.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: chipped around edges and worn on back.

**36134. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate III.

DESCRIPTION: In the centre a Hathor-head with uræi below: on either side the prenomen of Thothmes III within ovals. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of very fine quality, but turned brown in places.

TECHNIQUE: very fine modelling and cutting.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3716.

- 36135. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate III.—Abydos.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: below, an *ankh*-sign. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green? (turned whity-yellow).

TECHNIQUE: fair cutting, back coarsish.

PRESERVATION: fair.

BIBL.: *Journal d'entr e du Mus e*, No. 21938. MASPERO, *Slip Cat.*, No. 3725.

- 36136. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen, nomen and titles of Thothmes III. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: edge slightly chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 3715.

- 36137. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate III.

DESCRIPTION: Similar to No. 36129.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone brown in thinner places.

TECHNIQUE: cutting and modelling good.

PRESERVATION: chipped on edge.

- 36138. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the title and prenomen of Thothmes III with a figure of the king standing in the centre. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: rich blue, of fine quality.

TECHNIQUE: very good modelling and cutting.

PRESERVATION: edges slightly chipped and head of beetle broken off.

5.



**36139. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III in a cartouche: below, a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned whitish yellow.

TECHNIQUE: modelling of back and cutting good.

PRESERVATION: chipped on edge.

BIBL: *Journal d'entrée du Musée*, No. 3708. PETRIE, *Hist. Scarabs*, No. 1058.

**36140. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: back finely modelled, cutting good.

PRESERVATION: chipped at one end.

BIBL: *Journal d'entrée du Musée*, No. 2525. Provenance unknown. MASPERO, *Slip Cat.*, No. 1698.

**36141. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate III.

DESCRIPTION: Similar to No. 36140.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: back finely modelled, cutting good.

PRESERVATION: chipped edge.

BIBL: MASPERO, *Slip Cat.*, No. 3730.

**36142. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: around it are four urai. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brownish-white.

TECHNIQUE: back well modelled, cutting fine.

PRESERVATION: perfect, except head of beetle broken off.

BIBL: MASPERO, *Slip Cat.*, No. 3718.

- 36143. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: above, is the sun's disc with suspended uraei, and below, a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown on back.

TECHNIQUE: moulding fair.

PRESERVATION: partially damaged by salt.

- 36144. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: a brilliant sky blue, gone brownish-white in places.

TECHNIQUE: well moulded back and fair cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Ship Cat.*, No. 3726.

- 36145. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III with hieroglyphic legend below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: medium cutting and modelling.

PRESERVATION: chipped on edges.

- 36146. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III; to the left is a recumbent sphinx. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale green.

TECHNIQUE: coarse cutting.

PRESERVATION: perfect.

**36147. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left is a recumbent sphinx, and above it a hawk with outspread wings. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown and yellow.

TECHNIQUE: coarse cutting.

PRESERVATION: back flaked, otherwise good.

**36148. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: to the left is a figure of the goddess Maat; above, a winged disc, and below, a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: fair cutting and back.

PRESERVATION: edges chipped.

**36149. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left is a uræus, and below it a *neb*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone yellowish-white.

TECHNIQUE: cutting coarse but bold.

PRESERVATION: perfect.

**36150. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate III.—Abydos.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax indicated as No. 37107.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue, of good quality.

TECHNIQUE: back well moulded, cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 22070. MASPERO, *Stip. Cat.*, No. 3728.

- 36151. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: to the left is a figure of the king standing, and below is a *nub*-sign. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: back delicately carved, cutting good.

PRESERVATION: good, but head of beetle chipped.

BIBL.: *Journal d'entrée du Musée*, No. 25734.

- 36152. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval.

Above is a winged disc; below is a *nub*-sign, and hieroglyphs are cut on either side of the oval. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, crackled and gone white in thin parts but of very good quality.

TECHNIQUE: cutting good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 33439.

- 36153. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: above it are titles of the king. To the left is a seated figure of the king, and below is a *nub*-sign. *Back*, prothorax and elytra, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: Nacreous brown.

TECHNIQUE: back coarsely modelled, hieroglyphs good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. Carey in 1882. MASPERO, *Slip Cat.*, No. 3097.

- 36154. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: above it are his titles, and below is a *sam*-sign with feathers and urai on either side. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: back well modelled and cutting excellent.

PRESERVATION: perfect.

- 36155. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: back well modelled but cutting scratchy.

PRESERVATION: good.

- 36156. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III, within vertical lines: on either side are hieroglyphic signs, while in a division above are the double eyes. *Back*, see Fig. in Plate III.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown and crackled.

TECHNIQUE: modelling of back good: cutting coarse.

PRESERVATION: good.

- 36157. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. To the left is a winged sphinx with hieroglyphic signs above. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned yellow-brown.

TECHNIQUE: coarse.

PRESERVATION: flaked on back and chipped round edges.

- 36158. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate III.—Mitrahény (1900).

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: a hieroglyphic legend to the left. *Back*, prothorax and elytra marked, with a  $\nabla$  on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: coarse cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 34064.

- 36159. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche. Below it is a *nub*-sign, while on either side are uræi upon *nub*-signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: back fair; cutting coarse.

PRESERVATION: good.

- 36160. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. On either side of it are hawks with wings outspread. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone whitish-yellow.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: good.

- 36161. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. On either side is a hieroglyphic legend. *Back*, prothorax indicated as No. 36603.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: back fair but cutting coarse.

PRESERVATION: good.

- 36162. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: roughly cut and modelled.

PRESERVATION: good: chipped on one side and glazed over.

*Catal. du Musée, n. 36001.*

6

- 36163. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate III.—Abydos.

DESCRIPTION: Inscribed with the prenomen of Thothmes III with a hieroglyphic legend to the left. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 21933.

- 36164. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III between vertical lines: on either side are uræi. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: good.

- 36165. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. To the left is a standing figure of a hawk-headed Deity, and below, a *neb*-sign. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: poor modelling and cutting.

PRESERVATION: back flaked, otherwise good.

- 36166. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III between vertical lines. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, of good quality.

TECHNIQUE: coarse work.

PRESERVATION: good.

- 36167. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: on either side, his titles. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: good cutting and modelling.

PRESERVATION: chipped on lower edge.

BIBL.: *Journal d'entré du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36168. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III, with a winged disc on the right. *Back*, prothorax indicated as No. 37179.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale blue-green.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36169. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, turning green.

TECHNIQUE: badly moulded and cutting very coarse.

PRESERVATION: good.

- 36170. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·008.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality, going brown in places.

TECHNIQUE: cutting of back exquisite and of hieroglyphs good.

PRESERVATION: Perfect.

6.



- 36171. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: back roughly modelled and cutting coarse.

PRESERVATION: chipped on edge.

- 36172. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '009.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling of back coarse; hieroglyphs, fair.

PRESERVATION: good.

- 36173. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '008.—Plate III.—Sakkara.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within horizontal lines: the name of the god Ptah above, and a *del*-sign and two-hawks below. *Back*, see Plate III.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: modelling of back and cutting of hieroglyphs, medium.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 21873.

- 36174. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, see Plate III.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, turning nacreous.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36175. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: modelling of back fair, hieroglyphs good.

PRESERVATION: good.

- 36176. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: roughly modelled and glazing run.

PRESERVATION: good.

- 36177. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '006. Height, 0 m '005.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: roughly modelled and cut.

PRESERVATION: head broken off.

- 36178. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '01.—Plate III.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of uneven quality and slightly cracked.

TECHNIQUE: medium. *Back*, coarsish.

PRESERVATION: good.

- 36179. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Thothmes III within vertical lines with hieroglyphs on either side. *Back*, rounded prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

GLAZE : green, turning whity-grey.

TECHNIQUE : cutting coarse.

PRESERVATION : good.

- 36180. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate III.

DESCRIPTION : Inscribed with the prenomen of Thothmes III. *Back*, see Plate XXII.

DATE : Middle Eighteenth Dynasty.

GLAZE : blue.

TECHNIQUE : very coarse modelling and cutting.

PRESERVATION : broken on lower edge.

- 36181. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Thothmes III within an oval above is a beetle with uræi on either side, and below is a *nub*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Middle Eighteenth Dynasty.

GLAZE : green, gone brown.

TECHNIQUE : medium work.

PRESERVATION : chipped on edge.

- 36182. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Middle Eighteenth Dynasty.

GLAZE : light blue, turning white.

TECHNIQUE : back delicately carved, cutting of hieroglyphs good.

PRESERVATION : perfect.

- 36183. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate IV.—Abydos.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval. Above is an *ankh*-sign, and to the left a crocodile. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, turning brown in places and slightly cracked.

TECHNIQUE: coarsish work.

PRESERVATION: chipped at head and on back.

BIBL.: *Journal d'entrée du Musée*, No. 21921.

- 36184. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III, a uræus and a hieroglyphic legend. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, turning white in thin places.

TECHNIQUE: moulding of back good, but cutting poor.

PRESERVATION: good.

- 36185. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '01.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III between vertical lines: on either side, feathers. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, unequally distributed and worn off in places.

TECHNIQUE: rather coarse.

PRESERVATION: medium.

- 36186. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche: above is a lion recumbent, while to the left is a *hes*-vase. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: olive-green, of good quality.

TECHNIQUE: excellent cutting and modelling.

PRESERVATION: slightly chipped at edges.

- 36187. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: brilliant blue, of medium colour.

TECHNIQUE: coarse.

PRESERVATION: good.

- 36188. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '004.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine blue-green, of excellent quality.

TECHNIQUE: well modelled but cutting coarse.

PRESERVATION: top of head chipped, otherwise perfect.

- 36189. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: decorative designs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: olive-green, of fine quality.

TECHNIQUE: cutting coarse.

PRESERVATION: chipped on edge.

- 36190. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '026. Width, 0 m '017. Height, 0 m '013.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: on either side are feathers. Above, a winged disc, and below, a *neb*-sign. For the back see Plate IV.

DATE: Twenty-fourth Dynasty.

GLAZE: green (?), turned white and in places rubbed off.

TECHNIQUE: modelling and cutting fair.

PRESERVATION: edges rubbed away and generally worn.

- 36191. Scarab-shaped Seal.**—Matrix turquoise (?).—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: cutting rough, and piercing does not run through.

PRESERVATION: perfect.

- 36192. Scarab-shaped Seal.**—Matrix turquoise (?).—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: cutting rough, and piercing does not run through.

PRESERVATION: perfect.

- 36193. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·007.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval: a hieroglyphic legend below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going white and brown and turning nacreous.

TECHNIQUE: fair.

PRESERVATION: good.

- 36194. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within an oval; on either side is a winged disc. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine colour on back.

TECHNIQUE: coarse cutting, but modelling of back good.

PRESERVATION: perfect.

*Catal. du Musée, n. 36901.*

7

- 36195. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: cutting and back coarse.

PRESERVATION: good.

- 36196. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: very roughly cut.

PRESERVATION: good.

- 36197. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left is an uræus. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine deep sky-blue, unequally distributed.

TECHNIQUE: coarse.

PRESERVATION: chipped at edges.

- 36198. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: to the left is a hawk-headed figure holding a lotus flower. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: medium cutting.

PRESERVATION: good.

- 36199. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes III: *Back*, see Plate XXI.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned brown and white.

TECHNIQUE: very rough.

PRESERVATION: fair.

- 36200. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·006.—Plate IV.

DESCRIPTION: The king, Thothmes III, in a chariot drawn by a pair of horses, hunts a lion in the desert. On the back is the prenomen of Thothmes III surmounted by two feathers.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue or green, turned grey.

TECHNIQUE: good cutting and modelling.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cut.*, No. 3722.

- 36201. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep II with legend below. To the left is a figure of the king standing. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: excellent modelling and cutting.

PRESERVATION: very good.

BIBL.: *Journal d'entré du Musée*, No. 31293. Bought.

- 36202. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate IV.

DESCRIPTION: Inscribed with the titles and prenomen of Amenhetep II within a cartouche. To the left is a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: medium cutting.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 25733. Bought.



**36203. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep II within a cartouche: below are lotus and papyrus flowers, and at the sides an ornamental device. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: very good cutting and modelling.

PRESERVATION: good.

**36204. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep II within a cartouche: on either side are hawks with wings outspread, and below is a *nub*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: modelling of back good, cutting fair.

PRESERVATION: excellent.

**36205. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Thothmes IV. On either side, an *usa*-eye with two *nefer*-signs below. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning white in places.

TECHNIQUE: very fine cutting.

PRESERVATION: good.

**36206. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate IV.—Sakkara.

DESCRIPTION: Inscribed with the prenomen of Thothmes IV. To the left is a hawk-headed sphinx. *Back*, prothorax indicated as No. 36555.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: fine cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 35218. MASPERO, *Slip Cat.*, No. 3735. PETRIE, *Hist. Scarabs*, No. 1150.

- 36207. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate IV.—Sakkara.

DESCRIPTION: Inscribed with the prenomen of Thothmes IV within a cartouche: above it are feathers, urai and horns. On each side are urai, and below, a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: very good modelling and cutting.

PRESERVATION: excellent.

BIBL: *Journal d'entr e du Mus e*, No. 30699.

- 36208. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: cutting poor, modelling medium.

PRESERVATION: good.

- 36209. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: bold and fine cutting.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3747.

- 36210. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: to the right is a feather and above and below are *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: dull blue-green, of poor quality.

TECHNIQUE: back coarse, cutting fair.

PRESERVATION: good.

BIBL: MASPERO, *Slip Cat.*, No. 3749.

**36211. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, roughly modelled as No. 36210.

DATE: Late Eighteenth Dynasty.

GLAZE: a deep sky-blue, of fine quality.

TECHNIQUE: back roughly modelled, cutting good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3740.

**36212. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the titles, prenomen and nomen of Amenhetep III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue-green, turned a whity-brown.

TECHNIQUE: very well cut and modelled.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3741. PETRIE, *Hist. Scarabs*, No. 1274.

**36213. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '01.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche. Below is a beetle with wings outspread. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: back roughly modelled but cutting good.

PRESERVATION: good.

**36214. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, roughish, like No. 36210.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, turning brown on back.

TECHNIQUE: back roughish but cutting fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3739.

- 36215. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a *V* on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: back roughly modelled and cutting coarse.

PRESERVATION: good.

- 36216. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: to the left is an *ura*-eye with three *nefers* below. *Back*, prothorax and elytra marked, with a *V* on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned whity-yellow in places.

TECHNIQUE: modelling and cutting good.

PRESERVATION: good.

- 36217. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a *V* on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned brown, of fine quality.

TECHNIQUE: modelling and cutting very fine.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181; given by M. CAREY, 1882.

- 36218. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: to the left is a hieroglyphic legend. The seal is set in a gold funda. *Back*, prothorax and elytra marked, with a *V* on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, and unequally distributed.

TECHNIQUE: coarse.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 31292.

**36219. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate IV.—Sakkara (1858).

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: to the left is a hieroglyphic legend. Set in a gold fundu. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned brown on back.

TECHNIQUE: cutting good and back well modelled.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 2536. MASPERO, *Slip Cat.*, No. 3745. PETRIE, *Hist. Scarabs*, No. 1251.

**36220. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned yellowy-brown and slightly nacreous.

TECHNIQUE: cutting and back good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3738.

**36221. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned white in places.

TECHNIQUE: poor.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29953. Bought in Upper Egypt.

**36222. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, rough, as No. 36210.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned brown on back and crackled.

TECHNIQUE: back roughly modelled, cutting good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3737.

- 36223. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, see Plate XX.

DATE: Late Eighteenth Dynasty.

GLAZE: violet, of fine quality but turning white.

TECHNIQUE: good.

PRESERVATION: fair.

BIBL.: MASPERO, *Stip. Cat.*, No. 3736.

- 36224. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: fine light blue, unequally distributed and turning white in places.

TECHNIQUE: good modelling and cutting.

PRESERVATION: good.

- 36225. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '036. Width, 0 m '026. Height, 0 m '016.—Plate IV.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III. *Back*, as No. 36226.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, badly burnt.

TECHNIQUE: bold and good cutting.

PRESERVATION: slightly chipped.

BIBL.: *Journal d'entré du Musée*, No. 28559.

- 36226. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '04. Width, 0 m '029. Height, 0 m '019.—Plate V.—Heliopolis.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: beneath is a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Late Eighteenth Dynasty.

GLAZE: fine blue, going green in places.

TECHNIQUE: well cut and modelled.

PRESERVATION: fair.

BIBL.: *Journal d'entré du Musée*, No. 35233.

*Catal. des Musées*, n. 36001.

- 36227. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '053. Width, 0 m '039. Height, 0 m '025.—Plate IV.—Ouardan.

DESCRIPTION : Inscribed with the prenomen of Amenhetep III within a cartouche : beneath is a hieroglyphic legend. *Back*, as No. 36226.

DATE : Late Eighteenth Dynasty.

GLAZE : dull green, uneven and badly burnt.

TECHNIQUE : well cut and modelled.

PRESERVATION : chipped on edges.

BIBL. : *Journal d'entrée du Musée*, No. 28615.

- 36228. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '045. Width, 0 m '033. Height, 0 m '018.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Amenhetep III within a cartouche : beneath is a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

GLAZE : green, turning whity-yellow.

TECHNIQUE : coarsely cut and modelled.

PRESERVATION : fair.

BIBL. : *Journal d'entrée du Musée*, No. 25849. Bought. PETRIE, *Hist. Scarabs*, No. 1262.

- 36229. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '051. Width, 0 m '038. Height, 0 m '022.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Amenhetep III within a cartouche : beneath is a hieroglyphic legend. *Back*, as No. 36228.

DATE : Late Eighteenth Dynasty.

GLAZE : green, turned brown.

TECHNIQUE : well cut and modelled.

PRESERVATION : good.

BIBL. : *Journal d'entrée du Musée*, No. 25398. Bought. MASPERO, *Slip Cat.*, No. 3743. PETRIE, *Hist. Scarabs*, No. 1261.

- 36230. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '052. Width, 0 m '037. Height, 0 m '022.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Amenhetep III within a cartouche : beneath, a hieroglyphic legend. *Back*, as No. 36228.

DATE : Late Eighteenth Dynasty.

GLAZE : a brilliant sky blue, of fine quality.

TECHNIQUE : well cut and modelled.

PRESERVATION : chipped on edge.

BIBL. : *Journal d'entrée du Musée*, No. 30829. Given by PRINCE HENRY DE BOURBON.

- 36231. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '045. Width, 0 m '032. Height, 0 m '023.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: beneath is a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turning grey.

TECHNIQUE: well cut and modelled.

PRESERVATION: worn on back.

BIBL.: *Journal d'entrée du Musée*, No. 29934. Bought.

- 36232. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '043. Width, 0 m '032. Height, 0 m '02.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Amenhetep III within a cartouche: on either side, titles and hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, turning green and unevenly distributed.

TECHNIQUE: good cutting and modelling.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cut*, No. 3748. PETRIE, *Hist. Scarabs*, No. 1267.

- 36233. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '047. Width, 0 m '034. Height, 0 m '021.—Plate V.—Île de Saï, Ethiopia.

DESCRIPTION: Inscribed with the name and titles of Queen Thÿi. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, turning brown and uneven.

TECHNIQUE: well cut and modelled.

PRESERVATION: large piece flaked off back.

BIBL.: *Journal d'entrée du Musée*, No. 25401. (Given by M. INSINGER, 1883).

MASPERO, *Slip Cut*, No. 3753. PETRIE, *Hist. Scarabs*, No. 1300.

- 36234. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate IV.

DESCRIPTION: Inscribed with name and title of Queen Thÿi. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: good cutting and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25682 (bought). PETRIE, *Hist. Scarabs*, No. 1289.



- 36235. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Akhenaten : a hieroglyphic legend below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

GLAZE : light blue-green, turning white and crackled.

TECHNIQUE : medium cutting.

PRESERVATION : fair.

BIBL : *Journal d'entrée du Musée*, No. 25728. Bought.

- 36236. Scarab-shaped Seal.**—Beryl.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Akhenaten. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

TECHNIQUE : modelling of back lumpy, cutting fair.

PRESERVATION : slightly chipped at edges.

- 36237. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Akhenaten within a cartouche : to the left is a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

GLAZE : dark blue, of good quality.

TECHNIQUE : good modelling and cutting.

PRESERVATION : good.

BIBL : *Journal d'entrée du Musée*, No. 31293. Bought.

- 36238. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate IV.

DESCRIPTION : Inscribed with the prenomen of Hor-em-heb within a cartouche : to the left and right are titles and legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

GLAZE : bright blue, of good quality.

TECHNIQUE : medium.

PRESERVATION : fair.

BIBL : MASPERO, *Slip Cut.*, No. 3752. PETRIE, *Hist. Scarabs*, No. 1579.

- 36239. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses I. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull green, of good quality.

TECHNIQUE: cutting and modelling good.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 31293. Bought.

- 36240. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate V.—Mitraheny (1863).

DESCRIPTION: Inscribed with the prenomen of Sety I. *Back*, rounded prothorax and elytra marked

DATE: Nineteenth Dynasty.

GLAZE: green, turning nacreous white.

TECHNIQUE: moulding of back lumpy, cutting poor.

PRESERVATION: fair.

BIBL: *Journal d'entrée du Musée*, No. 20469. MASPERO, *Slip Cat.*, No. 3755.

- 36241. Scarab-shaped Seal.**—Paste.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate V.

DESCRIPTION: Inscribed with a prenomen of a king, reading *Nub-ka-ra*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: a dull dark blue green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: good.

- 36242. Scarab-shaped Seal.**—Glass.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '08.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Tum standing on a  $\nabla$ -sign and holding spear; on either side are titles. *Back*, prothorax and elytra marked with a V on either wing-case (see Plate XXII).

DATE: Late Eighteenth Dynasty.

GLASS: pale blue and opaque.

TECHNIQUE: cutting and modelling good.

PRESERVATION: broken into three pieces.

**36243. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate XVIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

Back, see Plate XVIII. Set in a plain hoop ring, the maximum diameter of the hoop being 0 m '0026.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: the hoop is much corroded, otherwise perfect.

**36244. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '009.—Plate XVII.

DESCRIPTION: A hieroglyphic legend (?) surrounded by a loop pattern. Back, plain (see Plate XIX).

DATE: Hyksos Period.

GLAZE: blue green, going brown.

TECHNIQUE: fair cutting.

PRESERVATION: worn on back.

**36245. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate XVI.

DESCRIPTION: The title *netet hent wt*, with a *mer*-sign below. Set in a gold fundu.

Back, prothorax and elytra marked, with a V on either wing-case.

DATE: Early Eighteenth Dynasty.

GLAZE: blue (?), gone white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good, but head of beetle chipped.

**36246. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '009.—Plate XVII.

DESCRIPTION: Above is a *sam*-sign connecting bushes of papyrus, and below it a

*kheper* with *nefer*-signs on either side. Mounted in a gold fundu. Back, prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: palish blue, of fine quality.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: fair.

- 36247. Scarab-shaped Seal.**—Steatite, glazed(?).—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XVII.

DESCRIPTION: *Ded*-signs and lotus flowers ornamentally arranged. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: turned brown, or not glazed?

TECHNIQUE: coarse work.

PRESERVATION: worn.

- 36248. Scarab-shaped Seal.**—Paste.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the signs *neb-uferru-Ra*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: pale pea-green.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: good.

- 36249. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brownish.

TECHNIQUE: fair.

PRESERVATION: good.

- 36250. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Sety I. *Back*, prothorax indicated (see Plate XIX).

DATE: Nineteenth Dynasty.

GLAZE: blue-green, turning brown and crackled.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25732. Bought.

**36251. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Sety I. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue, turning green.

TECHNIQUE: badly moulded and glazed.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 25734. Bought.

**36252. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Sety I. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: moulding of back fair, cutting good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3757.

**36253. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Sety I. To the right is a winged disc, to the left a hieroglyphic legend. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: medium.

PRESERVATION: edges badly chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 3756.

**36254. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the name of Sety. *Back*, as No. 36239.

DATE: Nineteenth Dynasty.

GLAZE: green, turned a whity-brown.

TECHNIQUE: coarse cutting.

PRESERVATION: back flaked.

- 36255. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II within a rope-pattern border. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: poor.

PRESERVATION: back flaked.

- 36256. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·013. Height, 0 m ·009.—Plate V.—Abydos (1881).

DESCRIPTION: Inscribed with the prenomen of Rameses II within a cartouche: on either side are the king's titles and a hieroglyphic legend. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: modelling and cutting fair.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 25087. MASPERO, *Slip Cat.*, No. 3767.

- 36257. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·017. Height, 0 m ·01.—Plate V.—Abydos (Amelineau).

DESCRIPTION: Inscribed with the prenomen of Rameses II within a cartouche: with hawks with outspread wings on either side. Above, the king smites an enemy before the gods Ptah and Sekhmet: behind him stands the goddess Maat, and above his head is a winged disc. *Back*, prothorax and elytra marked, see Plate XXI.

DATE: Nineteenth Dynasty.

GLAZE: dark blue-green of excellent quality.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 31356.

- 36258. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·014. Height, 0 m ·009.—Plate V.

DESCRIPTION: The king smites a prisoner: behind him is a fan, and above is the prenomen of Rameses II with a hieroglyphic legend. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: dark blue-green, crackled.

TECHNIQUE: very good modelling and cutting.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3765. PETRIE, *Hist. Scarabs*, No. 1529. *Catal. du Musée*, n. 36001.

**36259. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '011.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green.

TECHNIQUE: fair; legs pierced through whole width.

BIBL.: MASPERO, *Slip Cat.*, No. 3763.

**36260. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '025. Width, 0 m '018. Height, 0 m '012.—Plate V.

DESCRIPTION: The king before Ra smites an enemy: above is a winged disc, and behind him the prenomen of Rameses II. Below is a *mer-* and a *neb-*sign. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: dark blue-black glaze, of fine quality.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33440.

**36261. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '009.—Plate V.—Nebechah (Petrie).

DESCRIPTION: Rameses II in a chariot drawn by one horse: in front of it the prenomen of the king. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: very finely carved

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 27404.

**36262. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, see Plate XX.

DATE: Nineteenth Dynasty.

GLAZE: grey-green.

TECHNIQUE: poor cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25685. Bought.

- 36263. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·017. Width, 0 m ·014. Height, 0 m ·009.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, as No. 36262.

DATE: Nineteenth Dynasty.

GLAZE: blue, turning nacreous.

TECHNIQUE: poor modelling and cutting.

PRESERVATION: good.

- 36264. Scarab-shaped Seal.**—Bronze.—Length, 0 m ·022. Width, 0 m ·017. Height, 0 m ·011.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II within a cartouche surmounted by a *Ra*-sign and uræi. On either side are crowned uræi, and below is a *neb*-sign. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: very well modelled.

PRESERVATION: much worn.

BIBL: *Journal d'entr e du Mus e*, No. 30783.

- 36265. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·015. Height, 0 m ·006.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II within a cartouche: above it are the king's titles, and on either side are feathers. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turning white and crackled.

TECHNIQUE: fair.

PRESERVATION: much chipped on edges.

BIBL: MASPERO, *Stip Cat.*, No. 3769.

- 36266. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: good.

PRESERVATION: back finely modelled but cutting poor.



- 36267. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·00 (?).—Plate V.

DESCRIPTION : Inscribed with the prenomen of Rameses II between two horizontal lines : above is the name of Ptah, and below are hieroglyphic signs. *Back*, worn away.

DATE : Nineteenth Dynasty.

TECHNIQUE : very roughly cut.

PRESERVATION : much worn.

- 36268. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate V.—Kurneh (1862).

DESCRIPTION : Inscribed with the prenomen of Rameses II within an oval : around it is a series of concentric circles. *Back*, worn away.

DATE : Nineteenth Dynasty.

GLAZE : light blue-green.

TECHNIQUE : fine cutting.

PRESERVATION : back much worn.

BIBL : *Journal d'entrée du Musée*, No. 20425. MASPERO, *Slip Cat.*, No. 3761. PETRIE, *Hist. Scarabs*, No. 1487.

- 36269. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Rameses II and hieroglyphic legend. *Back*, see Plate XX.

DATE : Nineteenth Dynasty.

GLAZE : blue-green, turning brown and crackled.

TECHNIQUE : finely cut and modelled.

PRESERVATION : chipped on edges.

- 36270. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·023. Width, 0 m ·017. Height, 0 m ·01.—Plate V.

DESCRIPTION : On the *back* the prenomen of Rameses II within a cartouche, and to the left of it a cynocephalus ape. Below, on the seal, a hieroglyphic legend and the gods Amen and Ra seated with a winged disc above them.

DATE : Nineteenth Dynasty.

GLAZE : a dark rich blue-green of fine quality.

TECHNIQUE : very finely cut and modelled.

PRESERVATION : perfect.

BIBL : MASPERO, *Slip Cat.*, No. 3771.

- 36271. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: modelling of back lumpy, cutting fair.

PRESERVATION: good.

- 36272. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. Remains of a bronze fundu around it. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, of dull colour.

TECHNIQUE: medium cutting and modelling.

PRESERVATION: good.

- 36273. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate V.—Zagazig (1882).

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: yellow.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198. MASPERO, *Slip Cat.*, No. 1699.

- 36274. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '006.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turned grey-brown and crackled.

TECHNIQUE: back finely modelled but cutting poor.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 5056. MASPERO, *Slip Cat.*, No. 3760.

**36275. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '017. Height, 0 m '011.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Rameses II : to the left is an uræus with disc on head. Remains of a bronze pin in piercing. *Back*, rounded prothorax and elytra marked (see Plate XX).

DATE : Nineteenth Dynasty.

GLAZE : green, turned white and crackled.

TECHNIQUE : good and bold cutting.

PRESERVATION : good.

BIBL. : *Journal d'entrée du Musée*, No. 29956. Bought.

**36276. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate V.—Kurneh (1858).

DESCRIPTION : Inscribed with the prenomen of Rameses II. *Back*, without prothorax or elytra marked.

DATE : Nineteenth Dynasty.

GLAZE : green, turned brown on back.

TECHNIQUE : fair cutting and modelling.

PRESERVATION : good.

BIBL. : *Journal d'entrée du Musée*, No. 2541. MASPERO, *Slip Cat.*, No. 3775.

**36277. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Rameses II. *Back*, prothorax and elytra marked.

DATE : Nineteenth Dynasty.

GLAZE : green (?), turned white.

TECHNIQUE : fair.

PRESERVATION : good.

BIBL. : *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

**36278. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '006.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Rameses II. *Back*, see Plate XX.

DATE : Nineteenth Dynasty.

GLAZE : green.

TECHNIQUE : cutting coarse.

PRESERVATION : good.

- 36279. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '011. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses II. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green.

TECHNIQUE: very coarse cutting and back roughly modelled.

PRESERVATION: fair.

- 36280. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '011.—Plate V.—Nebesheh (Petrie).

DESCRIPTION: A king (Rameses II?) between Amen and Ra: below is a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: back very finely modelled and cutting excellent.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 27405.

- 36281. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '015. Height, 0 m '011.—Plate V.

DESCRIPTION: Inscribed with the name of Rameses and a hieroglyphic legend. *Back*, see Plate V.

DATE: Nineteenth Dynasty.

GLAZE: blue, turning white and nacreous, of bad quality.

TECHNIQUE: poor.

PRESERVATION: good.

- 36282. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '009. Height, 0 m '009.—Plate V.—Abydos (1881).

DESCRIPTION: Inscribed with the name of Rameses-mery-amen: with hieroglyphic legend below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, turning white, but of fine quality.

TECHNIQUE: very well cut.

PRESERVATION: slightly chipped at head.

BIBL: *Journal d'entrée du Musée*, No. 25039. MASPERO, *Slip Cat.*, No. 3766.

- 36283. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate V.—Tell el Yahudiyeh.

DESCRIPTION: Inscribed with the prenomen of Rameses III. *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: excellent cutting, and modelling fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 27717.

- 36284. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate V.—Memphis.

DESCRIPTION: Inscribed with the prenomen of Sety II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: medium cutting: back well modelled.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3774. PETRIE, *Hist. Scarab*, No. 1623. MAR., *M.D.*, 32, 1.

- 36285. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Sety II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: a very fine blue-green.

TECHNIQUE: fine modelling and cutting.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3773.

- 36286. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate V.

DESCRIPTION: Inscribed with the prenomen of Rameses IV. *Back*, see Plate XX.

DATE: Twentieth Dynasty.

GLAZE: blue, turning green.

TECHNIQUE: modelling of back, fair; cutting, coarse.

PRESERVATION: good.

- 36287. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '011.—Plate V.

DESCRIPTION: *Rameses II* (or *Sety II* ?) in a chariot drawn by a horse: above is the prenomen of the king. Remains of bronze swivel in piercing. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: green, turning white.

TECHNIQUE: modelling of back fine, cutting poor.

PRESERVATION: good.

- 36288. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate V.

DESCRIPTION: Inscribed with the prenomen of *Pa-mentu*. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-first Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: back fairly modelled, cutting poor.

PRESERVATION: flaked on back.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, in 1882.

- 36289. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the prenomen of *Osorkon II* (?). *Back*, rounded prothorax and elytra marked.

DATE: Twenty-second Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: very good cutting, and modelling fair.

PRESERVATION: chipped on edge.

BIBL.: MASPERO, *Slip Cat.*, No. 3785.

- 36290. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the name of *Nefret-ari-mer-en-mut*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: medium cutting, back lumpy.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29936. Bought in Upper Egypt. *Catal. du Musée*, n. 36001.

- 36291. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Taharqa. *Back*, rounded prothorax and elytra marked.

DATE : Twenty-fifth Dynasty.

GLAZE : green, turned brown.

TECHNIQUE : good cutting and modelling.

PRESERVATION : good.

- 36292. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m '028. Width, 0 m '02. Height, 0 m '014.—Plate V.

DESCRIPTION : Inscribed with the prenomen and nomen of Sheshanq I in cartouches, with titles above, and a *nub*-sign below. *Back*, see Plate V.

DATE : Twenty-second Dynasty.

GLAZE : green, turned brownish-yellow.

TECHNIQUE : good cutting and modelling.

PRESERVATION : chipped at sides.

BIBL : MASPERO, *Slip Cat.*, No. 3784.

- 36293. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate V.—Sheikh abd el Kurneh.

DESCRIPTION : Inscribed with the names of Kashta and Amenardes within cartouches. *Back*, see Plate V.

DATE : Twenty-fourth Dynasty.

GLAZE : deep blue, of very fine quality.

TECHNIQUE : cutting and modelling fine.

PRESERVATION : perfect.

BIBL : *Journal d'entrée du Musée*, No. 25714. Found together with Nos. 36001, 36002, and 36596. PETRIE, *Hist. Scarabs*, No. 1832.

- 36294. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '009.—Plate V.

DESCRIPTION : Inscribed with the nomen and prenomen of Sheshanq within cartouches; titles above and a *nub*-sign below. *Back*, prothorax and elytra marked.

DATE : Twenty-second Dynasty.

GLAZE : green, turned brown.

TECHNIQUE : good cutting and modelling.

PRESERVATION : good.

- 36295. Scarab-shaped Seal.**—Paste.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate V.

DESCRIPTION: Inscribed with the name of Amenardes within a cartouche: on either side are urai. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-fourth Dynasty.

PASTE: blue-green, of fine quality.

TECHNIQUE: good cutting.

PRESERVATION: chipped at side.

BIBL.: MASPERO, *Slip Cat.*, No. 3788. PETRIE, *Hist. Scarabs*, No. 1831.

- 36296. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate V.—Kurneh (1859).

DESCRIPTION: Inscribed with the names of Kashata and Amenardes within cartouches: titles above. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-fourth Dynasty.

GLAZE: green, turned brownish-white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25715. Found in a tomb at Sheikh abd el Kurneh, together with Nos. 36001, 36002, 36596. *Journal d'entrée du Musée*, No. 3416. MASPERO, *Slip Cat.*, No. 3787. PETRIE, *Hist. Scarabs*, No. 1770.

- 36297. Scarab-shaped Seal.**—Paste.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '011.—Plate V.

DESCRIPTION: Inscribed with the nomen and prenomen of Sheshanq within cartouches: a *nub*-sign below. Mounted in a silver fundu. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-second Dynasty.

PASTE: dark blue.

TECHNIQUE: back finely moulded and carved.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 3783. PETRIE, *Hist. Scarabs*, No. 1775.

- 36298. Scarab-shaped Seal.**—Paste.—Length, 0 m '011. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed with the name of Aahmes (II). *Back*, prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

PASTE: dark blue.

TECHNIQUE: coarse cutting and back lumpy.

PRESERVATION: good.



- 36299. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·01. Height, 0 m ·008.—Plate V.

DESCRIPTION : Inscribed with the prenomen of Psamtek I. *Back*, as No. 36298.

DATE : Twenty-sixth Dynasty.

GLAZE : fine pea-green.

TECHNIQUE : coarse.

PRESERVATION : good.

- 36300. Scarab-shaped Seal**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·00(?)—Plate VI.

DESCRIPTION : Inscribed with the prenomen of *Ded-ka-ra* (Shabataka) with a *nub*-sign below. *Back*, broken away.

DATE : Twenty-fifth Dynasty.

GLAZE : green.

TECHNIQUE : coarse.

PRESERVATION : back broken away.

- 36301. Scarab-shaped Seal**—Paste.—Length, 0 m ·029. Width, 0 m ·018. Height, 0 m ·014.—Plate VI.

DESCRIPTION : Inscribed with the name of Taharqa. *Back*, see Plate VI.

DATE : Twenty-fifth Dynasty.

PASTE : yellow (brown on surface).

TECHNIQUE : moulded.

PRESERVATION : much worn.

- 36302. Scarab-shaped Seal**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate VI.

DESCRIPTION : Inscribed with the name of Psamtek. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Twenty-sixth Dynasty.

GLAZE : pea-green, of good quality.

TECHNIQUE : modelling and cutting excellent.

PRESERVATION : good.

- 36303. Scarab-shaped Seal.**—Schist, unglazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed with the name of Psamtek. *Back*, prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

TECHNIQUE: coarse, back lumpy.

PRESERVATION: head of beetle chipped off.

BIBL: *Journal d'entrée du Musée*, No. 29952. Bought in Upper Egypt.

- 36304. Scarab-shaped Seal**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed with the name of Psamtek. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty.

GLAZE: green.

TECHNIQUE: fair and deeply cut.

PRESERVATION: back flaked.

- 36305. Scarab-shaped Seal.**—Paste.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with the name Psamtek. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

PASTE: light yellow.

TECHNIQUE: fair, back well cut.

PRESERVATION: much worn.

- 36306. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '011.—Plate V.

DESCRIPTION: Inscribed on the back with the prenomen of Rameses II: below, on the seal, are three deities, Amen, Ra, and Sekhmet.

DATE: Nineteenth Dynasty.

GLAZE: blue-green, of poor quality.

TECHNIQUE: badly moulded and damaged in baking.

PRESERVATION: fair.

BIBL: *Journal d'entrée du Musée*, No. 5113.

- 36307. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·00(?).—Plate VI.

DESCRIPTION: Inscribed with the name of Merḥ[t]-amen. *Back*, flaked away.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: good cutting and modelling.

PRESERVATION: back flaked, otherwise perfect.

- 36308. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·005.—Plate VI.

DESCRIPTION: Inscribed with the name of Psamtek. *Back*, flaked away.

DATE: Twenty-sixth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: fair.

PRESERVATION: back flaked, otherwise good.

- 36309. Scarab-shaped Seal.**—Paste.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·007.—Plate VI.

DESCRIPTION: Inscribed with the prenomen of Amenhetep II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty (?).

PASTE: dark blue.

TECHNIQUE: fair cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 27501. Bought.

- 36310. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·008.—Plate VIII.—Sakkara (1873).

DESCRIPTION: Inscribed with the name of Amen, "Lord of the Gods." *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: fine blue.

TECHNIQUE: good modelling of back and cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 22049.

- 36311. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate VIII.—Darb Esbeida.

DESCRIPTION: Inscribed with the name of Amen, "King of the Gods." *Back*, prothorax and elytra marked with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: fine green, of good quality.

TECHNIQUE: good cutting and modelling.

PRESERVATION: excellent.

BIBL.: *Journal d'entrée du Musée*, No. 35172.

- 36312. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·01.—Plate IX.

DESCRIPTION: Inscribed on the base with a kneeling figure of a king offering to a seated figure of Thoth as a cynocephalus (*cf.* No. 36443). *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Nineteenth Dynasty.

GLAZE: dark blue, of good quality, crackled.

TECHNIQUE: finely cut.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cut.*, No. 3823.

- 36313. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate IX.

DESCRIPTION: Inscribed with a figure of the god Bes. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: fair.

PRESERVATION: good.

- 36314. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·009.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra. *Back*, see Plate VIII.

DATE: Nineteenth Dynasty or later.

GLAZE: green, turned white.

TECHNIQUE: the inscription is in relief and well cut.

PRESERVATION: perfect.

BIBL.: Note on a label—"Given by E. BRUGSCH BEY."

**36315. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '017. Height, 0 m '011.—Plate IX.

DESCRIPTION: Inscribed with figures of the deities Amen, Ra, and Sekhmet. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: coarse.

PRESERVATION: fair.

**36316. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '009.—Plate IX.

DESCRIPTION: Inscribed with a figure of the god Ptah holding an *uas*-sceptre, and before him two altars. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: cutting and modelling good.

PRESERVATION: good.

**36317. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate VII.—Abydos (1881).

DESCRIPTION: Inscribed with a figure of a hawk-headed man with uræus in front of him. *Back*, rounded prothorax and elytra marked.

DATE: Hyksos period.

GLAZE: green, uneven and dull.

TECHNIQUE: coarse.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 25046.

**36318. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed with a figure of the god Set. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: good cutting and modelling.

PRESERVATION: excellent.

BIBL: *Journal d'entrée du Musée*, No. 31293. Bought.

- 36319. Scarab-shaped Seal.**—Pottery.—Length, 0 m '009. Width, 0 m '006. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra. *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: pea-green.

TECHNIQUE: coarse.

PRESERVATION: worn at edges.

- 36320. Scarab-shaped Seal.**—Rock crystal.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '011.—Plate IX.

DESCRIPTION: Inscribed with figures of the gods Amen and Ra. *Back*, prothorax slightly indicated but no elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: back roughly modelled and cutting coarse.

PRESERVATION: fair.

- 36321. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '009.—Plate IX.

DESCRIPTION: Inscribed with a figure of a king standing between Ra and Anubis. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (Rameses II).

GLAZE: dark green, of uneven quality.

TECHNIQUE: back fair; cutting poor.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181 (given by M. CAREY in 1882). MASPERO, *Slip Cat.*, No. 3097.

- 36322. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed with a figure of the god Amen (?) and hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, slightly crackled.

TECHNIQUE: modelling of back and cutting fair.

PRESERVATION: good.

*Catal. du Musée*, n. 36001.

11

**36323. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·009.—Plate IX.—Abydos.

DESCRIPTION: Inscribed with seated figures of Hathor, Ra, and Set. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25831.

**36324. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·016. Height, 0 m ·01.—Plate IX.

DESCRIPTION: Inscribed with a recumbent figure of the god Amen as a ram; above his back is a winged uræus, and before him a figure of Maat. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (Rameses II).

GLAZE: green, turning to white.

TECHNIQUE: modelling and cutting good.

PRESERVATION: good.

**36325. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·014. Height, 0 m ·008.—Plate IX.

DESCRIPTION: A recumbent figure of the god Amen as a ram; above his back the word Amen and before him a figure of Maat. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green.

TECHNIQUE: modelling and cutting good.

PRESERVATION: good.

**36326. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·006.—Plate XVII.

DESCRIPTION: Inscribed with a figure of a hawk with wings outspread: to the right are hieroglyphic signs. *Back*, round prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of very fine quality.

TECHNIQUE: modelling of back very delicate and cutting fine.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cut.*, No. 3811.

- 36327. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·01.—Plate IX.

DESCRIPTION: Inscribed with the standing figures of three gods upon a *web*-sign.

*Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty.

GLAZE: dark blue, badly burnt.

TECHNIQUE: modelling of back good, cutting poor.

PRESERVATION: much destroyed by salt.

- 36328. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·015. Height, 0 m ·008.—Plate X. Abydos (1881).

DESCRIPTION: Inscribed with a Hathor-head, with uraei suspended from ears.

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Hyksos period.

GLAZE: green, turning brown.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 25038.

- 36329. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate XIV.

DESCRIPTION: Inscribed with a figure of a man in a chariot hunting animals in the desert. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turned whitey-brown.

TECHNIQUE: coarse but deep cutting, modelling coarse.

PRESERVATION: edges chipped.

- 36330. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.

DESCRIPTION: Similar to No. 36329.

DATE: Nineteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: coarse.

PRESERVATION: edges chipped.



**36331. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·007.—Plate IX.

DESCRIPTION: Inscribed on the base with the figure of a man and a vase. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: green, turned brown.

TECHNIQUE: modelling of back good, cutting coarse.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

**36332. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·016. Height, 0 m ·011.—Plate IX.

DESCRIPTION: A papyrus flower with two figures of the god Hapi on either side, facing one another. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: modelling good; cutting fair.

PRESERVATION: chipped on edge.

BIBL.: *Journal d'entrée du Musée*, No. 28152. Bought.

**36333. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·026. Width, 0 m ·018. Height, 0 m ·01.—Plate XII.

DESCRIPTION: A twisted rope pattern. Set in a gold fundu. *Back*, see Plate XII.

DATE: Thirteenth—Seventeenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: modelling of back poor, cutting good.

PRESERVATION: medium.

**36334. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·013. Height, 0 m ·008.—Plate IX.

DESCRIPTION: A kneeling figure of the goddess Maat with arms upraised: on either side of her an *ankh*-sign. Set in a gold fundu. *Back*, see Plate IX.

DATE: Middle Eighteenth Dynasty. (Thothmes III.)

GLAZE: blue-green, of fine quality.

TECHNIQUE: exquisite modelling and fine cutting.

PRESERVATION: perfect.

- 36335. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '01.—Plate VII.—Tell el Yahudiyeh.

DESCRIPTION: A crocodile-headed man holding in his left hand a lotus flower. Below is a *neb*-sign. *Back*, see Plate VII.

DATE: Hyksos Period.

GLAZE: blue, turned white.

TECHNIQUE: very fine modelling and cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entré du Musé*, No. 27713.

- 36336. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VII.

DESCRIPTION: A bearded sphinx with a *ra*-sign in front of it and below, a *neb*-sign. *Back*, broken.

DATE: Nineteenth Dynasty (?).

GLAZE: green.

TECHNIQUE: poor cutting.

PRESERVATION: back broken away.

- 36337. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '00(?).—Plate VII.

DESCRIPTION: A bearded sphinx with a *ra*-sign over its back, a feather before it and a *neb*-sign below. *Back*, broken.

DATE: Nineteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: cutting coarse.

PRESERVATION: back broken away.

- 36338. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra, and a *nefer*-sign. *Back*, see Plate XX.

DATE: Nineteenth Dynasty or later.

GLAZE: green, turned white.

TECHNIQUE: modelling medium, cutting fine.

PRESERVATION: good.

BIBL: *Journal d'entré du Musé*, No. 34129.

**36339. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate IX.

DESCRIPTION: Inscribed with the figure of the god Amen-ra as a ram, wearing the *atef*-crown. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: good modelling and fine cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29935. Bought.

**36340. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '03. Width, 0 m '022. Height, 0 m '013.—Plate IX.—Abydos.

DESCRIPTION: Inscribed with a figure of Ra between two obelisks. Above him a *men*-sign and the sun's disc. *Back*, see Plate IX.

DATE: Twentieth Dynasty (?).

GLAZE: blue, of good quality.

TECHNIQUE: modelling and cutting coarsish.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 34450.

**36341. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged, and a loop and coil pattern border around them. *Back*, Shesha type.

DATE: Twelfth Dynasty or Hyksos period.

GLAZE: green.

TECHNIQUE: fine cutting.

PRESERVATION: worn on back and chipped at head.

BIBL.: *Journal d'entrée du Musée*, No. 29945. Bought in Upper Egypt.

**36342. Scarab-shaped Seal.**—Paste.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a human-headed sphinx trampling over a cobra. *Back*, prothorax indicated as No. 36709.

DATE: Early Eighteenth Dynasty.

PASTE: dark green.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 31293. Bought.

- 36343. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with a figure of Maat holding branches in her hands and below her, a *nub*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: light green, going white.

TECHNIQUE: coarse cutting, back fairly modelled.

PRESERVATION: good.

- 36344. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '01. Height, 0 m '006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, see Plate XX.

DATE: Late Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: very fine cutting and good modelling.

PRESERVATION: excellent.

BIBL.: *Journal d'entrée du Musée*, No. 29993. Upper Egypt.

- 36345. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '01.—Plate VI.

DESCRIPTION: Inscribed on the base with the name Nefer-Ra in an oval: hieroglyphic signs above and at the sides. *Back*, prothorax and elytra marked.

DATE: Twelfth or Hyksos period.

GLAZE: blue, gone white and nacreous.

TECHNIQUE: cutting good.

PRESERVATION: chipped on back.

- 36346. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with the name *Nub-maat-Ra*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: green.

TECHNIQUE: medium cutting and modelling.

PRESERVATION: flaked on back.

- 36347. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate VI.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with the legend (?) *Nub-ma-es-Ra*. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: light grey-blue, going white.

TECHNIQUE: good modelling of back.

BIBL: *Journal d'entrée du Musée*, No. 25198. MASPERO, *Stip Cat.*, No. 1698, PETRIE, *Hist. Scarabs*, No. 743.

- 36348. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·008.—Plate VI.—Drah abu'l Negga.

DESCRIPTION: Inscribed on the base with the titles and name (?) of a king. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good colour.

TECHNIQUE: cutting very rough.

PRESERVATION: legs of beetle chipped.

BIBL: *Journal d'entrée du Musée*, No. 33438.

- 36349. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate XV.

DESCRIPTION: Inscribed on the base with figures of three scorpions. *Back*, see Plate XV.

DATE: Middle Eighteenth Dynasty. (Thothmes III.)

GLAZE: dark green, going brown.

TECHNIQUE: very fine cutting and modelling.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36350. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a hand. *Back*, see Plate XX.

DATE: Nineteenth Dynasty or later.

GLAZE: dark blue.

TECHNIQUE: poor work.

PRESERVATION: perfect.

- 36351. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a man in a chariot drawn by a horse. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: good cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36352. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '010.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a man in a chariot drawn by a horse. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: cutting medium.

PRESERVATION: fair.

- 36353. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '011.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs within a border of concentric circles. *Back*, see Plate XIV.

DATE: Hyksos Period (?).

GLAZE: gone white and nacreous.

TECHNIQUE: very delicate cutting.

PRESERVATION: perfect.

- 36354. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with the titles *seten buti*. *Back*, Shesha type.

DATE: Eighteenth Dynasty.

GLAZE: green, of fine colour, going brown on back.

TECHNIQUE: cutting fair.

PRESERVATION: slightly chipped on edge.

*Catal. du Musée*, n. 36001.

12

**36355. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate VI.—Kurneh (1858).

DESCRIPTION: Inscribed on the base with the signs *kha-neferu* within a cartouche, and hieroglyphic signs above and below. *Back*, prothorax indicated as No. 36543.

DATE: Hyksos Period.

GLAZE: medium blue, of fine colour, turning white on back.

TECHNIQUE: fine deep cutting and good modelling.

PRESERVATION: worn on back.

BIBL: *Journal d'entrée du Musée*, No. 2527. MASPERO, *Slip Cut.*, No. 3675, Abydos, 1391 (?). PETRIE, *Hist. Scarabs*, No. 567.

**36356. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate VII.—Abydos (Amlineau).

DESCRIPTION: Inscribed on the base with the figure of a beetle with outspread wings. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 31356.

**36357. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, see Plate XI.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: fine blue-green.

TECHNIQUE: fine cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 31979. Bought.

**36358. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '017. Height, 0 m '01.—Plate XI.

DESCRIPTION: Inscribed on the base with the figure of a lion with hieroglyphs in the field. *Back*, see Plate XI.

DATE: Hyksos Period.

GLAZE: green, turning whity-brown.

TECHNIQUE: fine cutting.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 29350. Given by Mr. FRASER.

- 36359. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '031. Width, 0 m '02. Height, 0 m '014.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra with a *dmd*-sign below. On the back is a beetle with ram's head and horns, wearing disc (see Plate VIII).

DATE: Twenty-fourth Dynasty.

GLAZE: fine light blue, going white in thin parts.

TECHNIQUE: fair cutting, and legs pierced through the whole width.

PRESERVATION: perfect.

- 36360. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a *V* on either wing-case (see Plate XXII).

DATE: Middle Eighteenth Dynasty (Thothmes III).

GLAZE: bluey-green, of fine quality and colour.

TECHNIQUE: very delicate work.

PRESERVATION: excellent.

BIBL.: *Journal d'entré du Musée*, No. 31293. Bought.

- 36361. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of uniting of Upper and Lower Egypt with a *neb*-sign below. *Back*, see Plate XI.

DATE: Early Eighteenth Dynasty.

GLAZE: fine light green glaze, rich in colour.

TECHNIQUE: good cutting.

PRESERVATION: excellent.

BIBL.: *Journal d'entré du Musée*, No. 31293. Bought.

- 36362. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with the titles *Suten huti*. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty.

GLAZE: turned white.

TECHNIQUE: very coarse work.

PRESERVATION: much chipped.



- 36363. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with the titles *Seten bati*. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue.

TECHNIQUE: coarse.

PRESERVATION: chipped on edge.

- 36364. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·016. Height, 0 m ·01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: green, gone a brownish-grey.

TECHNIQUE: very fine and bold cutting.

PRESERVATION: excellent.

- 36365. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk with wings outspread and holding in its talons seals. Below is a necklace. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fine cutting, and legs pierced through whole width.

PRESERVATION: excellent.

BIBL.: *Journal d'entré du Musée*, No. 31293. Bought.

- 36366. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, Shesha type.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, turned a brownish-grey.

TECHNIQUE: cutting fair.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 25684. Bought.

- 36367. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a winged griffon with hieroglyphic signs before it. *Back*, prothorax indicated as No. 36555.

DATE: Hyksos Period (?).

GLAZE: a fine green, turning brown.

TECHNIQUE: good.

PRESERVATION: excellent.

- 36368. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs, *Back*, see Plate XV.

DATE: Nineteenth Dynasty.

GLAZE: light blue glaze, going brown.

TECHNIQUE: fine back and cutting.

PRESERVATION: good.

- 36369. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged, and a loop-pattern border around them. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: light blue-green, gone white in places.

TECHNIQUE: Delicate cutting.

PRESERVATION: chipped on edge.

BIBL.: *Journal d'entré du Musée*, No. 25181. Given by M. CAREY, 1882.

MASPERO, *Slip Cat.*, No. 3097.

- 36370. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with a decorative device. *Back*, see Plate XIII.

DATE: Early Eighteenth Dynasty.

GLAZE: fine blue.

TECHNIQUE: very delicate work on back, but coarsish below.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36371. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '018. Height, 0 m '011.—Plate IX.

DESCRIPTION: Inscribed on the base with two figures of Ra. *Back*, rounded prothorax and elytra marked (see Plate XX).

DATE: Nineteenth Dynasty.

GLAZE: green, of dullish hue.

TECHNIQUE: coarse cutting.

PRESERVATION: good.

- 36372. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with the figure of a man between two crocodiles. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turned a brownish-white.

TECHNIQUE: very poor but deep cutting.

PRESERVATION: good.

- 36373. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '034. Width, 0 m '025. Height, 0 m '016.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, see Plate XI.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned a dull red-brown.

TECHNIQUE: poor cutting.

PRESERVATION: perfect.

- 36374. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion, an uræus and a feather. *Back*, see Plate VII.

DATE: Early Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: finely cut and modelled.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882. MASPERO, *Slip Cut.*, No. 3097.

- 36375. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .011. Width, 0 m .009. Height, 0 m .006.—Plate IX.

DESCRIPTION: Inscribed on the base with a kneeling figure of Hapô. *Back*, prothorax indicated as No. 36709.

DATE: Nineteenth Dynasty or later.

GLAZE: green, going white on back.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

- 36376. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .009. Height, 0 m .007.—Plate VIII.

DESCRIPTION: Inscribed with the legend "Khensu in Thebes" (*uas?*). *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, gone brownish-white.

TECHNIQUE: cutting poor, modelling of back poor.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 29967. Bought.

- 36377. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .016. Width, 0 m .011. Height, 0 m .009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. (Compare Nos. 36378 and 36560.) *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone a whitish-brown.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good.

- 36378. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .015. Width, 0 m .011. Height, 0 m .007.—Plate X.

DESCRIPTION: Similar to No. 36377. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning white in places.

TECHNIQUE: good cutting.

PRESERVATION: worn on back.

- 36379. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: rich blue, of medium colour.

TECHNIQUE: fine cutting.

PRESERVATION: good.

- 36380. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: fine cutting.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29961. Bought.

- 36381. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VI.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone a yellow-brown.

TECHNIQUE: coarse, but back fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198. MASPERO, *Slip Cat.*, No. 1697.

- 36382. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate XI.—Abydos.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Twelfth Dynasty, or Hyksos Period.

GLAZE: green, turned white in thin places.

TECHNIQUE: medium work.

PRESERVATION: slightly chipped on edge.

BIBL.: *Journal d'entrée du Musée*, No. 30259.

- 36383. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 37132.

DATE: Hyksos Period.

GLAZE: green, of good quality, turning white in thin places.

TECHNIQUE: excellently cut.

PRESERVATION: Excellent.

- 36384. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with figures of two scorpions. *Back*, prothorax and elytra marked, with a **V** on left wing-case.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: very coarse cutting.

PRESERVATION: fair.

- 36385. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, turned white in places.

TECHNIQUE: cutting bold.

BIBL: *Journal d'entr e du Mus e*, No. 29957. Bought.

- 36386. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs between two vertical lines. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turned yellow-brown.

TECHNIQUE: cutting bold.

PRESERVATION: good.

BIBL: *Journal d'entr e du Mus e*, No. 29950. Bought in Upper Egypt.

*Catal. du Mus e*, n. 36001.

13

- 36387. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate XV.—Abydos (1881).

DESCRIPTION: Inscribed on the base with figures of four uræi. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light green.

TECHNIQUE: cutting coarse.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 25042.

- 36388. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·008.—Plate XV.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue (?), turned white.

TECHNIQUE: poor work.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36389. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion: above it is a flying hawk. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: light emerald-green, turning white.

TECHNIQUE: cutting good.

PRESERVATION: good.

- 36390. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate X.—Abydos.

DESCRIPTION: Inscribed with the title *neter nefer*, and *tawi* blundered for *neb tawi*. *Back*, prothorax indicated as No. 37107.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: brilliant blue.

TECHNIQUE: run in baking.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cut.*, No. 3798, Abydos, 1379. PETRIE, *Hist. Scarabs*, No. 151.

- 36391. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a human head. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, turned a yellowish-white and burnt black below.

TECHNIQUE: delicate cutting and modelling.

PRESERVATION: good.

- 36392. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VII.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with the figure of a human-headed and winged sphinx standing before a cobra with wings outspread. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (Thothmes III).

GLAZE: light blue, gone white in thin parts.

TECHNIQUE: cutting fair.

PRESERVATION: head of beetle chipped, otherwise perfect.

BIBL: *Journal d'entré du Musée*, No. 25198.

- 36393. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra. "Lord of the breath of life," with *ankh* and *was*-signs to the left. The scarab at the back is human-headed (see Plate VIII).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: greeny-blue.

TECHNIQUE: cutting good. Head on back a separate piece, and legs pierced right through the width of beetle.

PRESERVATION: perfect.

BIBL: *Journal d'entré du Musée*, No. 31293. Bought.

- 36394. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '01.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs within an oval, and crowned urai on either side. Above are three papyrus flowers and below a *neb*-sign.

DATE: Hyksos Period.

GLAZE: green, turned brown in thin places.

TECHNIQUE: cutting excellent and sharp.

PRESERVATION: very good.

BIBL: MASPERO, *Slip Cat.*, No. 3676. PETRIE, *Hist. Scarabs*, No. 538.



**36395. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '00(?).—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus, a *ufer*- and a *neb*-sign. *Back*, broken away.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dullish blue.

TECHNIQUE: medium.

PRESERVATION: back broken away.

**36396. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: good cutting.

PRESERVATION: good.

BIBL: MASPERO, *Stip Cat.*, No. 1684.

**36397. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: greeny-blue, turning white, of good quality

TECHNIQUE: fair work and modelling good.

PRESERVATION: chipped on one end.

**36398. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *mart Amen-ra nen send*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: medium work.

PRESERVATION: chipped at head.

- 36399. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '01.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra, "King of the Gods," and a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: cutting rough.

PRESERVATION: back flaked, otherwise perfect.

BIBL: MASPERO, *Slip Cut.*, No. 1692.

- 36400. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, without prothorax or elytra marked.

DATE: Twelfth Dynasty.

GLAZE: light blue, turning white on back.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

- 36401. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width 0 m '013. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with the name of the *Sab Amenhetep*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-second Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: modelling and cutting coarse.

PRESERVATION: head chipped, otherwise perfect.

- 36402. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt, with a *nefer*-sign above in an oval. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty, or Hyksos Period.

GLAZE: blue, gone white and worn.

TECHNIQUE: cutting good.

PRESERVATION: fair, but glaze worn.

**36403. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·013. Height, 0 m ·009.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Middle Eighteenth Dynasty.

GLAZE: fine green, gone white in thin parts.

TECHNIQUE: modelling very fine.

PRESERVATION: slightly chipped.

**36404. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx, wearing a disc on its head. Before it is a *nefer*-sign, and over its back a cobra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: light green.

TECHNIQUE: coarse work.

PRESERVATION: good.

**36405. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·013. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a human-headed sphinx with hieroglyphs in the field. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone white in places.

TECHNIQUE: cutting very deep and fine; back fair.

PRESERVATION: perfect.

**36406. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·014. Height, 0 m ·009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a bull, with a *nefer*-sign above. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turned a whity-brown.

TECHNIQUE: cutting and modelling good.

PRESERVATION: perfect.

- 36407. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with a name (?) in an oval; a *nub*-sign above, and hieroglyphs to the left. *Back*, prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: green, turned brown in places.

TECHNIQUE: cutting coarse, and back lumpy.

PRESERVATION: perfect.

- 36408. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Twelfth Dynasty.

GLAZE: green, turning brown and grey.

TECHNIQUE: cutting good, and modelling of back good.

PRESERVATION: fair.

- 36409. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '011.—Plate XIII.—Drah abu'l Negga.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax and elytra marked.

DATE: Seventeenth Dynasty.

GLAZE: fine blue-green.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: back partly broken.

BIBL.: *Journal d'entrée du Musée*, No. 21475. Found in the tomb of Thuau at Drah abu'l Negga.

- 36410. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '013. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt, and *ankh*-signs on either side. *Back*, prothorax indicated as No. 37132.

DATE: Twelfth Dynasty.

GLAZE: blue, of fine colour and quality.

TECHNIQUE: modelling of back and cutting fine.

PRESERVATION: back chipped at bottom, otherwise perfect.

- 36411. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width 0 m '011. Height, 0 m '009.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green (turned blue on seal), of very fine quality.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

- 36412. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate XI.—Zawiet el Arrian.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, gone brown on back.

TECHNIQUE: modelling and cutting fair.

BIBL: *Journal d'entrée du Musée*, No. 25165.

- 36413. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: red, worn off in parts.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 33619. Given by EMILE BRUGSCH BEY.

- 36414. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '019. Height, 0 m '012.—Plate IX.—Abydos.

DESCRIPTION: Inscribed on the base with figures of Amen and Ra holding a papyrus sceptre before them. *Back*, prothorax indicated (see Plate XIX).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light blue.

TECHNIQUE: cutting of seal coarse, modelling of back fair.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 34450.

- 36415. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '025. Width, 0 m '017. Height, 0 m '012.—Plate XI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend(?) with a decorative border. *Back*, see Plate XI.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: cutting coarse.

PRESERVATION: edges chipped.

- 36416. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '009. Height, 0 m '006.—Plate XI.—Abydos.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, worn off on back.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 30261.

- 36417. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '007.—Plate XI.—Mitraheny (1900).

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, plain (see Plate XIX).

DATE: Twelfth Dynasty.

GLAZE: light blue, turned white on back.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 34085.

- 36418. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VII.—Abydos (1900).

DESCRIPTION: Inscribed on the base with the figure of a beetle with four concentric circles around it. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, turning brown, and of poor quality.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 34146.

*Catal. du Musée*, n. 36001.

14

- 36419. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity with a cobra in front. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: perfect.

- 36420. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate VIII.—Abydos (1900).

DESCRIPTION: Inscribed with the name of Amenhetep. *Back*, see Plate XX.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: light grey-violet.

TECHNIQUE: modelling and cutting good.

PRÉSERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31991.

- 36421. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend (?) of doubtful meaning. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty or later.

GLAZE: green, gone a yellowy-white.

TECHNIQUE: cutting fair, legs pierced through the whole width.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 28155. Bought.

- 36422. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '025. Width, 0 m '018. Height, 0 m '00(?).—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a palm tree up which four monkeys are climbing. *Back*, prothorax marked, with a V on wing-case, rest worn away.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned a brownish-yellow.

TECHNIQUE: cutting good.

PRESERVATION: back worn away and edges chipped.

- 36423. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt with hieroglyphic signs symmetrically arranged above. *Back*, see Plate XI.

DATE: Nineteenth Dynasty.

GLAZE: light blue-green, of fine quality, worn on back to brown.

TECHNIQUE: fair work.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29349. Bought.

- 36424. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a winged griffon: before it is a beetle. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: chocolate-red, gone yellow in thin parts.

TECHNIQUE: fine work.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31980.

- 36425. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed on the base with a winged figure. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

PASTE: dull violet-blue.

TECHNIQUE: coarse cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 28153. Bought.

- 36426. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '009.—Plate VIII.—Tell el Yahudiyeh.

DESCRIPTION: Inscribed with the figure of a goose, the name of Amen above, and a *nefer*-sign in front. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: blue, turning white, and run in places.

TECHNIQUE: fair.

PRESERVATION: chipped on edges.

BIBL.: *Journal d'entrées du Musée*, No. 27715.



**36427. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate IX.—Gadrah.

DESCRIPTION: Inscribed on the base with a figure of the god Tum, holding a spear: hieroglyphs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Nineteenth Dynasty.

GLAZE: very light blue-green, turning yellow and crackled.

TECHNIQUE: fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29406.

**36428. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with the titles *seten bati, mery Amen*. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: cutting very coarse.

PRESERVATION: chipped on edge.

**36429. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion attacking a hawk-headed figure. *Back*, prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: fair, and cutting deep.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 27715.

**36430. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate IX.—Abydos.

DESCRIPTION: Inscribed on the base with a figure of Ptah standing before a seated figure of Thoth as a cynocephalus. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty.

GLAZE: a fine green-blue.

TECHNIQUE: excellent cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31991.

- 36431. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king standing before Ptah.

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white and slightly worn on back.

TECHNIQUE: cutting coarsish.

PRESERVATION: good.

- 36432. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed with the titles *Ntr nfr, nb tw*. *Back*, see Plate XXI.

DATE: Eighteenth Dynasty.

GLAZE: green, badly burnt.

TECHNIQUE: modelling good, but cutting bad.

PRESERVATION: slightly chipped on edge.

- 36433. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 36947.

DATE: Twelfth—Seventeenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fine cutting.

PRESERVATION: perfect.

- 36434. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: fair cutting and modelling good.

PRESERVATION: perfect.

**36435. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate XIII.—Mitraheny (1904).

DESCRIPTION: Inscribed on the base with four cobras and an ornamental design (*cf.* No. 37299). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: cutting and modelling good, legs deeply cut.

PRESERVATION: back worn, otherwise perfect.

BIBL.: *Journal d'entrée du Musée*, No. 34085.

**36436. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·009.—Plate XV.—Abydos.

DESCRIPTION: Inscribed on the base with a papyrus sceptre, an uræus and hieroglyphic signs. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, turned white on back.

TECHNIQUE: modelling good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 31991.

**36437. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·013. Height, 0 m ·008.—Plate XIV.—Abydos.

DESCRIPTION: Inscribed on the base with the figure of a king adoring a bull: over the bull is a hawk and hieroglyphic signs. *Back*, see Plate XXII.

DATE: Middle Eighteenth or Nineteenth Dynasty.

GLAZE: green.

TECHNIQUE: cutting and modelling very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31991.

**36438. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king kneeling in adoration before an obelisk. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: very light blue-green.

TECHNIQUE: cutting fair, modelling good.

PRESERVATION: perfect.

- 36439. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with a symmetrical design. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark blue-green, cracked.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: perfect.

- 36440. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a winged uræus with a *ra*-sign in front of it. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twentieth Dynasty or later.

GLAZE: medium blue.

TECHNIQUE: cutting and modelling excellent.

PRESERVATION: perfect.

- 36441. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·004.—Plate XV.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: green, turned a brownish-white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION; perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36442. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.—Plate X.

DESCRIPTION: Inscribed on the base with the title *Ankh Heru set*. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: good.

**36443. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·011.—Plate IX.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with a kneeling figure of a king offering to a seated figure of Thoth as a cynocephalus (*cf.*, No. 36312). *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: dark green, gone brown.

TECHNIQUE: cutting and modelling excellent, legs deeply cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25198. MASPERO, *Slip Cat.*, No. 1697.

**36444. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, see Plate XX.

DATE: Nineteenth Dynasty or later.

GLAZE: light grey-green, rubbed off in thin places.

TECHNIQUE: coarse work.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29948. Bought in Upper Egypt.

**36445. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed with legend:—"The King of Upper and Lower Egypt, Amen-ra." *Back*, rounded prothorax and elytra marked.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: green, of poor quality.

TECHNIQUE: coarsish work and cutting coarse.

PRESERVATION: chipped on back.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

**36446. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with three *nfer*-signs. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: good.

- 36447. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: blue-green, turning whity-brown.

TECHNIQUE: cutting and modelling good, legs deeply cut.

PRESERVATION: good.

- 36448. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx with a disc upon its head. Before it is a figure of the goddess Maat, and over its back are hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue-green, turning white and brown.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: much worn, and edges chipped.

BIBL.: *Journal d'entré du Musée*, No. 25181. Given by M. CAREY, 1882.

MASPERO, *Stip Cat.*, No. 3097.

- 36449. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull blue-green.

TECHNIQUE: modelling and cutting coarse.

PRESERVATION: chipped.

- 36450. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 36529.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, turned white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: good.

*Catal. du Musée*, n. 36001.

15

**36451. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: greeny-blue, of poor quality.

TECHNIQUE: cutting and modelling good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 31293. Bought.

**36452. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Nineteenth Dynasty.

GLAZE: green, of good quality, turning white in thin parts.

TECHNIQUE: cutting good, modelling very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31293. Bought.

**36453. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a fish between two scorpions. *Back*, prothorax indicated but no elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, turned brown and white in thin places.

TECHNIQUE: modelling and cutting excellent.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29962. Bought.

**36454. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '08.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a flying hawk with an *ankh*- and *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light-green, turning white.

TECHNIQUE: cutting and modelling good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29955. Bought.

- 36455. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate X.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with the title *Ankh Heru zt.* *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, turning brown and white in thin places.

TECHNIQUE: coarsish work.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36456. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion pouncing upon a lioness (?). *Back*, prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

PASTE: blue, of a medium colour.

TECHNIQUE: cutting and modelling good.

PRESERVATION: slightly worn.

- 36457. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate IX.—Zagazig.

DESCRIPTION: Inscribed on the base with a figure of the infant Horus: a *neb*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: cutting good, modelling fair; legs cut through width.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36458. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of Harpocrates sitting in a boat with a winged uraeus in front. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-sixth Dynasty (?).

GLAZE: green (?), turned yellow and cracked.

TECHNIQUE: delicate modelling and cutting; legs cut through the width.

PRESERVATION: good.



**36459. Scarab-shaped Seal.**—Black Steatite.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate IX.

DESCRIPTION: Inscribed on the base with three figures of deities: a *mer*-sign below.  
*Back*, Shesha type.

DATE: Nineteenth Dynasty.

TECHNIQUE: coarsely cut.

PRESERVATION: very much worn on both sides.

**36460. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower. *Back*, prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: green, turned brown.

TECHNIQUE: cutting and modelling poor.

PRESERVATION: good.

**36461. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra: before him are hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: cutting and modelling rough.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 27564.

**36462. Scarab-shaped Seal.**—Violet glass.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '012.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a bull (?) with a disc above it and an uraeus in front. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth or Twenty-sixth Dynasty.

GLASS: violet, and turning white on surface.

TECHNIQUE: coarsely cut back, but seal well cut.

PRESERVATION: chipped.

- 36463. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a fish between a *nefer*- and an *ankh*-sign. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine colour and quality (brown on back).

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

BIBL: *Journal d'entr e du Mus e*, No. 29963. Bought.

- 36464. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XVI.

DATE: Early Eighteenth Dynasty.

GLAZE: light green, of fine quality.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

- 36465. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate XI.—Tell el Yahudiyeh.

DESCRIPTION: Inscribed on the base with the signs *ankh* and *nefer*, with a loop pattern around them. *Back*, plain, as No. 36702, Plate XIX.

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

BIBL: *Journal d'entr e du Mus e*, No. 27714.

- 36466. Scarab-shaped Seal.**—Pottery.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *mart Amen nea scud*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark indigo-blue.

TECHNIQUE: modelling and cutting very good, legs pierced through whole width.

PRESERVATION: chipped.

BIBL: *Journal d'entr e du Mus e*, No. 29940. Bought in Upper Egypt.

**36467. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs between two coils in ovals. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, gone white, of fine quality.

TECHNIQUE: fine modelling and back.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29958. Bought.

**36468. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turning brown, polished on back.

TECHNIQUE: fair cutting and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29944. Bought in Upper Egypt.

**36469. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device consisting of interwoven coils. *Back*, prothorax indicated as No. 36947.

DATE: Twelfth Dynasty.

GLAZE: light blue glaze.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY in 1882.

**36470. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing upon a *dad*-sign. In front of the hawk is an uraeus, and on either side of the *dad* an *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light creamy green on back; light blue green on face.

TECHNIQUE: exquisite modelling and cutting, legs pierced through width.

PRESERVATION: perfect.

- 36471. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a goat between two cobras.  
*Back*, see Plate XX.

DATE: Hyksos Period.

GLAZE: green, turned brown, but nearly all rubbed off.

TECHNIQUE: work bold and coarse.

PRESERVATION: chipped at head.

- 36472. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '018. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a man standing with cobras on either side of him. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, going brown on back.

TECHNIQUE: coarse work.

PRESERVATION: slightly chipped.

- 36473. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '017. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion between two urai.  
*Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull blue-green, worn on back.

TECHNIQUE: work bold, but coarse.

PRESERVATION: perfect.

- 36474. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion trampling on a fallen man: in the field are hieroglyphs. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone a whity-brown.

TECHNIQUE: cutting bold and good.

PRESERVATION: good.

**36475. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figures of a lion, a crocodile, and a cobra. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: work bold, but rather coarse.

PRESERVATION: perfect.

**36476. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a hawk-headed deity and a man with arm upraised; above and below are *neb*-signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, worn on back and slightly nacreous.

TECHNIQUE: cutting coarse.

PRESERVATION: good.

**36477. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·016. Height, 0 m ·01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a man with a uraeus on his forehead, standing before a crocodile-headed deity who holds a sceptre. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: green.

TECHNIQUE: bold and good cutting.

PRESERVATION: perfect.

BIBL.: MASPERO, *Stip. Cut.*, No. 3802.

**36478. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·022. Width, 0 m ·015. Height, 0 m ·01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a beetle between two cobras; a crocodile below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone brown and slightly nacreous.

TECHNIQUE: cutting coarse.

PRESERVATION: perfect.

- 36479. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '027. Width, 0 m '019. Height, 0 m '011.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a man kneeling and holding in his left hand a lotus flower; on either side of him are cobras, and below is a crocodile. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull green.

TECHNIQUE: coarse work.

PRESERVATION: perfect.

- 36480. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figures of a lion and a crocodile (*cf.* No. 36769). *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: coarse work.

PRESERVATION: perfect.

- 36481. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with figures of two lions couchant back to back. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Hyksos Period (?).

GLAZE: green, gone grey.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: good.

- 36482. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '016. Height, 0 m '01.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Middle Eighteenth Dynasty (?).

GLAZE: green.

TECHNIQUE: coarse work.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

16

**36483. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone yellow-brown, worn off at back.

TECHNIQUE: cutting fair, legs pierced right through.

PRESERVATION: edges chipped.

**36484. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, crackled.

TECHNIQUE: good cutting and back.

PRESERVATION: chipped round edges.

**36485. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of very fine quality.

TECHNIQUE: cutting and modelling excellent.

PRESERVATION: excellent.

**36486. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·006.—Plate IX.—Sakkarah.

DESCRIPTION: Inscribed on the base with a figure of Set seated on a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: blue, gone white, and crackled.

TECHNIQUE: cutting fair, modelling good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 22104.

- 36487. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone white.

TECHNIQUE: cutting good, modelling fair; legs deeply cut.

PRESERVATION: chipped at edges.

BIBL.: MASPERO, *Slip Cut.*, No. 3822. PETRIE, *Hist. Scarabs*, No. 730.

- 36488. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '025. Width, 0 m '019. Height, 0 m '014.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty or later.

GLAZE: green-blue.

TECHNIQUE: coarse work.

PRESERVATION: good.

- 36489. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate VIII.

DESCRIPTION: On the base is a kneeling figure with arms upraised (in relief). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: the hieroglyphs are in relief and well executed.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 4508.

- 36490. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '013.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, see Plate XXI. Traces of gold foil in cutting.

DATE: Nineteenth or Twentieth Dynasty.

TECHNIQUE: well modelled and cut.

PRESERVATION: chipped on edge.

BIBL.: *Journal d'entrée du Musée*, No. 5361. Collection Hüber.



- 36491. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·008.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra, "King of the Gods," and a hieroglyphic legend similar to that of No. 36399. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

- 36492. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a griffon with a disc above it. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Twenty-sixth Dynasty.

GLAZE: dull light green.

TECHNIQUE: cutting and modelling good.

PRESERVATION: perfect.

- 36493. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes. *Back*, rounded prothorax and elytra marked.

DATE: Eighteenth Dynasty.

GLAZE: green, turning yellowish.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: good.

- 36494. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·012. Height, 0 m ·008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case. Set in a silver fundu (corroded).

DATE: Nineteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: cutting good.

PRESERVATION: good.

- 36495. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed with the name Men (? Amen) between two *nwb*-signs. *Back*, worn and flaked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: fair cutting and modelling.

PRESERVATION: worn on back and flaked.

- 36496. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ra-nwb-ha* (*cf.* Nos. 37081, 36496, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of medium colour and good quality.

TECHNIQUE: cutting coarse, and modelling good.

PRESERVATION: perfect.

- 36497. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ra-nwb-ha* (*cf.* Nos. 36496, 36761, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green, crackled.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: perfect.

- 36498. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ra-nwb-ha* (*cf.* Nos. 37081, 36496, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dullish green glaze of good quality.

TECHNIQUE: back finely modelled and cutting fair.

PRESERVATION: perfect.

- 36499. Scarab-Shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ia-ncb-hu* (cf. Nos. 36496, 36497, etc.). *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green, gone brown in thin parts.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect.

- 36500. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate XIV.—Abydos.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty (?).

GLAZE: light blue.

TECHNIQUE: coarse work.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 22068.

- 36501. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '014. Height, 0 m '01.—Plate VIII.

DESCRIPTION: Inscribed with signs reading *men* with two circular signs and two strokes below (? blundered for Amen-ra): at the sides two *ncb*-signs. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Twentieth Dynasty or later.

GLAZE: blue, of medium colour.

TECHNIQUE: coarse work and modelling.

PRESERVATION: perfect.

- 36502. Scarab-Shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen-ra. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: rich blue glaze of exquisite quality.

TECHNIQUE: good cutting and modelling.

PRESERVATION: perfect.

- 36503. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '006. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, turning green, of medium quality.

TECHNIQUE: medium work.

PRESERVATION: perfect.

- 36504. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Eighteenth Dynasty or later.

GLAZE: blue glazed pottery, going green.

TECHNIQUE: modelling of back good, cutting poor.

PRESERVATION: chipped on edge.

- 36505. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of the god Set, with a winged uraeus over his back. *Back*, rounded prothorax and elytra marked.

DATE: Early or Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: cutting good, modelling fair.

PRESERVATION: perfect.

- 36506. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between an *wab* and a *neb*-sign. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: green, turned brownish-yellow and crackled.

TECHNIQUE: cutting and modelling medium.

PRESERVATION: perfect.

- 36507. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '004.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a hare. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: cutting coarse.

PRESERVATION: good.

- 36508. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with the legend *kha neferu*. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fair cutting.

PRESERVATION: good.

- 36509. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a hare with a *ra*-sign above. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale yellow.

TECHNIQUE: cutting fair.

PRESERVATION: flaked at back.

- 36510. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '016. Height, 0 m '01.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king wearing his war helmet standing before Ra. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: coarsish work and modelling.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 29987 (Upper Egypt).

- 36511. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, without prothorax or elytra marked.

DATE: Eighteenth Dynasty (?).

PASTE: dull indigo-blue.

TECHNIQUE: modelling and cutting fair, legs deeply cut.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 29951. Bought.

- 36512. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '14. Width, 0 m '01. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with the legend *asha-neferui*. *Back*, without elytra or prothorax marked, as No. 36244 (Plate XIX).

DATE: Nineteenth Dynasty.

GLAZE: light blue, going brown on back.

TECHNIQUE: coarsish work and cutting.

PRESERVATION: perfect.

- 36513. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed on the base with the name of the *hmt-sten* Sat-ah (?). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: modelling and cutting good, legs deep cut.

PRESERVATION: edges slightly chipped.

- 36514. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Ptah, with a *neb*-sign to the left, and a feather and *neb*-sign to the right; encircling the whole is a rope border. *Back*, see Plate XX.

DATE: Nineteenth Dynasty or later.

GLAZE: dull green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

*Catal. du Musée*, n. 63001.

17

- 36515. Scarab-shaped Seal.**—Grey Steatite.—Length, 0 m '024. Width, 0 m '016. Height, 0 m '013.—Plate XVII.

DESCRIPTION: Inscribed on the base with the cartouche of Ne-maat-Ra. *Back*, only roughed out, much worn.

DATE: Twelfth Dynasty.

TECHNIQUE: back only roughed out.

PRESERVATION: much worn.

- 36516. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a man with left arm upraised before a hawk-headed deity: above the figures are two cobras. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green.

TECHNIQUE: modelling of back fair, cutting coarse but bold.

PRESERVATION: slightly worn on back.

- 36517. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen-ra. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light dull yellow.

TECHNIQUE: cutting and modelling coarse.

PRESERVATION: good.

- 36518. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '004.—Plate VIII.

DESCRIPTION: Inscribed on the base with a *men*-sign (? for Amen). *Back*, see Plate VIII.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, of good quality.

TECHNIQUE: cutting very coarse.

PRESERVATION: slightly chipped.

- 36519. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '004.—Plate XII.

DESCRIPTION: Inscribed on the base with cross lines. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue, of medium colour and good quality.

TECHNIQUE: coarse work.

PRESERVATION: good.

- 36520. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '007. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, of good quality.

TECHNIQUE: very coarse work.

PRESERVATION: chipped on edges.

- 36521. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Eighteenth Dynasty or later.

GLAZE: light blue-green.

TECHNIQUE: medium.

PRESERVATION: head of beetle chipped.

- 36522. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a flying hawk, with a *ra*-sign in front. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: light blue-grey.

TECHNIQUE: cutting coarse.

PRESERVATION: good.



**36523. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a lion, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull light green.

TECHNIQUE: modelling fine and cutting good.

PRESERVATION: perfect.

**36524. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '008.—Plate VI.—Thebes.

DESCRIPTION: Inscribed on the base with the name Uaz-kheper-Ra and a fish below. *Back*, see Plate XXII.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of good quality.

TECHNIQUE: cutting and modelling very fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entré du Musé*, No. 25827.

**36525. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turning brown on back.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

**36526. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx, with hieroglyphic signs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: good.

- 36527. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: modelling good, cutting medium.

PRESERVATION: perfect.

- 36528. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend (?) of doubtful meaning (*cf.* No. 36579). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: pale green.

TECHNIQUE: modelling and cutting fair, legs cut through whole width.

PRESERVATION: side chipped.

- 36529. Scarab-shaped Seal.**—Black Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a man standing, with the left arm thrust forward and the right by his side. Hieroglyphic signs in the field. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: green, turned brown in parts.

TECHNIQUE: cutting and modelling good.

PRESERVATION: perfect.

- 36530. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '005.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a man with a cobra in front of him (*cf.* No. 36738). *Back*, prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: green.

TECHNIQUE: coarse.

PRESERVATION: back slightly chipped.

**36531. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '011. Height, 0 m '011.—Plate VII.—Abydos.

DESCRIPTION: Inscribed on the base with a figure of a human head above a crocodile. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone a yellow-brown.

TECHNIQUE: modelling good, cutting medium.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21919.

**36532. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '027. Width, 0 m '012. Height, 0 m '012.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a man (?) kneeling before a lion, with a crocodile below. *Back*, see Plate XX.

DATE: Hyksos Period.

GLAZE: green, turned brown.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

**36533. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs in an oval, around which is a twisted rope pattern. *Back*, see Plate XX.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: cutting and modelling fine.

PRESERVATION: back slightly worn.

**36534. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a king with arms upraised before a crocodile. *Back*, see Plate VII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36535. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '013. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XIV.

DATE: Early Eighteenth Dynasty.

GLAZE: light green, of very fine quality.

TECHNIQUE: modelling good, cutting bold.

PRESERVATION: perfect.

- 36536. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus surrounded by a rope-pattern border. *Back*, see Plate XV.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark blue-green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36537. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate XII.

DESCRIPTION: Inscribed on the base with a twisted rope pattern. *Back*, prothorax indicated as No. 37179.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: modelling and cutting fine.

PRESERVATION: chipped.

- 36538. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Twelfth—Seventeenth Dynasty.

GLAZE: brilliant light blue.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

**36539. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '015. Height, 0 m '01.—Plate XI.—Drah abu'l Negga.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged: set in a silver funda. *Back*, covered with a sheet of gold foil.

DATE: Hyksos Period.

GLAZE: dull blue, of good quality.

TECHNIQUE: cutting very fine.

PRESERVATION: good.

BIBL: *Journal d'entré du Musée*, No. 21398. Found in a tomb at Drah Abu'l Negga together with Nos. 36649 and 37097.

**36540. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged: set in a gold funda which covers half of back. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

GLAZE: green, turned brown on back.

TECHNIQUE: fair.

PRESERVATION: back worn.

**36541. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with a rope-pattern design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull green, turning brown.

TECHNIQUE: cutting coarse.

PRESERVATION: good.

**36542. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '011. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XIII.

DATE: Early Eighteenth Dynasty.

GLAZE: brilliant blue.

TECHNIQUE: cutting and modelling very good.

PRESERVATION: perfect.

- 36543. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with a decorative device. *Back*, prothorax indicated (see Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality (crackled).

TECHNIQUE: cutting and modelling exquisite.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36544. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, turning brown on back.

TECHNIQUE: cutting and modelling fair.

PRESERVATION: perfect.

- 36545. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '017. Height, 0 m '01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XXI.

DATE: Hyksos Period, or Early Eighteenth Dynasty.

GLAZE: green, turning brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36546. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '011.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, turned white in thin parts.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

18

**36547. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, gone white on back.

TECHNIQUE: coarse modelling, cutting medium.

PRESERVATION: chipped edges.

**36548. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, nearly all worn off.

TECHNIQUE: coarsish.

PRESERVATION: good.

**36549. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, formless and worn.

DATE: Hyksos Period.

GLAZE: green (?).

TECHNIQUE: back formless and details worn away, cutting fair and bold.

PRESERVATION: worn on back.

**36550. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: modelling and cutting fair.

PRESERVATION: head of beetle chipped.

- 36551. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green, nearly all worn off.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: perfect.

- 36552. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs Ra-nefer within a cartouche: a continuous loop-pattern border around it. *Back*, see Plate XVI.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, of very fine quality.

TECHNIQUE: modelling and cutting very fine, legs deep sunk.

PRESERVATION: perfect.

- 36553. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with a design representing three coils of rope. *Back*, prothorax and elytra marked.

DATE: Early or Middle Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36554. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '01.—Plate XIII.

DESCRIPTION: Inscribed on the base with a series of three coils within a rope-pattern border. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: green, turned white in thin parts.

TECHNIQUE: modelling of back good, cutting poor.

PRESERVATION: perfect.



**36555. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling and cutting good.

PRESERVATION: edges chipped.

**36556. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·013. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* No. 36750). *Back*, prothorax indicated, as No. 37132.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling good, cutting fine.

PRESERVATION: perfect.

**36557. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·011. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: greeny-blue, of good quality.

TECHNIQUE: cutting and modelling good.

PRESERVATION: perfect.

**36558. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt: above it are two hawks with an *ankh*-sign between. *Back*, Shesha type.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, gone brown on back.

TECHNIQUE: modelling medium, cutting good and bold.

PRESERVATION: perfect.

- 36559. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .02. Width, 0 m .013. Height, 0 m .009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 37132.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, turned brown on back.

TECHNIQUE: good.

PRESERVATION: edge chipped.

- 36560. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .009. Height, 0 m .006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (compare Nos. 36377 and 36378). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: back very fine, cutting poor.

PRESERVATION: slightly chipped on edge.

- 36561. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .009. Height, 0 m .007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XXI.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, turning white and rubbed off on back.

TECHNIQUE: delicate modelling and cutting.

PRESERVATION: edges chipped.

- 36562. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .016. Width, 0 m .011. Height, 0 m .008.—Plate XIII.

DESCRIPTION: Inscribed on the base with ornamental designs symmetrically arranged. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting good and deep.

PRESERVATION: perfect.

- 36563. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

GLAZE: green, turned brown.

TECHNIQUE: modelling of back coarse, cutting fair.

PRESERVATION: chipped on head.

- 36564. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36565. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·014. Height, 0 m ·009.—Plate XI.—Abydos.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt, and a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, turning brown, and crackled.

TECHNIQUE: modelling good, cutting very fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 22069.

- 36566. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·023. Width, 0 m ·017. Height, 0 m ·012.—Plate XVII.

DESCRIPTION: Inscribed on the base with the name of Amen-Ra, and two *neb*-signs below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36567. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate XII.

DESCRIPTION: Inscribed on the base with coil-pattern decoration. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: light blue.

TECHNIQUE: back finely modelled, cutting coarse.

PRESERVATION: perfect.

- 36568. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·013. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* No. 36869). *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green (crackled), and going brown on back.

TECHNIQUE: coarse.

PRESERVATION: chipped on back.

- 36569. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Twelfth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fine cutting.

PRESERVATION: back much worn and chipped.

- 36570. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twentieth Dynasty or later.

GLAZE: greeny-blue, of medium colour and quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

**36571. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·00(?).—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs, and a loop pattern.  
*Back*: flaked away.

DATE: Twelfth—Seventeenth Dynasty.

GLAZE: green, turned a yellow-brown.

TECHNIQUE: poor.

PRESERVATION: chipped on edges and back flaked away.

**36572. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with a coil and a *neb*-sign. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull blue-green.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: perfect.

**36573. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·017. Width, 0 m ·013. Height, 0 m ·009.—Plate XII.

DESCRIPTION: Inscribed on the base with a *nezem*-sign between two eyes. *Back*, rounded prothorax and elytra marked. Fragment of string in piercing.

DATE: Nineteenth Dynasty or later.

GLAZE: pea-green, of good quality.

TECHNIQUE: modelling medium, cutting fair.

PRESERVATION: good.

**36574. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: coarse.

PRESERVATION: much worn.

BIBL.: *Journal d'entrée du Musée*, No. 29943. Bought.

- 36575. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty (?)

GLAZE: green, turned brown.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36576. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ptah, with a hieroglyphic sign in front of him. *Back*, see Plate IX.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, of fine quality and worn on back.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: good.

- 36577. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend of doubtful meaning. *Back*, with prothorax indicated but no elytra marked.

DATE: Middle or Late Eighteenth Dynasty.

GLAZE: blue, of good quality.

TECHNIQUE: excellent.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 29994. Upper Egypt.

- 36578. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·014. Height, 0 m ·007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: good.

*Catal. du Musée*, n. 36001.

19

**36579. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend (?) of doubtful meaning (*cf.* No. 36528). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull green.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: good.

**36580. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty or later.

GLAZE: pale blue, of very fine quality, gone pale yellow in thick parts.

TECHNIQUE: excellent.

PRESERVATION: perfect.

**36581. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed sphinx with wings. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: modelling lumpy, cutting coarse.

PRESERVATION: perfect.

**36582. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: modelling good, cutting fine; legs deeply cut.

PRESERVATION: perfect.

- 36583. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '00(?).—Plate XIII.—Khataneh.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, flaked.

DATE: Hyksos Period.

GLAZE: blue, turned white.

TECHNIQUE: fine cutting and back flaked.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 26683.

- 36584. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: On the base a necklace is figured, with the name of Amen-ra above it (compare No. 36643). *Back*, rounded prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: dull light pea-green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36585. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, see Plate XXI.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, of fine quality.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

- 36586. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: rich blue, of good quality.

TECHNIQUE: modelling fine and cutting good.

PRESERVATION: perfect.



- 36587. Scarab-shaped Seal**—Steatite, glazed.—Length, 0 m '029. Width, 0 m '021. Height, 0 m '016.—Plate IX.

DESCRIPTION: Inscribed on the base with a lotus or papyrus flower in the centre, with two seated figures of men on either side and a *nub*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown on back.

TECHNIQUE: coarse, legs deeply cut.

PRESERVATION: slightly chipped.

- 36588. Scarab-shaped Seal**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with coil pattern decoration. *Back*, Shesha type.

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: brilliant blue, glaze worn off on back.

TECHNIQUE: fair.

PRESERVATION: much worn on back.

- 36589. Scarab-shaped Seal**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with two oval devices and two drooping flower buds. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dullish green, worn off on back.

TECHNIQUE: modelling good, and cutting good and bold.

PRESERVATION: perfect.

- 36590. Scarab-shaped Seal**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate XI.—Abydos.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Hyksos Period.

GLAZE: green.

TECHNIQUE: modelling good, cutting delicate.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 30262.

- 36591. Scarab-shaped Seal.**—Green slate.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·008.—Plate VI.

DESCRIPTION: Inscribed on the base with the name of Amen. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: perfect.

- 36592. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·011.—Plate XI.

DESCRIPTION: Inscribed on the base with a rope pattern and two sacred eyes (*cf.* No. 36593). *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue, of fine quality.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: chipped on edges.

- 36593. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·004.—Plate XI.

DESCRIPTION: Inscribed on the base with a double coil and two eyes (*cf.* No. 36592). *Back*, see Plate XXI.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: excellent.

PRESERVATION: perfect.

- 36594. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a horse and hieroglyphic signs within a rope-pattern border. *Back*, see Plate XIV.

DATE: Nineteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: coarse.

PRESERVATION: good.

**36595. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a palm tree, up which two monkeys are climbing (*cf.* Nos. 36422, 36640). *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone a whity-yellow.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

**36596. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·008.—Plate V.—Sheikh abd el Kurneh.

DESCRIPTION: Inscribed with the name of Nefer-ra. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-fourth Dynasty.

GLAZE: rich deep blue, of fine colour and quality.

TECHNIQUE: moulded back and very fine cutting.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25716. Found in a tomb at Sheikh Abd el Kurneh together with Nos. 36001, 36002, 36293. PETRIE, *Hist. Scarabs*, No. 1836.

**36597. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·016. Height, 0 m ·01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked. Set in a gold fundu.

DATE: Hyksos Period.

GLAZE: green, of fine quality.

TECHNIQUE: modelling and cutting very fine and bold.

PRESERVATION: perfect.

**36598. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with a standing figure of a woman, with twigs or branches on either side of her. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling very good, cutting excellent.

PRESERVATION: chipped at head.

- 36599. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx between two cobras. *Back*, rounded prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

- 36600. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a human-headed sphinx with a cobra above. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting deep and bold.

PRESERVATION: back flaked.

- 36601. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·014. Height, 0 m ·011.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a beetle, with two cobras facing one another above. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, nearly worn off, and nacreous on back.

TECHNIQUE: modelling and cutting coarse.

PRESERVATION: perfect.

- 36602. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·015. Height, 0 m ·008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XIV.

DATE: Nineteenth Dynasty (?).

GLAZE: light dull green.

TECHNIQUE: fair.

PRESERVATION: perfect.

**36603. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·023. Width, 0 m ·016. Height, 0 m ·01.—Plate XII.

DESCRIPTION: Inscribed on the base with a twisted rope pattern. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: blue-green, of fine quality.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: excellent.

**36604. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a king holding two cobras before him. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

**36606. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk between two cobras; a crocodile below and a *nefer*-sign to the left. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: green, gone yellowish and crackled.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: slightly chipped.

**36605. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity with a cobra in front. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull green, turning brown.

TECHNIQUE: modelling very coarse, cutting coarse.

PRESERVATION: perfect.

- 36607. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .017. Width, 0 m .013. Height, 0 m .008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: edges chipped.

BIBL.: *Journal d'entrée du Musée*, No. 29931. Bought.

- 36608. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .007.—Plate VI.—Mitraheny (1900).

DESCRIPTION: Inscribed on the base with the name (?) Se-nefer-Ra within a rope-pattern border. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twentieth Dynasty or later.

GLAZE: blue, gone white.

TECHNIQUE: modelling and cutting very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 34055.

- 36609. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .007. Height, 0 m .005.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *hes Khensu*. *Back*, rounded prothorax and elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: modelling and cutting good.

PRESERVATION: chipped on edges.

- 36610. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .011. Width, 0 m .008. Height, 0 m .006.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, see Plate XXII.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling and cutting good, legs deeply cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31293. Bought.

*Catal. du Musée*, n. 36001.

20

**36611. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate VI.—Abydos.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 37179.

DATE: Twentieth Dynasty or later.

GLAZE: light dull pea-green.

TECHNIQUE: modelling and cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29835. MASPERO, *Slip Cat.*, No. 6804.

**36612. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: bluey-green.

TECHNIQUE: modelling and cutting excellent, legs deeply cut.

PRESERVATION: perfect.

BIBL.: MASEPRO, *Slip Cat.*, No. 3097.

**36613. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: modelling excellent, cutting fair, legs deeply cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

**36614. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the back with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling and cutting very good, legs deeply cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882. MASPERO, *Slip Cat.*, No. 3097.

- 36615. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *Amen-ra ha ncu send*.  
*Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

PASTE: dull and opaque light blue.

TECHNIQUE: modelling very good, legs pierced through width.

PRESERVATION: chipped on head.

BIBL: *Journal d'entrée du Musée*, No. 29941.

- 36616. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.  
MASPERO, *Slip Cat.*, No. 3097.

- 36617. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III, and legend *scp-en-Ra*. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: brilliant sky-blue, going white in thin parts.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: perfect.

- 36618. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate VI.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case. Set in a silver fundu.

DATE: Nineteenth Dynasty.

GLAZE: dull blue-green.

TECHNIQUE: good, legs deeply cut.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 25198. MASPERO, *Slip Cat.*, No. 1698.



**36619. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (*cf.* No. 36624). *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, turned yellow-brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

**36620. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty (?).

GLAZE: blue-green.

TECHNIQUE: modelling and cutting fine.

PRESERVATION: perfect.

**36621. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (compare Nos. 36627 and 37114). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull blue, of good quality.

TECHNIQUE: good, legs pierced through width.

PRESERVATION: much chipped.

**36622. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: pale green.

TECHNIQUE: modelling good, cutting medium.

PRESERVATION: good.

- 36623. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .009. Height, 0 m .007.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *hes Khensu Us*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth—Twenty-first Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36624. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .016. Width, 0 m .011. Height, 0 m .008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (*cf.* No. 36619). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark blue, badly burnt.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36625. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .013. Width, 0 m .009. Height, 0 m .006.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

- 36626. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .009. Width, 0 m .006. Height, 0 m .005.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *hes Khensu*. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: medium.

PRESERVATION: back worn.

**36627. Scarab-shaped Seal.**—Black steatite.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (compare Nos. 36621 and 37114). *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: fair, legs pierced through width.

PRESERVATION: back much worn.

**36628. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling fine, cutting good, legs deeply cut.

PRESERVATION: perfect.

**36629. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *Amen-ra ha nen sen*. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: lightish green.

TECHNIQUE: modelling medium, cutting coarse; legs pierced through width.

PRESERVATION: chipped on one side.

**36630. Scarab-shaped seals.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, of medium quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36631. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the back with a hieroglyphic legend. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: green, gone yellow-white.

TECHNIQUE: good.

PRESERVATION: chipped at head.

- 36632. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fair.

PRESERVATION: chipped slightly.

- 36633. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36634. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '011.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes, with monkeys on either side of him (*cf.* Nos. 36698 and 37057). *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown and worn off back.

TECHNIQUE: medium.

PRESERVATION: slightly chipped.

**36635. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '033. Width, 0 m '022. Height, 0 m '014.—Plate IX.

DESCRIPTION: Inscribed on the base with a papyrus flower in the centre, with standing figures of Anubis on either side and a crocodile below. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: chipped.

**36636. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with figures of two lizards. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: dark blue, going green.

TECHNIQUE: coarse.

PRESERVATION: good.

**36637. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged between two oval devices. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling and cutting very good.

PRESERVATION: perfect.

**36638. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown, worn off back.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: worn on back.

- 36639. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '01.—Plate VII.—Tell el Yahudiyeh.

DESCRIPTION: Inscribed on the base with the figure of a lion trampling a fallen man. *Back*, see Plate VII.

DATE: Hyksos Period.

GLAZE: green, gone yellow-brown.

TECHNIQUE: modelling very fine, cutting very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entr e du Mus e*, No. 27718.

- 36640. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a palm tree, up which two monkeys are climbing (*cf.* Nos. 36595, 36422). *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: chipped on edge.

- 36641. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Maat: before her is a feather and on either side are *wjer*-signs. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: Light blue-green, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36642. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx, with hieroglyphic signs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone a brownly-white.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: perfect.

*Catal. du Mus e*, n. 36901.

21

**36643. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '005.—Plate VIII.

DESCRIPTION: On the base a necklace is figured, with the name of Amen-ra above it (compare No. 36584). *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: bright blue, worn on back to brown.

TECHNIQUE: modelling good, cutting very good.

PRESERVATION: slightly chipped on edge.

**36644. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra (?) standing upon a *neb*-sign; hieroglyphs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty (?).

GLAZE: blue-green, gone brown in parts.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: fair.

**36645. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '025. Width, 0 m '018. Height, 0 m '011.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt with uræi and hieroglyphic signs symmetrically arranged above. *Back*, see Plate XI.

DATE: Hyksos Period.

GLAZE: medium blue, of fine quality.

TECHNIQUE: modelling fine, cutting excellent.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 31978. Bought.

**36646. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '01.—Plate XV.

DESCRIPTION: Inscribed on the base with figures of three uræi crowned with feathers, and a *neb*-sign below them. *Back*, see Plate XV.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: medium blue.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 34268.

- 36647. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king seated on a throne and holding a lotus flower to his face. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: modelling of back very fine, cutting medium, legs pierced through width.

PRESERVATION: perfect.

- 36648. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '01.—Plate X.

DESCRIPTION: Inscribed on the base with a legend (?) of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fine modelling and cutting, legs pierced through width.

PRESERVATION: chipped.

- 36649. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '015. Height, 0 m '009.—Plate XI.—Drah abu'l Negga.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked. Set in a silver fundu.

DATE: Twelfth—Seventeenth Dynasty (?).

GLAZE: lightish blue.

TECHNIQUE: fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21397. Found in a tomb at Drah Abu'l Negga, together with Nos. 36539 and 37097.

- 36650. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '011.—Plate XI.—Aswân.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, see Plate XI.

DATE: Twelfth Dynasty.

GLAZE: fine blue, gone white on thin parts.

TECHNIQUE: very fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30373.



- 36651. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '016. Height, 0 m '01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XIII.

DATE: Early Eighteenth Dynasty.

GLAZE: medium green, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36652. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '023. Width, 0 m '016. Height, 0 m '011.—Plate XV.

DESCRIPTION: Inscribed on the base with an uræus and other hieroglyphic signs.

*Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: rich dark blue, of exquisite quality.

TECHNIQUE: exquisite modelling and cutting.

PRESERVATION: perfect.

- 36653. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '024. Width, 0 m '018. Height, 0 m '01.—Plate XIII.—Abydos.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax and elytra marked. Set in a gold fundus.

DATE: Thirteenth—Eighteenth Dynasty.

GLAZE: green, going brown, of poor quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 30258.

- 36654. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Un-nefer. *Back*, plain (see Plate XIX).

DATE: Twentieth Dynasty or later.

GLAZE: dull light pea-green.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36655. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '01.—Plate VIII.

DESCRIPTION: Inscribed with signs reading *men* (? for Amen). *Back*, see Plate XX.  
 DATE: Eighteenth Dynasty or later.  
 GLAZE: greeny-blue, going brown on back.  
 TECHNIQUE: very coarse.  
 PRESERVATION: chipped on edges.

- 36656. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XI.—Sakkara (1858).

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked. Set in a gold fundu.  
 DATE: Twelfth Dynasty.  
 GLAZE: dull blue.  
 TECHNIQUE: modelling good, cutting fair.  
 PRESERVATION: good.  
 BIBL.: *Journal d'entré du Musé*, No. 3064.

- 36657. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with the title *Sa Ra* and a *Ka*-sign within a rope-pattern border. *Back*, plain (see Plate XIX).  
 DATE: Twentieth Dynasty or later.  
 GLAZE: blue, gone grey, and rubbed off on back.  
 TECHNIQUE: modelling fair, cutting poor.  
 PRESERVATION: good.  
 BIBL.: MASPERO, *Slip Cat.*, No. 3809.

- 36658. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king seated on his throne. *Back*, prothorax and elytra marked, with a *V* on either wing-case.  
 DATE: Nineteenth Dynasty.  
 GLAZE: blue, of medium colour.  
 TECHNIQUE: medium.  
 PRESERVATION: perfect.  
 BIBL.: *Journal d'entré du Musé*, No. 25181. Given by M. CAREY, 1882.

**36659. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate XV.—Abydos.

DESCRIPTION: Inscribed on the base with figures of three uræi, with feathers upon their heads. *Back*, without prothorax or elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light blue.

TECHNIQUE: coarse.

PRESERVATION: perfect.

BIBL.: MASPERO, *Stip. Cat.* No. 3809, Abydos, 1379.

**36660. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with figures of three uræi, with feathers upon their heads. *Back*, without prothorax or elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue.

TECHNIQUE: coarse.

PRESERVATION: worn.

**36661. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of Sekhmet standing before an obelisk. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, of medium colour and cracked.

TECHNIQUE: coarse.

PRESERVATION: chipped.

**36662. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twentieth Dynasty or later.

GLAZE: blue, gone white.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

- 36663. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·024. Width, 0 m ·015. Height, 0 m ·009.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

- 36664. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light bluey-green.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36665. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·014. Height, 0 m ·009.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a hawk-headed sphinx, with a cobra behind it and a *nub*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone yellow-white.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36666. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: medium.

PRESERVATION: good.

- 36667. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a gazelle. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull green.

TECHNIQUE: modelling fair, cutting bold.

PRESERVATION: perfect.

- 36668. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '00(?)—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: modelling fine, cutting fair.

PRESERVATION: back nearly all flaked away.

- 36669. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk with outstretched wings and holding seals in its talons. *Back*, plain (see Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling fine, cutting coarse.

PRESERVATION: perfect.

- 36670. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk with outstretched wings and holding seals in its talons. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of very fine quality.

TECHNIQUE: modelling exquisite, cutting very fine.

PRESERVATION: perfect.

- 36671. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged, and a winged disc below. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

- 36672. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·004.—Plate VI.—Kurneh (1862).

DESCRIPTION: Inscribed on the base with the name Neb-kheper-Ra. *Back*, rounded prothorax and elytra marked.

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: blue, gone a nacreous white.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: good.

BIBL.: *Journal d'entré du Musée*, No. 20423. MASPERO, *Slip Cat.*, No. 3680, Abydos, 1393. PETRIE, *Hist. Scarabs*, No. 1340.

- 36673. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·009.—Plate XI.

DESCRIPTION: Inscribed on the base with a geometrical device, with papyrus flowers above and below. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling fair, cutting medium.

PRESERVATION: good.

- 36674. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·023. Width, 0 m ·017. Height, 0 m ·01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty or later.

GLAZE: blue, gone white.

TECHNIQUE: modelling and cutting coarse.

PRESERVATION: back flaked.

*Catal. du Musée*, n. 36001.

22

- 36675. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarsish, cutting fair.

PRESERVATION: edge chipped.

- 36676. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '024. Width, 0 m '018. Height, 0 m '01.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus and a *nefer*-sign. *Back*, plain (see Plate XIX).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36677. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a man. *Back*, see Plate XXII.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: dull green.

TECHNIQUE: modelling fair, cutting medium.

PRESERVATION: good.

- 36678. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VIII.—Abydos.

DESCRIPTION: Inscribed with the name of Amen-ra; a *neb*-sign beneath. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling medium, cutting fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25050.

- 36679. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra, with a *neb*-sign to the left. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 36680. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·00(?)—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-Ra, with a *mer*- and *neb*-sign beneath. *Back*, worn away.

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: green (?), gone grey-black.

TECHNIQUE: poor.

PRESERVATION: back worn away, chipped on back.

- 36681. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen-ra. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: brilliant light green, of excellent quality.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: good.

- 36682. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra (blundered) and an eye to the right. *Back*, see Plate XXI.

DATE: Nineteenth Dynasty or later.

GLAZE: green, gone brown.

TECHNIQUE: very rough.

PRESERVATION: back worn.



**36683. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·009.—Plate VIII.

DESCRIPTION : Inscribed with the name of Amen. *Back*, see Plate XX.

DATE : Nineteenth Dynasty.

GLAZE : dark green.

TECHNIQUE : modelling coarse (no legs indicated), cutting coarse.

PRESERVATION : perfect.

**36684. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate VIII.

DESCRIPTION : Inscribed on the base with the name of Amen. *Back*, rounded prothorax and elytra marked (see Plate XXII).

DATE : Late Eighteenth Dynasty.

GLAZE : light blue, of very good quality.

TECHNIQUE : modelling good, cutting poor.

PRESERVATION : perfect.

**36685. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate VIII.

DESCRIPTION : Inscribed with the name of Amen-ra between two *nb*-signs. *Back*, rounded prothorax and elytra marked.

DATE : Late Eighteenth Dynasty.

GLAZE : rich blue, of fine quality.

TECHNIQUE : very good.

PRESERVATION : perfect.

**36686. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·008.—Plate VIII.

DESCRIPTION : Inscribed with the name of Amen, with two semi-circles below. *Back*, prothorax and elytra marked.

DATE : Late Eighteenth Dynasty.

GLAZE : blue, of medium colour.

TECHNIQUE : medium.

PRESERVATION : perfect.

- 36687. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra, a *neb*-sign beneath. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: light green-blue.

TECHNIQUE: modelling excellent, cutting good.

PRESERVATION: chipped at head.

- 36688. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling coarse, cutting medium.

PRESERVATION: good.

- 36689. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen between two *neb*-signs and three strokes below the *n*. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: good.

- 36690. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with a rope-pattern design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull green.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36691. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate XV.

DESCRIPTION: Inscribed on the base with a figure of a winged uræus and hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: light blue-green, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36692. Scarab-shaped Seal.**—Black steatite.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·008.—Plate VIII.

DESCRIPTION: Inscribed with the name of the goddess Isis. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Twentieth Dynasty or later.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36693. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate VI.

DESCRIPTION: Inscribed on the base with the name Amenhetep(?). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green, of fine quality.

TECHNIQUE: very fine work.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip. Cat.*, No. 1695.

- 36694. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty(?).

GLAZE: green.

TECHNIQUE: modelling good, cutting fine.

PRESERVATION: head chipped.

- 36695. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: emerald-green, gone white in places.

TECHNIQUE: fair.

PRESERVATION: edge chipped.

- 36696. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '01.—Plate XIII.—Pyramids (1859).

DESCRIPTION: Inscribed on the base with an oval within a rope-pattern border. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty or later.

GLAZE: blue, gone a dull grey-brown.

TECHNIQUE: modelling good, cutting rough.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 3845.

- 36697. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III: to the left a sphinx with two feathers upon its head and above it a hawk with outspread wings. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling rough, cutting good.

PRESERVATION: perfect.

- 36698. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '029. Width, 0 m '022. Height, 0 m '012.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes, with monkeys on either side of him (*cf.* Nos. 36634 and 37057). *Back*, prothorax and elytra marked. Remains of bitumen on the scarab.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, of medium colour.

TECHNIQUE: coarse.

PRESERVATION: edges chipped.



- 36699. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '017. Height, 0 m '011.—Plate IX.

DESCRIPTION : Inscribed on the base with two cynocephalus apes standing between an obelisk : below is a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE : Nineteenth Dynasty.

GLAZE : bluish-green, gone white in places.

TECHNIQUE : modelling good, cutting rough, legs deeply cut.

PRESERVATION : perfect.

- 36700. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '024. Width, 0 m '017. Height, 0 m '01.—Plate XIII.

DESCRIPTION : Inscribed on the base with an ornamental design. *Back*, see Plate XX.

DATE : Nineteenth or Twentieth Dynasty.

GLAZE : blue, of poor quality.

TECHNIQUE : very rough.

PRESERVATION : good.

- 36701. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '026. Width, 0 m '018. Height, 0 m '009.—Plate VII.

DESCRIPTION : Inscribed on the base with the figure of a hawk-headed deity with left arm raised. Above is a disc with cobra, and in front of the figure is a cobra. *Back*, prothorax indicated, as No. 36709.

DATE : Nineteenth Dynasty.

GLAZE : greyish.

TECHNIQUE : fair, pottery of excellent quality.

PRESERVATION : perfect.

- 36702. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XI.

DESCRIPTION : Inscribed on the base with three concentric circles, and above and below hieroglyphic signs symmetrically arranged. *Back*, plain (Plate XIX).

DATE : Hyksos Period.

GLAZE : dull green, gone brown in places.

TECHNIQUE : medium.

PRESERVATION : perfect.



- 36703. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '009.—Plate XIV.

DESCRIPTION: Inscribed on the base with a *nefer*-sign within a border of concentric circles. *Back*, see Plate XIV.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36704. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 37179.

DATE: Hyksos Period.

GLAZE: blue-green, gone brown, and worn in places.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36705. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green, worn off on back, and gone brown in places.

TECHNIQUE: rough, but good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29960. Bought.

- 36706. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '025. Width, 0 m '018. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of an oryx, and beneath it a crocodile. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: medium blue, going green.

TECHNIQUE: fair.

PRESERVATION: edge chipped.

*Catal. du Musée*, n. 36001.

23

- 36707. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '027. Width, 0 m '019. Height, 0 m '011.—Plate IX.

DESCRIPTION : Inscribed on the base with a figure of Ra with a cobra behind him, and a *neb*-sign below. *Back*, prothorax indicated, (see Plate XIX).

DATE : Nineteenth or Twentieth Dynasty.

GLAZE : green, turned brownish-yellow.

TECHNIQUE : fair.

PRESERVATION : perfect.

- 36708. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '017. Height, 0 m '011.—Plate XVII.

DESCRIPTION : Inscribed on the base with a figure of Anubis and hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE : Nineteenth or Twentieth Dynasty.

GLAZE : light blue.

TECHNIQUE : modelling good, cutting bad, legs deeply cut.

PRESERVATION : perfect.

- 36709. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XI.

DESCRIPTION : Inscribed on the base with three papyrus flowers, and on either side a *nefer*-sign within an oval. *Back*, prothorax indicated (see Plate XIX).

DATE : Twelfth Dynasty.

GLAZE : light blue.

TECHNIQUE : excellent.

PRESERVATION : perfect.

- 36710. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '009.—Plate XV.

DESCRIPTION : Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE : Hyksos Period.

GLAZE : green, gone brown.

TECHNIQUE : modelling good, cutting excellent.

PRESERVATION : chipped at head.

- 36711. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two horizontal lines, with red crowns on either side. Above, between vertical lines, is the name of Ptah, and below are two winged urai with a *ra*-sign between. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: chipped on edge.

- 36712. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36713. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·021. Width, 0 m ·016. Height, 0 m ·011.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Late Eighteenth Dynasty or later (?).

GLAZE: dull pea-green.

TECHNIQUE: modelling very good, cutting fair, legs deeply cut.

PRESERVATION: chipped on edge.

- 36714. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·014. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a beetle with outspread wings: above it are two feathers and two flying hawks. *Back*, see Plate XXII.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: perfect.



- 36715. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate XIII.

DESCRIPTION : Inscribed on the base with an ornamental design and hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE : Early Eighteenth Dynasty.

GLAZE : blue, gone white.

TECHNIQUE : modelling good, cutting excellent.

PRESERVATION : back flaked and head chipped.

- 36716. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate XI.

DESCRIPTION : Inscribed on the base with uræi and hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked (see Plate XXI).

DATE : Hyksos Period.

GLAZE : green, gone white.

TECHNIQUE : modelling good, cutting bold and deep.

PRESERVATION : perfect.

- 36717. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·013. Height, 0 m ·008.—Plate XI.

DESCRIPTION : Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE : Hyksos Period.

GLAZE : dark blue-green.

TECHNIQUE : modelling good, cutting rough but bold.

PRESERVATION : back worn.

- 36718. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·006.—Plate XIII.

DESCRIPTION : Inscribed on the base with a design representing three coils of rope. *Back*, Shesha type.

DATE : Hyksos Period.

GLAZE : dark green, of fine quality.

TECHNIQUE : modelling fair, cutting fine.

PRESERVATION : perfect.

- 36719. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: exquisite.

PRESERVATION: perfect.

- 36720. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative coil pattern. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very fine.

PRESERVATION: perfect.

- 36721. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with a series of concentric circles. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: light blue, going white in places.

TECHNIQUE: coarse.

PRESERVATION: chipped on sides.

- 36722. Scarab-shaped Seal.**—Paste.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (Amenhetep III).

PASTE: light blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

**36723. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with a winged beetle, and below, hieroglyphic signs symmetrically arranged. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

**36724. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 36603.

DATE: Hyksos Period.

GLAZE: green, gone yellow.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

**36725. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *nefr*-sign surrounded by coils. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling fair, cutting good, legs deeply cut.

PRESERVATION: head chipped.

**36726. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Twelfth Dynasty.

GLAZE: dull green.

TECHNIQUE: very fine.

PRESERVATION: perfect.

- 36727. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a beetle with a cobra on either side. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

GLAZE: blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36728. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra holding an *was*-sceptre (*cf.* No. 36934). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 36729. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a crowned uraeus and hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: blue, gone white and worn off back.

TECHNIQUE: good.

PRESERVATION: worn on back.

- 36730. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·01. Height, 0 m ·00(?)—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very good.

PRESERVATION: back flaked and edge chipped.

**36731. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate VI.

DESCRIPTION: Inscribed with the name of *Kheper-en-ra* within an oval: above is a winged disc, and below, a *neb*-sign. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty or later.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: edges worn down.

**36732. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·009.—Plate XIV.—Sakkara.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21873.

**36733. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·008.—Plate XI.—Sakkara (1859).

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked.

DATE: Hyksos Period (?).

GLAZE: green, gone grey in places.

TECHNIQUE: fair.

PRESERVATION: much chipped.

BIBL.: *Journal d'entrée du Musée*, No. 4505.

**36734. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, without prothorax or elytra marked.

DATE: Twelfth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: head chipped.

- 36735. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Hyksos Period.

GLAZE: green, gone yellowish.

TECHNIQUE: modelling fair, cutting good and deep.

PRESERVATION: perfect.

- 36736. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king (?) standing before Ra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting very coarse.

PRESERVATION: perfect.

- 36737. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·013. Height, 0 m ·01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XIII.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling good, cutting medium.

PRESERVATION: perfect.

- 36738. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·023. Width, 0 m ·015. Height, 0 m ·01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity, holding in his hand a feather: before him is a cobra (*cf.* No. 36530). *Back*, see Plate XX.

DATE: Hyksos Period.

GLAZE: blue-green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

24

**36739. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs within a rope-pattern border. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling fine, cutting coarse.

PRESERVATION: head chipped.

**36740. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·009.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity with a cobra in front. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: worn on edges.

**36741. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with figures of an obelisk and a pyramid: on either side of the obelisk are seated figures of a hawk-headed deity, and from the top of the pyramid two uræi are suspended. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: coarse, legs deeply cut.

PRESERVATION: legs much chipped.

**36742. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·008.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium green, of fine quality.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: perfect.

- 36743. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed on the base with the name *Tahutimes kha neferu*. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: bluey-green, gone brown in thin places.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36744. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a seated man; a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very poor.

PRESERVATION: perfect.

- 36745. Scarab-shaped Seal.**—Paste.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate X.—Abydos.

DESCRIPTION: Inscribed with the titles *Neter nefer, neb tau*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light opaque blue, of fine quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 30354.

- 36746. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, gone a light brown.

TECHNIQUE: modelling fair, cutting excellent.

PRESERVATION: perfect.



- 36747. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: head chipped.

- 36748. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·009.—Plate VI.

DESCRIPTION: Inscribed on the base with the signs *Kheper-ra*. *Back*, plain (see Plate XIX).

DATE: Twentieth Dynasty or later.

GLAZE: light dull pea-green.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: edges chipped.

- 36749. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·02. Width, 0 m ·015. Height, 0 m ·009.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Amen standing between two figures of Ra (*cf.* No. 37307). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling poor, cutting good and deep.

PRESERVATION: back flaked.

- 36750. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* No. 36556). *Back*, prothorax indicated as No. 37107.

DATE: Twelfth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36751. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '015. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figures of a sphinx and a cynocephalus ape, with hieroglyphic signs in the field. *Back*, see Plate XX.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone whity-brown.

TECHNIQUE: modelling rough, cutting good.

PRESERVATION: edges chipped.

- 36752. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a horse and a *ankh*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting very coarse.

PRESERVATION: chipped.

- 36753. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk between two cobras; a crocodile below. *Back*, see Plate XXII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: good, legs deeply cut.

PRESERVATION: perfect.

- 36754. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a beetle between two cobras; a crocodile below. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown in parts.

TECHNIQUE: good.

PRESERVATION: perfect.

**36755. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '022. Width, 0 m '016. Height, 0 m '01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity standing before a crocodile. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone white in parts.

TECHNIQUE: medium.

PRESERVATION: perfect.

**36756. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '009.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a hawk-headed deity, with two cobras facing one another above him. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: modelling fair, cutting bold.

PRESERVATION: perfect.

**36757. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax indicated as No. 37179.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown in parts.

TECHNIQUE: good.

PRESERVATION: edge chipped.

**36758. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone a brownish-yellow.

TECHNIQUE: modelling fair, cutting very coarse.

PRESERVATION: perfect.

- 36759. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed with signs reading *men* (?blundered for Amen-ra), with *neb*-signs on either side. *Back*, see Plate XX.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: medium green.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

- 36760. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra (blundered), with a *neb*-sign to the left and an *nhb*-sign to the right. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: coarse.

PRESERVATION: back and head chipped.

- 36761. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs, reading *Ra-neh-ha* (cf. Nos. 37081, 36496, etc.). *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark blue-green (crackled).

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36762. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate X.

DESCRIPTION: Similar to No. 36761. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, of medium colour.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

**36763. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen, with a *setep*-sign below and a *neb*-sign to the left. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: rough.

PRESERVATION: edges chipped and back flaked.

**36764. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a hawk standing on a *neb*-sign; in front is an uraeus and at the back a feather. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light dull pea-green.

TECHNIQUE: good.

PRESERVATION: perfect.

**36765. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing upon a *neb*-sign. The hawk wears the crown of Lower Egypt; before it is a *hen*-sign and behind are two lotus buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

**36766. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate V.

DESCRIPTION: Inscribed on the base with the name of Amenhetep. *Back*, Shesha type.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of medium colour and fine quality.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36767. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ptah standing between two *nefer*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light dull pea-green.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: back flaked.

- 36768. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Twenty-sixth Dynasty (?).

GLAZE: light dull pea-green, going grey.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: back flaked.

- 36769. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a lion, with a crocodile behind it. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: good and bold.

PRESERVATION: perfect.

- 36770. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·01.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light dull-green.

TECHNIQUE: very coarse.

PRESERVATION: chipped edges.

*Catal. du Musée*, n. 36001.

25

- 36771. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a standing hawk-headed sphinx. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: perfect.

- 36772. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, see Plate XX.

DATE: Nineteenth or Twentieth Dynasty (?).

GLAZE: dark green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36773. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *nefer*-signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36774. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: very rough.

PRESERVATION: perfect.

- 36775. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .008. Width, 0 m .007. Height, 0 m .005.—Plate XVI.

DESCRIPTION: Inscribed on the base with a decorative design. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull violet-green.

TECHNIQUE: coarse.

PRESERVATION: slightly chipped.

- 36776. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .009. Height, 0 m .005.—Plate XVI.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light bluey-green.

TECHNIQUE: fair, circles drilled with a concentric drill.

PRESERVATION: perfect.

- 36777. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .00(?).—Plate VIII.

DESCRIPTION: Inscribed with the legend *Ptah-en-neb*. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light blue, going white.

TECHNIQUE: roughish.

PRESERVATION: back flaked away.

- 36778. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .016. Width, 0 m .012. Height, 0 m .007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx: before it is a *nfr*-sign, and over its back a flying cobra. *Back*, prothorax and elytra marked, with head as No. 36275 (Plate XX).

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: poor.

PRESERVATION: back flaked.



- 36779. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Late Eighteenth Dynasty.

GLAZE: fine blue.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

- 36780. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting very coarse.

PRESERVATION: perfect.

- 36781. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '008.—Plate IX.—Abydos.

DESCRIPTION: Inscribed on the base with a figure of Ptah standing before a *ded*-shaped altar. *Back*, see Plate XX.

DATE: Nineteenth Dynasty (Rameses II).

GLAZE: blue.

TECHNIQUE: modelling very good, cutting good, legs not indicated.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25828.

- 36782. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed on the base with the legend "Ptah of the gods." *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: rough.

PRESERVATION: good.

- 36783. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '011. Height, 0 m '08.—Plate XIII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs within a rope-pattern border. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: blue-green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: slightly chipped.

- 36784. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '08.—Plate VIII.

DESCRIPTION: Inscribed on the base with a *khprw*-sign with feathers on either side; above is a vulture with wings outspread. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: coarse, legs deeply cut.

PRESERVATION: perfect.

- 36785. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark blue-green, brown on bottom.

TECHNIQUE: modelling fair, cutting deep and bold.

PRESERVATION: perfect.

- 36786. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed on the base with a standing figure of a hawk; before it is a *wfrw*-sign, and to the left a lotus bud. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLAZE: fine blue.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: fair.

- 36787. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XIII.—Abydos.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: light green, gone white and grey.

TECHNIQUE: coarse.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21929.

- 36788. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a coil-pattern decoration. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: head broken.

- 36789. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative *ankh*-sign, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36790. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36791. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown in thin parts.

TECHNIQUE: good.

PRESERVATION: slightly worn and edge chipped.

- 36792. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·021. Width, 0 m ·014. Height, 0 m ·01.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XXI.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, thick on back.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 36793. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36794. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: modelling coarse, cutting with drill good.

PRESERVATION: perfect.

- 36795. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design (*cf.* No. 36861).

*Back*, see Plate XXI.

DATE: Nineteenth Dynasty.

GLAZE: dull pea-green.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: good.

- 36796. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '008.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative rope-pattern. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Hyksos Period.

GLAZE: dull blue, crackled.

TECHNIQUE: good.

PRESERVATION: head chipped away.

- 36797. Scarab-shaped Seal.**—Glass.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds.

*Back*, prothorax indicated but no elytra marked.

DATE: Late Eighteenth Dynasty.

GLASS: opaque, light blue.

TECHNIQUE: modelling coarsish, cutting scratchy.

PRESERVATION: back worn.

- 36798. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark blue-green.

TECHNIQUE: bold.

PRESERVATION: perfect.

- 36799. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: green, cracked.

TECHNIQUE: fair.

PRESERVATION: edges and back chipped.

- 36800. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with three double coils. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, turned white.

TECHNIQUE: fair, legs deeply cut.

PRESERVATION: perfect.

- 36801. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting bold.

PRESERVATION: good.

- 36802. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a human head, with long neck and feathers (?) on the head (*cf.* No. 36812). *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

26

- 36803. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: modelling fair, cutting with drill good.

PRESERVATION: back worn.

- 36804. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with a geometrical design. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36805. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with a geometrical design. *Back*, see Plate XX.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36806. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XII.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, plain, with legs indicated (see Plate XIX).

DATE: Middle Eighteenth Dynasty (?).

GLAZE: green, gone grey.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36807. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a series of coils symmetrically arranged.  
*Back*, Shesha type.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: blue, gone white.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36808. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36809. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '008.—Plate XII.—Zagazig (1882).

DESCRIPTION: Inscribed on the base with the figure of a vase from which two flowers are hanging; below is a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fine, cutting very good, legs deeply cut.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25198.

- 36810. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with a geometrical design (*cf.* No. 36811).  
*Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.



- 36811. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with a geometrical design. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36812. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a human head, with long neck and two feathers (?) on the head (*cf.* No. 36802). *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: light blue-green, gone white in places.

TECHNIQUE: coarse.

PRESERVATION: back worn.

- 36813. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: dark green, turning brown.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: edges chipped.

- 36814. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull green, turning brown.

TECHNIQUE: fair.

PRESERVATION: good.

- 36815. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .008. Height, 0 m .005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, worn down.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, going brown.

TECHNIQUE: good.

PRESERVATION: back worn.

- 36816. Scarab-shaped Seal.**—Paste.—Length, 0 m .011. Width, 0 m .008. Height, 0 m .006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light blue.

TECHNIQUE: fair.

PRESERVATION: back slightly chipped.

- 36817. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .009. Height, 0 m .006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Hyksos Period.

GLAZE: dull light blue.

TECHNIQUE: modelling good, cutting medium.

PRESERVATION: perfect.

- 36818. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .006.—Plate X.

DESCRIPTION: Inscribed on the base with a hawk's head surmounted by an uraeus and two feathers, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull light green.

TECHNIQUE: fine.

PRESERVATION: back slightly worn.

BIBL.: *Journal d'entrée du Musée*, No. 31293. Bought.

- 36819. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with a double coil and hieroglyphic signs.

*Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: very dark green and thick, but badly burnt.

TECHNIQUE: good.

PRESERVATION: fair.

- 36820. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with coil-pattern decoration. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling good, cutting good.

PRESERVATION: chipped on back.

- 36821. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·008. Height, 0 m ·005.—Plate X.

DESCRIPTION: Similar to No. 36836. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dullish blue, of fine quality.

TECHNIQUE: modelling fine, cutting fair.

PRESERVATION: good.

- 36822. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of uncertain meaning (*cf.* No. 37093). *Back*, prothorax and elytra marked.

DATE: Twenty-sixth Dynasty (?)

GLAZE: light blue-green.

TECHNIQUE: modelling poor, cutting good.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1881.

- 36823. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling poor, cutting good.

PRESERVATION: perfect.

- 36824. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36825. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a conventional lotus flower and *nefr*-signs on either side of it. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: fine.

PRESERVATION: perfect.

- 36826. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with a twisted rope-pattern decoration. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty.

GLAZE: blue.

TECHNIQUE: modelling and cutting fine.

PRESERVATION: chipped.

- 36827. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION : Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, Shesha type.

DATE : Twelfth Dynasty.

GLAZE : blue, of fine quality.

TECHNIQUE : good.

PRESERVATION : perfect.

- 36828. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION : Inscribed on the base with hieroglyphic (?) signs. *Back*, prothorax and elytra marked.

DATE : Late Eighteenth Dynasty.

GLAZE : dull violet blue.

TECHNIQUE : good.

PRESERVATION : perfect.

- 36829. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION : Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

GLAZE : fine green, turned brown in parts.

TECHNIQUE : modelling very delicate, cutting very good.

PRESERVATION : perfect.

- 36830. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '006. Height, 0 m '005.—Plate XII.

DESCRIPTION : Inscribed on the base with a conventional eye-sign between two *nebs*. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE : Middle Eighteenth Dynasty.

GLAZE : green.

TECHNIQUE : good.

PRESERVATION : perfect.

- 36831. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '004.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs, reading *Ra-de-ha*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: fair.

PRESERVATION: back chipped.

- 36832. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light green, turning brown.

TECHNIQUE: excellent.

PRESERVATION: perfect.

- 36833. Scarab-shaped Seal.**—Paste.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '07.—Plate XII.

DESCRIPTION: Inscribed on the base with three papyrus flowers. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light blue, of fine quality.

TECHNIQUE: medium.

PRESERVATION: perfect.

- 36834. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with three papyrus flowers. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: coarse.

PRESERVATION: back flaked.

*Catal. du Musée*, n. 38001.

27

- 36835. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of an uræus and a crown of Lower Egypt. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, of good quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36836. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a hawk's head, a *Ra*-sign above it and a *nub*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: rich blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36837. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum (*cf.* No. 36802, 36812). *Back*, prothorax indicated as No. 36947.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, turning brown.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36838. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate X.

DESCRIPTION: Inscribed on the base with the figure of a sistrum. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull green, turned grey.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 36839. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XIII.

DATE: Nineteenth Dynasty (?).

GLAZE: dark green, gone brown.

TECHNIQUE: rough.

PRESERVATION: chipped.

- 36840. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with a symmetrical geometric design. *Back*, see Plate XXI.

DATE: Twelfth Dynasty.

GLAZE: pale blue.

TECHNIQUE: fine.

PRESERVATION: slightly worn.

- 36841. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with human-headed handle and two uraei below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: coarse.

PRESERVATION: good.

- 36842. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower. *Back*, plain (see Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: medium.

PRESERVATION: chipped on edge.



- 36843. Scarab-shaped Seal.**—Paste.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *ha-neb*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light blue-grey.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: good.

- 36844. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: modelling very fine, cutting good.

PRESERVATION: perfect.

- 36845. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design (*cf.* No. 36814). *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36846. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·004.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going brown in places.

TECHNIQUE: modelling fine, cutting fair, legs deeply cut.

PRESERVATION: perfect.

- 36847. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with a double coil between two *ankh*-signs in ovals. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dull green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36848. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '008.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: rich olive-green.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

- 36849. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a papyrus flower and two buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36850. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with three papyrus flowers. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light green.

TECHNIQUE: modelling poor, cutting fair.

PRESERVATION: chipped at head.

- 36851. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds.

*Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: modelling good, cutting rough.

PRESERVATION: perfect.

- 36852. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with four uræi with feathers upon their heads. *Back*, see Plate XX.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, going brown in places.

TECHNIQUE: modelling fair, cutting medium.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29964. Bought.

- 36853. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with five uræi with discs upon their heads.

*Back*, Shesha type.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: medium.

PRESERVATION: perfect.

- 36854. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: dull green, going brown in places.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36855. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with a rope-pattern design with *nefer*-signs on either side. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: modelling good, cutting bold.

PRESERVATION: perfect.

- 36856. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate XVI.

DESCRIPTION: Inscribed on the base with a decorative device. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36857. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36858. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine blue-green.

TECHNIQUE: modelling medium, cutting poor.

PRESERVATION: perfect.

**36859. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: lightish green.

TECHNIQUE: modelling very delicate, cutting fair, legs deeply cut.

PRESERVATION: perfect.

**36860. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of medium colour.

TECHNIQUE: poor.

PRESERVATION: good.

**36861. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue-green, going brown.

TECHNIQUE: good.

PRESERVATION: head chipped.

**36862. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·005.—Plate X.

DESCRIPTION: Inscribed on the base with a lion's head, with a *ra*-sign and uræus above, and a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: good.

PRESERVATION: back chipped.

- 36863. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a hawk's(?) head with horns, a *ra*-sign above and a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone whitish-yellow and nacreous.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 36864. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, of very fine quality, but uneven and going white in places.

TECHNIQUE: modelling good, cutting very poor and scratchy.

PRESERVATION: good.

- 36865. Scarab-shaped Seal.**—Paste.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: dull grey-blue, of medium colour.

TECHNIQUE: modelling good, cutting fine.

PRESERVATION: perfect.

- 36866. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '006. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a human head, with long neck and feathers(?) on the head. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green, badly run.

TECHNIQUE: modelling medium, cutting coarse.

PRESERVATION: good.

*Catal. du Musée*, n. 36001.

28

**36867. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '011. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and Lower Egypt, with two uræi above. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: light green, rubbed off on back.

TECHNIQUE: modelling good, cutting very good.

PRESERVATION: chipped on edge.

**36868. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate XIII.

DESCRIPTION: Inscribed on the base with a decorative design composed of a series of concentric circles. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Hyksos Period.

GLAZE: dull dark-blue, of fine quality.

TECHNIQUE: modelling very good, cutting coarse.

PRESERVATION: perfect.

**36869. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated, as No. 37132.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, unevenly burnt.

TECHNIQUE: modelling very good, cutting fair.

PRESERVATION: perfect.

**36870. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with ornamental devices. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: Medium green, of fine quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 36871. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *ankh*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLAZE: light blue.

TECHNIQUE: modelling coarse, cutting medium.

PRESERVATION: fair.

- 36872. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown in places and cracked.

TECHNIQUE: modelling fair, cutting coarse, legs deeply cut.

PRESERVATION: perfect.

- 36873. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '009.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: dullish blue, going black-brown in places.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36874. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate XIII.—Abydos.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light green, of fine quality.

TECHNIQUE: modelling fine, cutting fair.

PRESERVATION: good.

BIBL: *Journal d'entrée du Musée*, No. 30260.



- 36875. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·009.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a cat, a fish and an eye (*cf.* Nos. 36884, 36978, 37143 and 37145.) *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of good quality.

TECHNIQUE: modelling good, cutting fair, legs deeply pierced.

PRESERVATION: perfect.

- 36876. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *amwkh les neter*. *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: blue.

TECHNIQUE: medium.

PRESERVATION: chipped on head.

- 36877. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *se-nza-khet* (*cf.* No. 36878). *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty or later.

GLAZE: blue, gone grey.

TECHNIQUE: fair.

PRESERVATION: slightly chipped on back.

- 36878. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *se-nza-khet* (*cf.* No. 36877). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty or later.

GLAZE: dull blue-green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36879. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *hes Kheusu ena hes*.  
*Back*, see Plate XXII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling excellent, cutting good.

PRESERVATION: perfect.

- 36880. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: light green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36881. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: light green-blue.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: back worn.

- 36882. Scarab-shaped Seal.**—Green jasper.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign, and a *neb*-sign below.  
*Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling roughish, cutting good.

PRESERVATION: perfect.

- 36883. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: fine dark green, unevenly burnt.

TECHNIQUE: modelling coarse, cutting rough.

PRESERVATION: perfect.

- 36884. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a cat, a fish, and an eye (*cf.* Nos. 36875, 36978, 37143, and 37145).

DATE: Late Eighteenth Dynasty.

GLAZE: dull light green-blue.

TECHNIQUE: modelling medium, cutting fair, legs deeply cut.

PRESERVATION: perfect.

- 36885. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull blue-green, of fine quality.

TECHNIQUE: modelling very good, cutting good, legs deeply cut.

PRESERVATION: perfect.

- 36886. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, coarse, going brown.

TECHNIQUE: very coarse.

PRESERVATION: head chipped.

- 36887. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: fair.

PRESERVATION: head chipped.

- 36888. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .017. Width, 0 m .012. Height, 0 m .008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: dull blue-green.

TECHNIQUE: modelling coarse, cutting very coarse, legs pierced through whole width.

PRESERVATION: perfect.

- 36889. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .018. Width, 0 m .013. Height, 0 m .008.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uraeus, an *ankh*-sign, and a branch of a shrub (?). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36890. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .014. Width, 0 m .012. Height, 0 m .008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 36709.

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLAZE: blue.

TECHNIQUE: modelling rough, cutting coarse.

PRESERVATION: good.

- 36891. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: blue, very brilliant and fine in quality.

TECHNIQUE: no detail on back, cutting rough.

PRESERVATION: perfect.

- 36892. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fair.

PRESERVATION: head chipped.

- 36893. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: dark blue, of fine quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 36894. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty.

GLAZE: fine light blue.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36895. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: brilliant sky-blue.

TECHNIQUE: good.

PRESERVATION: back and edge chipped.

- 36896. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate XII.

DESCRIPTION: Inscribed on the base with a double coil between two *nefer*-signs. *Back*, plain (see Plate XIX).

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36897. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer* and *ankh*. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: modelling medium, cutting poor.

PRESERVATION: perfect.

- 36898. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue.

TECHNIQUE: good.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

29

- 36899. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·01. Height, 0 m ·008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 37132

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: back chipped.

- 36900. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *Amakh, hes Amen*. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull grey-blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36901. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·006. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: poor.

PRESERVATION: good.

- 36902. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·07. Height, 0 m ·005.—Plate VIII.

DESCRIPTION: Inscribed with the signs *neb* and *men*. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: coarse.

PRESERVATION: fair.

- 36903. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .007. Height, 0 m .005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green, gone brownish-white

TECHNIQUE: coarse.

PRESERVATION: chipped on back.

- 36904. Scarab-shaped Seal.**—Paste.—Length, 0 m .027. Width, 0 m .019. Height, 0 m .013.—Plate IV.

DESCRIPTION: Inscribed on the base with the name and titles of the Vezir Ptahmes. *Back*, see Plate IV.

DATE: Middle Eighteenth Dynasty (Thothmes III).

PASTE: light blue, of good quality.

TECHNIQUE: exquisite.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 31008. Bought. NEWBERRY, *Scarabs*, Plate XXIX, 10.

- 36905. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .009. Width, 0 m .008. Height, 0 m .006.—Plate XVI.

DESCRIPTION: Inscribed on the base with the figure of a scarab between two *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: rough.

PRESERVATION: good.

- 36906. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .008. Width, 0 m .007. Height, 0 m .004.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going light brown.

TECHNIQUE: poor.

PRESERVATION: chipped on back and head.



- 36907. Scarab-shaped Seal.**—Steatite, glazed. Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: chipped on back.

- 36908. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling very good, cutting medium.

PRESERVATION: slightly chipped.

- 36909. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005. Plate VIII.

DESCRIPTION: Inscribed with a *men*-sign between four horizontal lines. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: coarse.

PRESERVATION: slightly chipped on head.

- 36910. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* No. 36911). *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark blue-green.

TECHNIQUE: modelling good, cutting bold.

PRESERVATION: perfect.

- 36911. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·006—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* No. 36910). *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: back flaked.

- 36912. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·019. Width, 0 m ·013. Height, 0 m ·01. Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: fair.

PRESERVATION: good.

- 36913. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with the figure of a man holding two gazelles. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: thin green, gone brown below.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36914. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·008. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *amakh, hes, Khcasu*. *Back*, see Plate XXII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light green.

TECHNIQUE: modelling excellent, cutting good, legs deeply cut.

PRESERVATION: perfect.

- 36915. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·008. Height, 0 m ·005.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36916. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue.

TECHNIQUE: rough.

PRESERVATION: good.

- 36917. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·004.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: very rough.

PRESERVATION: chipped on back.

- 36918. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with a *Nrith* (?) sign. *Back*, without prothorax or elytra marked (very rough).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark blue, gone violet.

TECHNIQUE: very coarse.

PRESERVATION: good.

- 36919. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate VII.

DESCRIPTION: Inscribed on the base with figures of two crocodiles. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue, gone greyish-white.

TECHNIQUE: modelling roughish, cutting fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36920. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '011.—Plate X.—Kurneh, 1862.

DESCRIPTION: Inscribed on the base *Ra neb tawi*. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: rough.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 20420. MASPERO, *Slip Cat.*, No. 3650. PETRIE, *Hist. Scarabs*, No. 153.

- 36921. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with the title *Sa Ra*, and a papyrus sign. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: medium blue.

TECHNIQUE: coarse.

PRESERVATION: back flaked.

BIBL.: MASPERO, *Slip Cat.*, No. 3825.

- 36922. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with a hornet-sign. *Back*, without prothorax or elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: green (?), gone black.

TECHNIQUE: modelling good, cutting roughish.

PRESERVATION: perfect.

- 36923. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·005.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs (*cf.* Nos. 37095, 37357).

*Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: greeny-blue.

TECHNIQUE: modelling very poor, cutting poor.

PRESERVATION: slightly chipped.

- 36924. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·012. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged (*cf.* Nos. 36675, 37369). *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: back chipped and flaked.

- 36925. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·007.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut?).

GLAZE: dark blue, of good quality.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: chipped at head.

- 36926. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light opaque blue-green.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36927. Scarab-shaped Seal.**—Paste.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·004.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer* and *ankh*. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

PASTE: dark opaque violet.

TECHNIQUE: fair.

PRESERVATION: good.

- 36928. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative *ankh*-sign. *Back*, rounded prothorax and elytra marked.

GLAZE: light opaque blue.

TECHNIQUE: modelling rough, cutting good.

PRESERVATION: perfect.

- 36929. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (Thothmes III).

GLAZE: green, of good quality.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 36930. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green, pale in places.

TECHNIQUE: coarse.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.  
*Catal. du Musée*, n. 36001.

30

- 36931. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *ankh*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: brilliant blue-green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36932. Scarab-shaped Seal.**—Black jasper.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.

- 36933. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx, with hieroglyphic signs in the field. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: poor.

PRESERVATION: chipped on back.

BIBL.: *Journal d'entrée du Musée*, No. 35172.

- 36934. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '009. Width, 0 m '014. Height, 0 m '009.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra holding an *uas*-sceptre (*cf.* No. 36728). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: light blue.

TECHNIQUE: poor.

PRESERVATION: slightly chipped.

BIBL.: *Journal d'entrée du Musée*, No. 35172.

- 36935. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .01. Height, 0 m .007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a man. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: medium blue.

TECHNIQUE: poor, legs pierced through width.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 35172.

- 36936. Scarab-shaped Seal.**—Emerald stone.—Length, 0 m .016. Width, 0 m .011. Height, 0 m .007.—Plate VI.—Gharaq.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period (?).

TECHNIQUE: fair.

PRESERVATION: fair.

BIBL.: *Journal d'entrée du Musée*, No. 34249.

- 36937. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .019. Width, 0 m .014. Height, 0 m .011.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Set. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: blue, of poor quality.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 36938. Scarab-shaped Seal.**—Steatite, glazed. Length, 0 m .012. Width, 0 m .009. Height, 0 m .006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going white.

TECHNIQUE: modelling medium, cutting poor.

PRESERVATION: good.



- 36939. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XV.

DESCRIPTION : Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE : Nineteenth Dynasty or later.

GLAZE : green, gone deep grey-black.

TECHNIQUE : fair.

PRESERVATION : chipped at head.

- 36940. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION : Inscribed on the base with the name *Neb-ded-Ra*, with a *neb*-sign below and a feather to the right. *Back*, Shesha type.

DATE : Middle Eighteenth Dynasty.

GLAZE : sky-blue, of very fine quality, worn at edges to brown.

TECHNIQUE : good.

PRESERVATION : perfect.

BIBL : MAR, *M.D.*, 32. PETRIE, *Hist. Scarabs*, No. 1215.

- 36941. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VII.

DESCRIPTION : Inscribed on the base with the figure of a hawk-headed sphinx with wings. *Back*, see Plate XXI.

DATE : Eighteenth Dynasty.

GLAZE : light blue, of fine colour.

TECHNIQUE : modelling medium, cutting bold.

PRESERVATION : chipped on back.

- 36942. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate VIII.

DESCRIPTION : Inscribed on the base with a figure of a hawk, with a *neb*-sign above. *Back*, rounded prothorax and elytra marked.

DATE : Early Eighteenth Dynasty (Hatshepsût).

GLAZE : sky-blue, of fine quality.

TECHNIQUE : good.

PRESERVATION : chipped on head.

- 36943. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .02. Width, 0 m .015. Height, 0 m .01.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing upon a *neb*-sign. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue, going white in places.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 36944. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .015. Width, 0 m .012. Height, 0 m .007.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing upon a *neb*-sign with an uraeus before it. *Back*, see Plate XXI.

DATE: Late Eighteenth Dynasty.

GLAZE: medium blue, of good quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36945. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .009. Height, 0 m .007.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing on a *neb*-sign. *Back*, see Plate XXI.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, of very good quality.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

- 36946. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .022. Width, 0 m .015. Height, 0 m .01.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uraeus and a *neb*-sign. *Back*, prothorax indicated as No. 36707.

DATE: Nineteenth Dynasty.

GLAZE: dark blue, of fine quality.

TECHNIQUE: modelling fair, cutting rough.

PRESERVATION: perfect.

- 36947. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an *ankh*-sign surrounded by a coil-pattern decoration. *Back*, prothorax indicated (see Plate XIX).

DATE: Twelfth Dynasty.

GLAZE: pale blue-green, gone white on back.

TECHNIQUE: excellent.

PRESERVATION: perfect.

- 36948. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull blackish-blue.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36949. Scarab-shaped Seal.**—Schist, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed on the base with figures of Amen and Ra. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: poor.

PRESERVATION: much chipped.

- 36950. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a canoe, in which are seated three deities. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: fine green, going white in thin places.

TECHNIQUE: modelling good, cutting excellent, legs deeply cut.

PRESERVATION: much chipped.

- 36951. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with hieroglyphic (?) signs within a rope-pattern border. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone a whity-green, of poor quality.

TECHNIQUE: poor.

PRESERVATION: chipped and badly preserved.

- 36952. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with an uraeus: before it, an *ankh*-sign, and below it, a *nub*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty or later.

GLAZE: deep sky-blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 36953. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '006. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 36954. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god [A]men-ra. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty or later.

GLAZE: fine blue, gone green on under surface.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36955. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain as No. 36244 (Plate XIX).

DATE: Nineteenth Dynasty or later.

GLAZE: bright blue-green, mostly rubbed off.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 36956. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with the name Aa-kheper-neb-Ra. *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty (?).

GLAZE: pale blue, of poor quality.

TECHNIQUE: poor.

PRESERVATION: chipped on back.

BIBL: *Journal d'entrée du Musée*, No. 25681.

- 36957. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '01. Height, 0 m '007.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated, as No. 37107.

DATE: Twelfth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling good, cutting coarsish.

PRESERVATION: back flaked.

- 36958. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphics symmetrically arranged. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling of back fair, cutting coarse.

PRESERVATION: slightly chipped.

- 36959. Scarab-shaped Seal.**—Steatite, unglazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XX.

DATE: Eighteenth Dynasty.

TECHNIQUE: modelling back unfinished, cutting fair.

PRESERVATION: chipped.

- 36960. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·019. Width, 0 m ·014. Height, 0 m ·009.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III, with a winged uræus to the left. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale green, of good quality.

TECHNIQUE: coarsish.

PRESERVATION: good.

- 36961. Scarab-shaped Seal.**—Paste.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra seated on a throne. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull violet indigo.

TECHNIQUE: modelling good, cutting fair, legs deeply cut.

PRESERVATION: perfect.

- 36962. Scarab-shaped Seal.**—Paste.—Length, 0 m ·011. Width, 0 m ·009. Height, 0 m ·005.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a flying hawk holding a seal in its talons. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull dark violet-indigo.

TECHNIQUE: fair.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

31

**36963. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a god (?) with a *nefer*-sign in front of him, and a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: pale blue, of poor quality.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

**36964. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a monkey and a *nefer*-sign. *Back*, prothorax indicated as No. 37107.

DATE: Nineteenth Dynasty (?).

GLAZE: pale dull green.

TECHNIQUE: modelling fair, cutting rough.

PRESERVATION: perfect.

**36965. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·005. Height, 0 m ·006.—Plate VI.

DESCRIPTION: Inscribed on the base with the name Aah-hetepu. *Back*, see Plate VI.

DATE: Early Eighteenth Dynasty (?).

GLAZE: blue, turned grey.

TECHNIQUE: coarse.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cut.*, No. 1694.

**36966. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a winged sphinx wearing the crown of Lower Egypt, and holding before it a feather. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: dullish pea-green, of good quality.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 36967. Scarab-shaped Seal.**—Pale amethyst.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '01.—Plate X.

DESCRIPTION: Inscribed on the base with a legend reading *Amen ha nen scnd*.  
*Back*, prothorax and elytra marked.

DATE: Nineteenth—Twenty-first Dynasty.

TECHNIQUE: fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30454. Bought.

- 36968. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax indicated as No. 37107.

DATE: Nineteenth Dynasty.

GLAZE: dull pea-green.

TECHNIQUE: fair.

PRESERVATION: back flaked.

- 36969. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue-green, turning white.

TECHNIQUE: medium.

PRESERVATION: chipped edge.

- 36970. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '008.—Plate VI.—Memphis.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: pale green, turned a yellowish-white.

TECHNIQUE: fair.

PRESERVATION: chipped on back.

BIBL.: MASPERO, *Slip Cat.*, No. 3817, ? 3800, Abydos, 1393. PETRIE, *Hist. Scarabs*, No. 1435.



- 36971. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '01.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull blue-green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: chipped on head.

- 36972. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with the name of Pe-de-ast. *Back*, see Plate XXII.

DATE: Twenty-sixth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: modelling fair, cutting coarse and deep.

PRESERVATION: good.

- 36973. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: medium green, of poor quality.

TECHNIQUE: modelling of back good, cutting rough, legs deeply cut.

PRESERVATION: perfect.

- 36974. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: coarse, no legs.

PRESERVATION: chipped on back.

- 36975. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: pea-green.

TECHNIQUE: modelling of back fair, cutting poorish.

PRESERVATION: perfect.

- 36976. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a winged uraeus, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light green, of poor quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 36977. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with the name of [A]men-ra between vertical lines. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: green, gone a light brown.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

- 36978. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a cat, a fish, and an eye (*cf.* Nos. 36875, 36884, 37143, 37145). *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling fair, cutting deep and good.

PRESERVATION: perfect.

- 36979. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '015. Height, 0 m '009.—Plate VIII.

DESCRIPTION: Inscribed with a *men* and other hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Nineteenth Dynasty or later.

GLAZE: poor grey-blue.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

- 36980. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, Shesha type.

DATE: Hyksos Period (?).

GLAZE: blue green, of good quality.

TECHNIQUE: modelling of back good, cutting coarse.

PRESERVATION: chipped.

- 36981. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '026. Width, 0 m '018. Height, 0 m '009.—Plate XV.

DESCRIPTION: Inscribed on the base with a *hes*-sign, on either side of which are *uraï*: above is a winged disc, and below, a *neb*-sign, while surrounding the whole is a rope-pattern border. *Back*, see Plate XX.

DATE: Nineteenth Dynasty.

GLAZE: green, turned a light-brown.

TECHNIQUE: fair.

PRESERVATION: edges chipped.

- 36982. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of good quality.

TECHNIQUE: modelling fair, cutting very coarse.

PRESERVATION: back flaked.

- 36983. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '024. Width, 0 m '019. Height, 0 m '011.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a pyramid, from the top of which two urai are suspended. Above is a *Ba*-sign, and below, a *neb*. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty.

GLAZE: light greyish-blue.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 36984. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with a winged uræus and hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: light blue-green.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: fair.

- 36985. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '014. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with a hawk-headed sphinx with outspread wings and wearing the double crown of Egypt; before it is a cobra. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull violet.

TECHNIQUE: good.

PRESERVATION: chipped on edge.

- 36986. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed deity, with a cobra and disc in front. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: dark bright green, of good quality.

TECHNIQUE: modelling roughish, cutting coarse.

PRESERVATION: perfect.

**36987. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '009. Height, 0 m '006.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra standing before an altar (?).

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: Bright pale green, going brown.

TECHNIQUE: modelling fair, cutting rough.

PRESERVATION: perfect.

**36988. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate IX.

DESCRIPTION: Inscribed on the base with figures of Amen (or Tum) and Sekhmet.

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone grey.

TECHNIQUE: modelling roughish, cutting excellent.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29937. Bought.

**36989. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, see Plate XXII.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling good, cutting fine, legs deeply cut.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882. MASPERO, *Slip Cat.*, No. 3097.

**36990. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged and a loop-pattern border around them. *Back*, prothorax indicated as No. 37132.

DATE: Eighteenth Dynasty.

GLAZE: green, turned brown.

TECHNIQUE: modelling of back fine, cutting very good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 3830.

- 36991. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx, with a uræus and hieroglyphic signs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: medium blue, going green.

TECHNIQUE: modelling fair, cutting fair and deep.

PRESERVATION: chipped at head.

- 36992. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green-blue, going yellow.

TECHNIQUE: medium.

PRESERVATION: perfect.

- 36993. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with human-headed handle, from which two uræi are suspended (*cf.* Nos. 36328, 37073, &c.). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone a dull yellow.

TECHNIQUE: fair.

PRESERVATION: somewhat damaged by action of water.

- 36994. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown and white.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

32

- 36995. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a double coil and hieroglyphic signs.

*Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light greenish-blue, going white, of good quality.

TECHNIQUE: fine.

PRESERVATION: back flaked and head chipped.

- 36996. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with three flower buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of fine quality.

TECHNIQUE: excellent.

PRESERVATION: perfect.

- 36997. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: coarse.

PRESERVATION: chipped on edge.

- 36998. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on base with four colours symmetrically arranged (*cf.* No. 36488). *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: fair, legs deeply cut.

PRESERVATION: good.

- 36999. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a hawk's head, with a *ra*-sign and *uræus* above, and a *nob*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, turning brown on back.

TECHNIQUE: modelling good, cutting very fine.

PRESERVATION: chipped on edge.

- 37000. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: dull pea-green.

TECHNIQUE: modelling poorish, cutting medium.

PRESERVATION: perfect.

- 37001. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: back and edge chipped.

- 37002. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '009.—Plate VI.

DESCRIPTION: Inscribed on the base with the name of the *Sab* Amenhetep. *Back*, without prothorax or elytra marked.

DATE: Twenty-first Dynasty.

GLAZE: blue, gone dull grey.

TECHNIQUE: good.

PRESERVATION: perfect.



**37003. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, gone a light brown.

TECHNIQUE: modelling fair, cutting very good, legs deeply cut.

PRESERVATION: head chipped.

**37004. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '026. Width, 0 m '019. Height, 0 m '014.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XXII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling good, cutting fair, legs cut through width.

PRESERVATION: head chipped.

**37005. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, prothorax indicated (see Plate XIX).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone light brown.

TECHNIQUE: modelling fair, cutting good, no legs indicated.

PRESERVATION: perfect.

**37006. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, crackled.

TECHNIQUE: modelling very good, cutting poor.

PRESERVATION: chipped at edges.

- 37007. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 37132.

DATE: Late Eighteenth Dynasty.

GLAZE: dark blue, of fine quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: edge chipped.

- 37008. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: pale green, of coarse quality.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: chipped.

- 37009. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: lightish blue, gone green and white in places.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37010. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: pale blue-green.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 37011. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone a yellow-grey.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37012. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '00(?)—Plate IX.

DESCRIPTION: Inscribed on the base with a kneeling figure of Hapÿ wearing three papyrus flowers on his head, and holding before him a cobra. *Back*, prothorax and elytra marked.

DATE: Twenty-sixth Dynasty.

GLAZE: pale pea-green.

TECHNIQUE: fair.

PRESERVATION: back worn down, edges chipped.

- 37013. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine blue-green, gone brown in places.

TECHNIQUE: coarse.

PRESERVATION: chipped on back.

- 37014. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: very dark green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37015. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra. *Back*, Shesha type.

DATE: Nineteenth Dynasty (?).

GLAZE: medium blue.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37016. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: dull greyish-green.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

- 37017. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

- 37018. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with a symmetrical ornamental device. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: fine.

PRESERVATION: perfect.

- 37019. Scarab-shaped Seal.**—Paste.—Length, 0 m '009. Width, 0 m '007, Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs reading *men*. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

PASTE: opaque light blue.

TECHNIQUE: modelling fair, cutting rough.

PRESERVATION: fair.

- 37020. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a cross. *Back*, Shesha type.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: very coarse.

PRESERVATION: head slightly chipped.

- 37021. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '007. Width, 0 m '004. Height, 0 m '003.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium green.

TECHNIQUE: coarsish.

PRESERVATION: chipped on back.

- 37022. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone green.

TECHNIQUE: rough.

PRESERVATION: slightly chipped on back.

- 37023. Scarab-shaped Seal.**—Paste.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: violet-blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37024. Scarab-shaped Seal.**—Emerald stone.—Length, 0 m ·007. Width, 0 m ·005. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

TECHNIQUE: modelling coarse, cutting scratchy.

PRESERVATION: perfect.

- 37025. Scarab-shaped Seal.**—Paste.—Length, 0 m ·008. Width, 0 m ·006. Height, 0 m ·004.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light dull pea-green.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: perfect.

- 37026. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green-blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

*Catal. des Musées*, n. 36001.

33

**37035. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '005. Height, 0 m '004.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of the goddess Sekhmet. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: blue-green, of medium colour.

TECHNIQUE: fair.

PRESERVATION: back much chipped.

**37036. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '008. Width, 0 m '005. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

**37037. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '007. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic (?) signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: light green, going brown.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

**37038. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Maat. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, going yellow-green in places.

TECHNIQUE: medium.

PRESERVATION: fair.

- 37039. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '003. Width, 0 m '007. Height, 0 m '003.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk between two uræi.  
*Back*, Shesha type.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale green, going brown.

TECHNIQUE: medium, back very flat.

PRESERVATION: perfect.

- 37040. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '007. Width, 0 m '006. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLAZE: light blue.

TECHNIQUE: modelling good, cutting scratchy.

PRESERVATION: perfect.

- 37041. Scarab-shaped Seal.**—Paste.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with three papyrus flowers. *Back*, plain as No. 36702 (Plate XIX).

DATE: Middle Eighteenth Dynasty (?).

PASTE: dull violet.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37042. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '007. Width, 0 m '005. Height, 0 m '004.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, prothorax indicated, but no elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone dark brown.

TECHNIQUE: modelling good, cutting very delicate.

PRESERVATION: perfect.



- 37043. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '005. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.  
 DATE: Middle Eighteenth Dynasty.  
 GLAZE: blue, gone greyish brown.  
 TECHNIQUE: coarse.  
 PRESERVATION: fair.

- 37044. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '007. Width, 0 m '005. Height, 0 m '004.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Ra. *Back*, Shesha type.  
 DATE: Middle Eighteenth Dynasty.  
 GLAZE: pale green.  
 TECHNIQUE: very good.  
 PRESERVATION: perfect.

- 37045. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '007. Width, 0 m '005. Height, 0 m '004.—Plate XV.—Abydos.

DESCRIPTION: Inscribed on the base with the figure of a monkey holding before it a *nefer*-sign (*cf.* No. 37273). *Back*, prothorax and elytra marked.  
 DATE: Middle Eighteenth Dynasty (?).  
 GLAZE: fine light green.  
 TECHNIQUE: fair.  
 PRESERVATION: perfect.  
 BIBL.: *Journal d'entrée du Musée*, No. 21958.

- 37046. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '005.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.  
 DATE: Twenty-sixth Dynasty (?).  
 GLAZE: blue, gone dark grey.  
 TECHNIQUE: very good.  
 PRESERVATION: perfect.

- 37047. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: pale green, going yellowish white.

TECHNIQUE: modelling excellent, cutting fair.

PRESERVATION: edge chipped.

- 37048. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '004.—Plate VI.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III (?) between vertical lines. *Back*, rounded prothorax and elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: green, gone yellow-brown.

TECHNIQUE: very rough.

PRESERVATION: chipped and broken.

- 37049. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a deity (?) with a cobra in front. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: deep violet (crackled).

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: perfect.

- 37050. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XV.—Abydos (1881).

DESCRIPTION: Inscribed on the base with the figure of a monkey climbing up a palm (?) tree. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green, going brown and crackled.

TECHNIQUE: modelling poor, cutting good.

PRESERVATION: chipped.

BIBL.: *Journal d'entrée du Musée*, No. 25091.

- 37051. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with the title *Sa Ra*. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue-green, of good quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37052. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: pale green, going brown.

TECHNIQUE: modelling delicate, cutting fine.

PRESERVATION: head and edge chipped.

- 37053. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dark green, of good quality.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: head chipped.

- 37054. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus and hieroglyphic signs. *Back*, see Plate XXI.

DATE: Middle Eighteenth Dynasty.

GLAZE: green; gone brown.

TECHNIQUE: delicate.

PRESERVATION: perfect.

- 37055. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XX.

DATE: Late Eighteenth Dynasty (?).

GLAZE: green, thin, and of good quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 37056. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with an uraeus: before it an *ankh*-sign and below it a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull greeny-blue, of bad quality.

TECHNIQUE: very coarse.

PRESERVATION: slightly chipped.

- 37057. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Bes with monkeys on either side of him. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, nearly all rubbed off.

TECHNIQUE: modelling medium, cutting poor.

PRESERVATION: good.

- 37058. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu son of Ra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty (?).

GLAZE: pale pea-green, going yellowish.

TECHNIQUE: delicate.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

34

**37059. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra. *Back*, plain, with legs (see Plate XIX).

DATE: Twenty-sixth Dynasty (?).

GLAZE: blue, gone whity-grey.

TECHNIQUE: good, the *sa*-sign delicately cut.

PRESERVATION: perfect.

**37060. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a seated figure of Sekhmet: behind her is a hawk (?) with wings outspread. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: dull dark green.

TECHNIQUE: modelling very good, cutting fair, legs pierced through width.

PRESERVATION: perfect.

**37061. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra, with a *neb*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty (?).

GLAZE: green, going brownish-grey.

TECHNIQUE: modelling fair, cutting rough.

PRESERVATION: perfect.

**37062. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: coarse.

PRESERVATION: edges chipped.

- 37063. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .016. Width, 0 m .01. Height, 0 m .007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: dull pea-green, going grey.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: edges chipped.

- 37064. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design with *ankh*-signs on either side. *Back*, worn down.

DATE: Early Eighteenth Dynasty.

GLAZE: pale blue-green.

TECHNIQUE: very good.

PRESERVATION: edges worn.

- 37065. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: pale green-blue, going grey.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37066. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .015. Width, 0 m .011. Height, 0 m .008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a god(?) and a cobra behind him. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone dark brown.

TECHNIQUE: very coarse.

PRESERVATION: back flaked and head chipped.

- 37067. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, see Plate XX.

DATE: Early Eighteenth Dynasty.

GLAZE: very brilliant green, of splendid quality.

TECHNIQUE: modelling very fine, cutting fine.

PRESERVATION: perfect.

- 37068. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a gazelle and two papyrus reeds behind it. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty (?).

GLAZE: dull light blue, of good quality.

TECHNIQUE: modelling good, cutting fine.

PRESERVATION: perfect.

- 37069. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XIV.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green, going brownish-grey; badly glazed.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37070. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '008.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ab*-sign. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light pea-green.

TECHNIQUE: fair.

PRESERVATION: back very much worn.

- 37071. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '008.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ptah standing: before him are hieroglyphic (?) signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: light blue, badly burnt.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: perfect.

- 37072. Scarab-shaped Seal.**—Black steatite.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Osiris. *Back*, carefully detailed and shown in Plate VIII.

DATE: Twenty-first Dynasty (?).

TECHNIQUE: modelling very good, cutting scratchy.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 3640.

- 37073. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with human-headed handle, from which two uræi are suspended (*cf.* Nos. 36993, 37349, etc.). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling fine, cutting very good, legs deeply cut.

PRESERVATION: head chipped.

- 37074. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale bluey-green.

TECHNIQUE: very good.

PRESERVATION: perfect.



- 37075. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*- and four *neb*-signs. *Back*, see Plate XX.

DATE: Early Eighteenth Dynasty (?).

GLAZE: medium blue, of very fine quality.

TECHNIQUE: very fine.

PRESERVATION: perfect.

- 37076. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: brilliant sky-blue, of fine quality.

TECHNIQUE: modelling good, cutting coarsish.

PRESERVATION: perfect.

- 37077. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue, of fine quality.

TECHNIQUE: modelling fair, back very coarse.

PRESERVATION: perfect.

- 37078. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *nefer*-sign between two *ankhs*. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: transparent blue-green, thick and of fine quality.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: perfect.

- 37079. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs of uncertain meaning.  
*Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: pale emerald-green, gone white in places.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37080. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '013. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality, gone white in thin places.

TECHNIQUE: good.

PRESERVATION: chipped.

- 37081. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ra-neb-ha* (cf. Nos. 37347, 36498, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: brilliant green, of fine quality.

TECHNIQUE: fine.

PRESERVATION: perfect.

- 37082. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '00(?)—Plate V.

DESCRIPTION: Inscribed on the base with the name of *Neb-ka-Ra* with a cartouche; hieroglyphic signs in the field. *Back*, worn.

DATE: Eighteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: coarsish.

PRESERVATION: back nearly worn down.

**37083. Scarab-shaped Seal.**—Brown quartz.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with a figure of a vulture (Mut) with a *wfer*-sign in front and a *neb*-sign below. *Back*, plain, as No. 37138 (Plate XIX).

DATE: Nineteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: chipped on the edge.

**37084. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate VI.

DESCRIPTION: Inscribed on the base with the name *Neb-maa-[Ra ?]*. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Late Eighteenth Dynasty (?).

GLAZE: blue.

TECHNIQUE: good.

PRESERVATION: back chipped and flaked.

**37085. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the back with a papyrus flower and two buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: fine blue.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

**37086. Scarab-shaped Seal.**—Pale blue glass.—Length, 0 m '021. Width 0 m '017. Height, 0 m '01.—Plate VI.—Abydos.

DESCRIPTION: Inscribed on the base with the name *Min-nekht (?)*. *Back*, prothorax and elytra marked, with a V on either wing-case (see Plate XXII).

DATE: Late Eighteenth Dynasty.

GLASS: pale blue.

TECHNIQUE: modelling medium, cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 3445.

- 37087. Scarab-shaped Seal.**—Glass.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '008.—Plate XIII.—Gadrah.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, plain (see Plate XIX).

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLASS: pale blue.

TECHNIQUE: cutting good.

PRESERVATION: back worn.

BIBL.: *Journal d'entrée du Musée*, No. 29407.

- 37088. Scarab-shaped Seal.**—White quartz.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '01.—Plate XIII.

DESCRIPTION: Inscribed on the base with two coils and hieroglyphic signs. *Back*, see Plate XXI.

DATE: Twelfth or Thirteenth Dynasty.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37089. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, without prothorax or elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling medium, cutting fair.

PRESERVATION: edges chipped.

BIBL.: *Journal d'entrée du Musée*, No. 30582.

- 37090. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with two urai below. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 29990.

*Catal. du Musée*, n. 36001.

- 37091. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '01.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of an altar (?) and hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: blue-green, of fine quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30422.

- 37092. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '00 (?).—Plate XV.—Mitraheny.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair, legs deeply cut.

PRESERVATION: back flaked badly.

BIBL.: *Journal d'entrée du Musée*, No. 31950.

- 37093. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '009. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of uncertain meaning (*cf.* No. 36822). *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Twenty-sixth Dynasty (?).

GLAZE: dull pea-green.

TECHNIQUE: very delicate.

PRESERVATION: perfect.

- 37094. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '008.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone greenish.

TECHNIQUE: fair, legs deeply cut.

PRESERVATION: perfect.

- 37095. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs (*cf.* Nos. 36923, 37357).  
*Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of good quality and going white.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

- 37096. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated as No. 36543.

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: dark green, gone brown in places.

TECHNIQUE: modelling good, cutting good and bold.

PRESERVATION: perfect.

BIBL.: *Journal d'entré du Musé*, No. 29949.

- 37097. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate XI.—Drah abu'l Negga.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark blue-green.

TECHNIQUE: coarsish. *Back* flaked off but glazed afterwards.

PRESERVATION: *back* flaked.

BIBL.: *Journal d'entré du Musé*, No. 21403. Found in a tomb at Drah abu'l Negga, together with Nos. 36539 and 36649.

- 37098. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: blue, gone grey.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

**37099. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '008.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged, and a loop-pattern border around them. *Back*, prothorax indicated as No. 37179.

DATE: Hyksos Period.

GLAZE: dark green, worn off on back and turning brown.

TECHNIQUE: fair.

PRESERVATION: chipped.

BIBL.: *Journal d'entrée du Musée*, No. 29946. Bought.

**37100. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate XIV.—Abydos.

DESCRIPTION: Inscribed on the base with an *ankh*-sign surrounded by a twisted rope-pattern border. *Back*, see Plate XXI.

DATE: Twelfth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: modelling very fine, cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21951.

**37101. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with a rope-pattern design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green.

TECHNIQUE: bold, but rough work.

PRESERVATION: perfect.

**37102. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XXII.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: modelling medium, cutting coarse, legs deeply cut.

PRESERVATION: perfect.

- 37103. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with the name of Amen with a sitting sphinx above. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone grey-brown.

TECHNIQUE: very coarse.

PRESERVATION: slightly worn.

- 37104. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '01.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king seated on his throne and a man standing before him. *Back*, see Plate XXII.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: modelling good, cutting bold.

PRESERVATION: chipped on head, otherwise perfect.

- 37105. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with figures of a cat, a fish, and an eye, with to the left, a gazelle, and a dog (?). *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Late Eighteenth or Nineteenth Dynasty.

GLAZE: blue, gone grey-brown.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: perfect.

- 37106. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '016. Height, 0 m '01.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, see Plate VI.

DATE: Twenty-second Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: modelling very fine, cutting good, legs pierced through width.

PRESERVATION: perfect.



**37107. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·009.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated (see Plate XIX).

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: slightly chipped.

**37108. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·013. Height, 0 m ·01.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a flying beetle with two feathers and two hawks with outspread wings above. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: green, gone brown and white.

TECHNIQUE: modelling good, cutting very good.

PRESERVATION: chipped on head.

**37109. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·01. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a king with a cobra in front and a disc above. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.

**37110. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·014. Height, 0 m ·009.—Plate IX.

DESCRIPTION: Inscribed on the base with the figure of a king standing between two figures of Ra. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone grey-brown.

TECHNIQUE: fair.

PRESERVATION: worn on both sides.

- 37111. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with a figure of an uræus and hieroglyphic signs. *Back*, see Plate XXII.

DATE: Early Eighteenth Dynasty (?).

GLAZE: blue, gone grey.

TECHNIQUE: modelling coarse, cutting very good and deep.

PRESERVATION: slightly chipped.

- 37112. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus wearing the crown of Lower Egypt. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Eighteenth Dynasty (?).

GLAZE: green, of good quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37113. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·009. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: roughish.

PRESERVATION: perfect.

- 37114. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning (compare Nos. 36621 and 36627). *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty.

GLAZE: pale green, going white.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: back worn.

**37115. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone a light brown.

TECHNIQUE: good.

PRESERVATION: perfect.

**37116. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: medium.

PRESERVATION: perfect.

**37117. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dark green, gone grey on back.

TECHNIQUE: modelling fine, cutting poor.

PRESERVATION: good.

**37118. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with a figure of a vulture (Mut), with a uraeus above, and a *neb*-sign below. To the right is the legend *Kha-nefer*. *Back*, see Plate XXI.

DATE: Eighteenth Dynasty (?).

GLAZE: green, going grey

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 37119. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye (?). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of medium colour.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37120. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a kneeling figure wearing an *atef*-crown and holding in one hand a figure of the goddess Maat (?) with a *her*-sign beneath. Below the kneeling figure is a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull pale pea-green.

TECHNIQUE: good.

PRESERVATION: back chipped.

- 37121. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: good, legs pierced through width.

PRESERVATION: chipped at head.

- 37122. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·018. Width, 0 m ·013. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a beetle with outspread wings. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (?).

GLAZE: blue (?), gone white, of bad quality.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

36

- 37123. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37124. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, with prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty (see Plate XXII).

GLAZE: blue, of fine quality.

TECHNIQUE: modelling poor, cutting very good.

PRESERVATION: perfect.

- 37125. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone yellow, but of good quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37126. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green, going grey.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 37127. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate VII.

DESCRIPTION: Inscribed on the base with a figure of a beetle with a cobra on either side. *Back*, prothorax and elytra marked.

DATE: Hyksos Period or Nineteenth Dynasty.

GLAZE: blue, gone a brownish-grey.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

- 37128. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with a *hes*-sign between two urai, while surrounding the whole is a rope-pattern border (*cf.* No. 37359). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: good, legs deeply cut.

PRESERVATION: chipped on head and edges.

- 37129. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·007. Height, 0 m ·005.—Plate XV.

DESCRIPTION: Inscribed on the base with a figure of the goddess Tauris, with a *sa*-sign before it. *Back*, prothorax indicated, as No. 36467.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brownish-grey.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37130. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate X.

DESCRIPTION: Inscribed on the base with the title *Semer-ua-ti*. *Back*, see Plate XXI.

DATE: Twenty-sixth Dynasty (?).

GLAZE: green, gone grey.

TECHNIQUE: very good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 1682, Abydos, 1398.

- 37131. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Nineteenth Dynasty (?).

GLAZE: dark green, gone brown in places.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37132. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a flying bird within a geometric border. *Back*, prothorax indicated (see Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37133. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·007.—Plate XIII.

DESCRIPTION: Inscribed on the base with four colours symmetrically arranged. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: fair, legs deeply cut.

PRESERVATION: slightly chipped on back.

- 37134. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·02. Width, 0 m ·14. Height, 0 m ·009.—Plate IX.—Abydos.

DESCRIPTION: Inscribed on the base with a figure of the emblem of the Thinite nome with deities on either side. *Back*, see Plate XXI.

DATE: Nineteenth Dynasty.

GLAZE: green (burnt).

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30446.

- 37135. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of an animal (?), with a rope-pattern border around it. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Twenty-sixth Dynasty (?).

PASTE: violet-blue.

TECHNIQUE: good.

PRESERVATION: back rubbed.

- 37136. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two horizontal lines. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37137. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate VIII.

DESCRIPTION: A double scarab, inscribed on the base of one with the name of Amen-ra, and on that of the other with four uraei with tails joining in the centre. *Back*, see Plate VIII.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: chipped on head of left beetle.

- 37138. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a king smiting a captive with his battle-axe. Between the king's feet is a lion and to the left an *ankh*-sign. *Back*, plain (see Plate XIX).

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone grey.

TECHNIQUE: good.

PRESERVATION: perfect.



- 37139. Scarab-shaped Seal.**—Brown stone (?).—Length, 0 m '02. Width, 0 m '013. Height, 0 m '01.—Plate XVII.

DESCRIPTION : Inscribed on the base with a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE : Twelfth—Seventeenth Dynasty (?)

STONE : brown, polished.

TECHNIQUE : modelling good, cutting very rough.

PRESERVATION : badly chipped.

- 37140. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '007. Height, 0 m '003.—Plate XIII.

DESCRIPTION : Inscribed on the base with an ornamental design. *Back*, see Plate XIII.

DATE : Early Eighteenth Dynasty.

GLAZE : blue-green, of good quality.

TECHNIQUE : good.

PRESERVATION : fair.

- 37141. Scarab-shaped Seal.**—Glass.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION : Inscribed on the base with a cross and hatched vertical lines  
*Back*, see Plate XX.

DATE : Early Eighteenth Dynasty.

GLASS : light blue.

TECHNIQUE : coarse.

PRESERVATION : slightly chipped.

- 37142. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate XV.

DESCRIPTION : Inscribed on the base with the figure of a seated man. *Back*, see Plate XX.

DATE : Eighteenth Dynasty (?)

TECHNIQUE : coarse.

PRESERVATION : perfect.

- 37143. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '009.—Plate X.—Erment.

DESCRIPTION: Inscribed on the base with a figure of a cat and a fish within an eye. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Late Eighteenth Dynasty.

GLAZE: light blue, of very fine quality.

TECHNIQUE: exquisite, legs pierced through width.

PRESERVATION: perfect.

BIBL.: found by Mr. Carter at Erment.

- 37144. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, plain, as No. 36702 (Plate XIX).

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37145. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a lotus flower and two buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling exquisite, cutting fair.

PRESERVATION: perfect.

- 37146. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a lion and a *ra*-sign above it. *Back*, prothorax and elytra marked. Set in a gold fundu.

DATE: Twenty-sixth Dynasty.

GLAZE: light yellow, of good quality.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: perfect.

- 37147. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a cynocephalus seated on a *neb*-sign and a feather in front of him. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone a metallic copper colour.

TECHNIQUE: fair.

PRESERVATION: back flaked.

- 37148. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '006.—Plate VIII.

DESCRIPTION: A double scarab with the name of Amen-ra, *uab*- and *neb*-signs on one base and *nefer em menu* on the other. *Back*, see Plate VIII.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling coarse, cutting medium.

PRESERVATION: perfect.

- 37149. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a hand. *Back*, plain, as No. 36575.

DATE: Early Eighteenth Dynasty (?).

GLAZE: blue, gone light grey.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: head chipped.

BIBL.: *Journal d'entrée du Musée*, No. 34050.

- 37150. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '01.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XIV. Yellow glazed funda.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37151. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, of medium colour.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37152. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a winged uraeus with a *neb*-sign below it. *Back*, see Plate XX.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: pale green, of good quality.

TECHNIQUE: modelling good, cutting deep.

PRESERVATION: perfect.

- 37153. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

PASTE: dull pale pea-green.

TECHNIQUE: fair.

PRESERVATION: back much worn.

- 37154. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: good.

*Catal. de Masé,* n. 36001.

37

**37155. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: green, going brown in places.

TECHNIQUE: fair.

PRESERVATION: perfect.

**37156. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull green.

TECHNIQUE: fair.

PRESERVATION: chipped.

**37157. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *nefer*-sign surrounded by a continuous loop-pattern border. *Back*, prothorax indicated, as No. 36009.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, going brown.

TECHNIQUE: very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 34265.

**37158. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·012. Height, 0 m ·007.—Plate X.

DESCRIPTION: Inscribed on the base with the figure of a man holding two flails. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: bluey-grey, of good quality, going white in places.

TECHNIQUE: modelling good, cutting fair and deep.

PRESERVATION: perfect.

- 37159. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a cynocephalus, an uræus, and a *neb*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: pea-green, going whity-grey.

TECHNIQUE: modelling fair, cutting coarsish.

PRESERVATION: back worn.

- 37160. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a man and hieroglyphic signs on either side of it. *Back*, see Plate XX.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: modelling good, cutting fair and deep.

PRESERVATION: perfect.

- 37161. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with a figure of a seated cynocephalus, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: very fine.

PRESERVATION: perfect.

- 37162. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown in places.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37163. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate XII.—Abydos.

DESCRIPTION: Inscribed on the base with a coil pattern and a lotus bud. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30356.

- 37164. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, plain (see Plate XIX).

DATE: Twelfth Dynasty.

GLAZE: green, gone white in places.

TECHNIQUE: very good.

PRESERVATION: back worn and head chipped.

- 37165. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·009.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative rope pattern. *Back*, prothorax indicated (see Plate XIX).

DATE: Hyksos Period.

GLAZE: green, going brown in places.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37166. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate XIII.

DESCRIPTION: Inscribed on the base with a rope-pattern design. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: olive green, gone brown in places.

TECHNIQUE: modelling fair, cutting very good and deep.

PRESERVATION: perfect.

- 37167. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, Shesha type.

DATE: Twelfth Dynasty.

GLAZE: green, gone grey in thin parts.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37168. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 36567.

DATE: Twelfth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: modelling good, cutting very delicate.

PRESERVATION: perfect.

- 37169. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds. *Back*, rounded prothorax and elytra.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: modelling good, cutting very good.

PRESERVATION: perfect.

- 37170. Scarab-shaped Seal.**—Paste.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer* and *ankh* between two *neb*-signs. *Back*, see Plate XVI.

DATE: Nineteenth Dynasty.

PASTE: dark violet-blue.

TECHNIQUE: modelling coarse, cutting fine.

PRESERVATION: good.



- 37171. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·007.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of uniting of Upper and Lower Egypt. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: dark green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37172. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·00(?)—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green, going white.

TECHNIQUE: fair.

PRESERVATION: back flaked.

- 37173. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·011. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Twenty-sixth Dynasty (?).

GLAZE: dull pea-green.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 37174. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·00(?)—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Amen (?). *Back*, flaked away.

DATE: Nineteenth Dynasty.

GLAZE: pale blue.

TECHNIQUE: coarse.

PRESERVATION: back flaked away.

- 37175. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '019. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.  
 DATE: Early Eighteenth Dynasty (Hatshepsut).  
 GLAZE: medium blue.  
 TECHNIQUE: coarse.  
 PRESERVATION: perfect.

- 37176. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, see Plate XXI.  
 DATE: Eighteenth Dynasty.  
 GLAZE: pea-green, gone brown.  
 TECHNIQUE: modelling good, cutting fair.  
 PRESERVATION: perfect.

- 37177. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, rounded prothorax and elytra marked.  
 DATE: Twelfth Dynasty (?).  
 GLAZE: blue, gone white.  
 TECHNIQUE: modelling good, cutting fine.  
 PRESERVATION: perfect.

- 37178. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *wfer*, *ankh*, and *neb*. *Back*, rounded prothorax and elytra marked.  
 DATE: Early Eighteenth Dynasty (Hatshepsut).  
 GLAZE: dark blue-green.  
 TECHNIQUE: good.  
 PRESERVATION: perfect.

- 37179. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, prothorax indicated (see Plate XIX).

DATE: Eighteenth Dynasty (?).

GLAZE: green, gone a pale brown.

TECHNIQUE: modelling very good, cutting poor.

PRESERVATION: perfect.

- 37180. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate VI.—Kurneh (1862).

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

GLAZE: medium green, going brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 20421.

- 37181. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: medium blue.

TECHNIQUE: modelling lumpy, cutting fair.

PRESERVATION: perfect.

- 37182. Scarab-shaped Seal.**—Paste.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: light blue pea-green.

TECHNIQUE: modelling medium, cutting poor.

PRESERVATION: worn slightly.

- 37183. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs of uncertain meaning.  
*Back*, Shesha type.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue, of fine quality.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

- 37184. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: dull grey-blue.

TECHNIQUE: poor.

PRESERVATION: slightly chipped.

- 37185. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: very dark green, of poor quality.

TECHNIQUE: modelling poor, cutting fair.

PRESERVATION: good.

- 37186. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a double coil and hieroglyphic signs.  
*Back*, Shesha type.

DATE: Twelfth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fair.

PRESERVATION: back worn.

*Catal. du Musée*, n. 36001.

38

- 37187. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XX.  
 DATE: Nineteenth or Twentieth Dynasty.  
 GLAZE: very pale green, nearly white.  
 TECHNIQUE: good.  
 PRESERVATION: perfect.

- 37188. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, see Plate XX.  
 DATE: Middle Eighteenth Dynasty.  
 GLAZE: dark blue-green, of fine quality.  
 TECHNIQUE: modelling good, cutting coarsish.  
 PRESERVATION: worn on back.

- 37189. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with three papyrus flowers and a *neb*-sign below. *Back*, rounded prothorax and elytra marked.  
 DATE: Early Eighteenth Dynasty.  
 GLAZE: blue-green, of fine quality.  
 TECHNIQUE: modelling good, cutting fair.  
 PRESERVATION: edges chipped.

- 37190. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.  
 DATE: Early Eighteenth Dynasty.  
 GLAZE: blue, of fine quality.  
 TECHNIQUE: fair.  
 PRESERVATION: perfect.

- 37191. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *hes*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37192. Scarab-shaped Seal.**—Paste.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: dark blue-violet.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37193. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue, gone a dirty grey, and decayed.

TECHNIQUE: coarse.

PRESERVATION: fair.

- 37194. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with signs of uncertain meaning. *Back*, without prothorax or elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue.

TECHNIQUE: very coarse.

PRESERVATION: fair.

- 37195. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a papyrus flower and two buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green, of fine quality, going white.

TECHNIQUE: excellent.

PRESERVATION: perfect.

- 37196. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer*, *ankh* and *neb*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, of very fine quality.

TECHNIQUE: very fine.

PRESERVATION: perfect.

- 37197. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with a papyrus flower and two coils. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fine, cutting roughish.

PRESERVATION: perfect.

- 37198. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '022. Width, 0 m '015. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra; a *neb*-sign between. *Back*, a beetle with a human head (Plate VIII).

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: medium greeny-blue.

TECHNIQUE: coarse.

PRESERVATION: worn on edge.

- 37199. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of good quality.

TECHNIQUE: roughish.

PRESERVATION: perfect.

- 37200. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green, of fine quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: good.

- 37201. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a lotus flower and buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, going green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37202. Scarab-shaped Seal.**—Paste.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

PASTE: dark blue-violet.

TECHNIQUE: roughish.

PRESERVATION: perfect.



- 37203. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·01. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with a papyrus flower and buds, with a *neb*-sign below. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling very good, cutting roughish.

PRESERVATION: perfect.

- 37204. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XVII.

DESCRIPTION: On the base is a sign in relief of uncertain meaning. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (?).

GLAZE: dull thin green.

TECHNIQUE: modelling fair, cutting very coarse.

PRESERVATION: perfect.

- 37205. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882.  
MASPERO, *Stip. Cat.*, No. 3097.

- 37206. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, see Plate XXI.

DATE: Middle Eighteenth Dynasty.

GLAZE: greeny-blue, of good quality.

TECHNIQUE: poor.

PRESERVATION: good.

- 37207. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated as No. 36709.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue, of fine quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37208. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: edge chipped.

- 37209. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a decorative *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull green-blue, of good quality.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: perfect.

- 37210. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '005.—Plate VI.—Abydos.

DESCRIPTION: Inscribed on the base with the name *A-r-s*. (Not a modern forgery.) *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: blue, gone white.

TECHNIQUE: modelling fair, cutting coarsish.

PRESERVATION: head chipped.

BIBL: *Journal d'entrée du Musée*, No. 29835. MASPERO, *Stip Cut.*, No. 6805.

- 37211. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a fish. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of fine quality, going brownish.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37212. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with a geometrical device. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue, of fine quality.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

- 37213. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: dull dark green.

TECHNIQUE: modelling fair, cutting coarsish.

PRESERVATION: edges chipped.

- 37214. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged. *Back*, with prothorax slightly indicated, but no elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull dark green, of fine quality.

TECHNIQUE: modelling fine, cutting very good.

PRESERVATION: perfect.

- 87215. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull green, gone grey in places.

TECHNIQUE: modelling medium, cutting fair.

PRESERVATION: chipped at head.

- 87216. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '01. Height, 0 m '004.—Plate V.

DESCRIPTION: Inscribed on the base with the name Nub-ka-Ra. *Back*, prothorax and elytra marked.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: perfect.

- 87217. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '013. Width, 0 m '008. Height, 0 m '007.—Plate VI.—Sakkara.

DESCRIPTION: Inscribed on the base with the name *Amen-bak* and legend *hez nfer*. *Back*, see Plate VI. Set in a gold fundu.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: modelling exquisite, cutting very delicate, legs pierced through width.

PRESERVATION: cracked across bottom.

BIBL: *Journal d'entrée du Musée*, No. 35219.

- 87218. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '006.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of a god or goddess. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale blue-green, going yellowish, of good quality.

TECHNIQUE: modelling fair, cutting very good.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

39

- 37219. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·00(?)—Plate V.—San (1863).

DESCRIPTION: Inscribed on the base with the legend *Se-hetep-ab-Ra-ankh* and a figure of the goddess Maat. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone pale yellow.

TECHNIQUE: cutting very good, legs deeply cut.

PRESERVATION: back flaked.

BIBL: MASPERO, *Slip Cat.*, No. 1696. *Journal d'entrée du Musée*, No. 21118.

- 37220. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·008. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with a hieroglyphic sign. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium green, of good quality.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: good.

- 37221. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: blue-green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37222. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·005.—Plate XV.

DESCRIPTION: Inscribed on the back with the figure of a snake-headed lion. *Back*, see Plate XXI.

DATE: Twenty-sixth Dynasty.

GLAZE: Pale dull pea-green.

TECHNIQUE: modelling medium, cutting fair.

PRESERVATION: perfect.

- 37223. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *ankh*-signs, with *neb*-signs above and below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30794.

- 37224. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '009.—Plate VIII.

DESCRIPTION: Inscribed with the name of Amen-ra between two *neb*-signs. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty (Amenhetep III).

GLAZE: sky-blue, of exquisite colour and quality.

TECHNIQUE: fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30793.

- 37225. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: pale blue, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30791.

- 37226. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, prothorax and elytra marked (see Plate XX).

DATE: Middle Eighteenth Dynasty.

GLAZE: pale light blue.

TECHNIQUE: modelling coarse, cutting coarse and scratchy, legs deeply cut.

PRESERVATION: perfect.

- 37227. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '007. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign between two *neb*-signs (*cf.* Nos. 37257, 37258, 37259). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: good, no legs indicated.

PRESERVATION: perfect.

- 37228. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: yellowish green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37229. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '07. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

- 37230. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: good, no legs indicated.

PRESERVATION: perfect.

- 37231. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *wfer*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue, of medium quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37232. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed with the name Amen. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: medium blue, of good quality.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 37233. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '004.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37234. Scarab-shaped Seal.**—Paste.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

PASTE: violet.

TECHNIQUE: poor.

PRESERVATION: chipped edges.



- 37235. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '008. Width, 0 m '006. Height, 0 m '004.—Plate VIII.

DESCRIPTION: Inscribed with a *men*-sign (? blundered for Amen). *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: light blue, of good quality.

TECHNIQUE: poor.

PRESERVATION: good.

- 37236. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing on a *neb*-sign. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, going white in places.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: good.

- 37237. Scarab-shaped Seal.**—Paste.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a winged sphinx, with a uræus in front of it. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

PASTE: light violet.

TECHNIQUE: good.

PRESERVATION: head chipped.

- 37238. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a lion. *Back*, prothorax indicated (see Plate XIX).

DATE: Middle Eighteenth Dynasty.

GLAZE: fine green.

TECHNIQUE: modelling very good, cutting very good.

PRESERVATION: chipped.

- 37239. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *ankh*-signs. *Back*, see Plate XXI.

DATE: Middle or Late Eighteenth Dynasty.

GLAZE: dull sky-blue.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37240. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer* and *ankh*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull violet-blue.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37241. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '006. Height, 0 m '00(?)—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, flaked away.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: green, going grey.

TECHNIQUE: rough.

PRESERVATION: back flaked away.

- 37242. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone yellowish.

TECHNIQUE: fair.

PRESERVATION: head chipped off.

- 37243. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·004.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a beetle with outspread wings. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: fair, no legs indicated.

PRESERVATION: perfect.

- 37244. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·009. Width, 0 m ·006. Height, 0 m ·004.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *kheper*-sign. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty (?).

GLAZE: dull blue.

TECHNIQUE: very coarse.

PRESERVATION: perfect.

- 37245. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·009. Width, 0 m ·006. Height, 0 m ·005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of an uræus. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: pale grey-blue.

TECHNIQUE: poor.

PRESERVATION: good.

- 37246. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37247. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .009. Width, 0 m .006. Height, 0 m .004.—Plate X.—San (1863).

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very delicate.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 21121.

- 37248. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .007. Height, 0 m .006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: delicate.

PRESERVATION: perfect.

- 37249. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .007. Height, 0 m .005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown in places, of fine quality.

TECHNIQUE: good, legs pierced through width.

PRESERVATION: good.

- 37250. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .009. Height, 0 m .005.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue-green.

TECHNIQUE: poor.

PRESERVATION: worn.

*Catal. du Musée*, n. 36001.

40

- 37251. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing upon a *nub*-sign. Before it an *ankh*-sign and behind a feather. *Back*, flaked away.

DATE: Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fair.

PRESERVATION: back flaked.

- 37252. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a sphinx with a *nefer*-sign before it and an uræus above its back. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37253. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '009. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: dark green (crackled), going brown and badly burnt.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 37254. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '006.—Plate VI.—Abydos.

DESCRIPTION: Inscribed on the base with the signs *Ra Kheper*. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, of fine quality, going white.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 25832.

- 37255. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, of poor quality.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: worn.

- 37256. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·004.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale blue, of fine quality.

TECHNIQUE: fair.

PRESERVATION: back chipped

- 37257. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·009. Width, 0 m ·008. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign between two *neb*-signs (*cf.* Nos. 37227, 37258, 37259). *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: pale greeny-brown.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37258. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·009. Width, 0 m ·007. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign between two *neb*-signs (*cf.* Nos. 37227, 37257, 37259). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: good.

- 37259. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign between two *neb*-signs (*cf.* Nos. 37227, 37257, 37258). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale green, badly glazed.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37260. Scarab-shaped Seal.**—Paste.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: dull green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37261. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone yellowish.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37262. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·008. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: dull green, going brown.

TECHNIQUE: coarse.

PRESERVATION: head chipped.

- 37263. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.—Plate XI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs symmetrically arranged. *Back*, Shesha type.

DATE: Hyksos Period or Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: slightly chipped.

- 37264. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue, of good quality, but decayed by water action.

TECHNIQUE: fair.

PRESERVATION: good.

- 37265. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·01. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone yellow and white.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 37266. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone brown.

TECHNIQUE: modelling coarse, cutting poor.

PRESERVATION: much worn.



- 37267. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark sky-blue, of brilliant quality.

TECHNIQUE: modelling medium, cutting rough.

PRESERVATION: back chipped.

- 37268. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone grey-brown.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 37269. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *nfr*-signs and a *neb*-sign above. *Back*, prothorax indicated as No. 37132.

DATE: Early Eighteenth Dynasty.

GLAZE: pale sky-blue, of fine quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 37270. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed with a figure of the goddess *Maat*, with a *neb*-sign above her knees. *Back*, prothorax and elytra marked, with a *V* on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37271. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed with the signs *n* and *men* between two *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling very fine, cutting poor.

PRESERVATION: perfect.

- 37272. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: pale blue-green.

TECHNIQUE: very poor.

PRESERVATION: good.

- 37273. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '005.—Plate XV.

DESCRIPTION: Inscribed on the base with the figure of a monkey holding a *nefer*-sign, surrounded by a rope-pattern border. *Back*, prothorax indicated but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: modelling good, cutting poor.

PRESERVATION: chipped.

- 37274. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III, with urai on either side. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: coarse, no legs indicated.

PRESERVATION: perfect.

- 37275. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a double coil between two *nefer*-signs.  
*Back*, rounded back and prothorax marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: modelling good, cutting very good, legs deeply cut.

PRESERVATION: perfect.

- 37276. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.—Plate XVI.

DESCRIPTION: Inscribed on the base with an *ankh*-sign, and a *neb*-sign below.  
*Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: blue-green.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 37277. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: pale green.

TECHNIQUE: coarse.

PRESERVATION: chipped.

- 37278. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of an eye, with *neb*-signs on either side and below. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: bluish green.

TECHNIQUE: modelling fair, cutting poor.

PRESERVATION: perfect.

- 37279. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk standing on a *neb*-sign. The hawk wears the double crown and before it is an uræus. *Back*, prothorax indicated as No. 36543.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue, of fine quality.

TECHNIQUE: modelling very good, cutting fair.

PRESERVATION: perfect.

- 37280. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with a coil and a *nefer*-sign. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, going white.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: perfect.

- 37281. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: bright blue-green, going white.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37282. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: perfect.

*Catal. du Musée*, n. 38001.

41

- 37283. Scarab-shaped Seal.**—Paste.—Length, 0 m '014.—Width, 0 m '011.  
Height, 0 m '00(?).—Plate V.

DESCRIPTION: Inscribed on the base with the name of the *seten hent*, Aâhmes.

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

PASTE: dull pale pea-green.

TECHNIQUE: cutting very good.

PRESERVATION: back flaked away, and edge chipped.

- 37284. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width,  
0 m '007. Height, 0 m '006.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III. *Back*,  
rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark blue.

TECHNIQUE: coarse.

PRESERVATION: good.

- 37285. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width,  
0 m '007. Height, 0 m '004.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded  
prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, of fine quality.

TECHNIQUE: very fine.

PRESERVATION: head chipped.

- 37286. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width,  
0 m '011. Height, 0 m '006.—Plate XI.

DESCRIPTION: Inscribed on the base with the symbol of the uniting of Upper and  
Lower Egypt with hieroglyphic signs symmetrically arranged below. Set in  
a silver fundâ. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty (?).

GLAZE: blue-green, of fine quality, going brown and worn off on back.

TECHNIQUE: excellent.

PRESERVATION: good.

- 37287. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .01. Height, 0 m .008.—Plate VI.

DESCRIPTION: Inscribed on the base with the name of Psamtek. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty.

GLAZE: pale green, gone grey.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: edge chipped.

- 37288. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .015. Width, 0 m .01. Height, 0 m .005.—Plate VIII.

DESCRIPTION: Inscribed with the name of the god Ptah, with a *nch*-sign below and vertical lines on either side. *Back*, prothorax and elytra marked.

DATE: Eighteenth or Nineteenth Dynasty.

GLAZE: dark green, badly burnt.

TECHNIQUE: rough.

PRESERVATION: good.

- 37289. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .01. Width, 0 m .008. Height, 0 m .006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: very good.

PRESERVATION: Slightly chipped on head.

- 37290. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .009. Height, 0 m .006.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of an altar. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: Brilliant sky-blue.

TECHNIQUE: fair.

PRESERVATION: chipped.

- 37291. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a flying hawk; an *ankh*-sign before it. *Back*, without prothorax or elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull blue-green, of fine quality.

TECHNIQUE: modelling excellent, cutting very good.

PRESERVATION: perfect.

- 37292. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with figures of a horse and a hippopotamus (?). *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green, going grey.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 37293. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate X.—Abydos.

DESCRIPTION: Inscribed on the base with the titles *neter nefer*, *neb tau*, and an *ankh*-sign above. *Back*, without prothorax or elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of fine quality.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: edges slightly chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 3810, Abydos, 1379.

- 37294. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate VI.

DESCRIPTION: Inscribed on the base with a hieroglyphic legend. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: olive green, of very fine quality.

TECHNIQUE: modelling very fine, cutting very good.

PRESERVATION: perfect.

- 37295. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .009. Height, 0 m .007.—Plate X.

DESCRIPTION: Inscribed on the base with a hawk's head (?) wearing an *atef*-crown, with a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: pale blue.

TECHNIQUE: modelling coarse, cutting good.

PRESERVATION: perfect.

- 37296. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device and hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light blue-green.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: chipped.

- 37297. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .011. Height, 0 m .008.—Plate XVI.

DESCRIPTION: Inscribed on the base with two *nefer*-signs between two *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull dark blue.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: edge chipped.

- 37298. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .013. Width, 0 m .01. Height, 0 m .006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: greeny-violet.

TECHNIQUE: fair.

PRESERVATION: perfect.



- 37299. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue-green, of fine quality.

TECHNIQUE: very good.

PRESERVATION: chipped.

- 37300. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: fine blue-green.

TECHNIQUE: modelling very fine, cutting very good.

PRESERVATION: head chipped.

- 37301. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Plate X.—Abydos.

DESCRIPTION: Inscribed on the base with the titles *seten bati, thctct*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: green, gone light brown.

TECHNIQUE: good.

PRESERVATION: back and edges chipped.

BIBL.: *Journal d'entrée du Musée*, No. 25040. MASPERO, *Slip Cat.*, No. 3813, Abydos, 1379.

- 37302. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '005.—Plate IX.

DESCRIPTION: Inscribed on the base with a kneeling figure of Hapÿ. *Back*, plain as No. 36702 (Plate XIX).

DATE: Twenty-sixth Dynasty.

GLAZE: dull pea-green.

TECHNIQUE: modelling good, cutting coarse.

PRESERVATION: perfect.

- 37303. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a lion. *Back*, rounded prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green, gone brown and white.

TECHNIQUE: coarse.

PRESERVATION: slightly chipped.

- 37304. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate VII.

DESCRIPTION: Inscribed on the base with the figure of a sphinx with hieroglyphic signs in the field. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone dark brown.

TECHNIQUE: modelling roughish, cutting medium.

PRESERVATION: perfect.

- 37305. Scarab-shaped Seal.**—Dark green jasper.—Length, 0 m '016. Width, 0 m '013. Height, 0 m '008.—Plate X.

DESCRIPTION: Inscribed on the base with a lotus flower between two papyrus flowers. *Back*, see Plate XXI.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: modelling fair, cutting nearly worn down.

PRESERVATION: seal worn.

- 37306. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '023. Width, 0 m '017. Height, 0 m '012.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III and the legend "beloved of Sebek." *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale pea-green, gone yellow on back.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: edge chipped.

- 37307. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '01.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Amen standing between two figures of Ra (*cf.* No. 36749). *Back*, see Plate XX.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brownish-grey.

TECHNIQUE: modelling coarsish, cutting fair.

PRESERVATION: perfect.

- 37308. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '011. Height, 0 m '009.—Plate X.

DESCRIPTION: Inscribed on the base with legend reading *Anakh uza Ra*. *Back*, with prothorax and elytra marked.

DATE: Nineteenth Dynasty or later.

GLAZE: pale blue, badly glazed.

TECHNIQUE: coarse, legs pierced through width.

PRESERVATION: head chipped.

- 37309. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '018. Width, 0 m '014. Height, 0 m '008.—Plate VIII.

DESCRIPTION: Inscribed with a figure of a hawk standing upon a *neb*-sign; behind it is a *ra*-sign with suspended uræus. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: medium blue.

TECHNIQUE: coarse.

PRESERVATION: slightly chipped.

- 37310. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '007.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, going green.

TECHNIQUE: very coarse.

PRESERVATION: edge chipped.

- 37311. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·00(?)—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, broken.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: pale dull blue.

TECHNIQUE: cutting good.

PRESERVATION: back flaked.

- 37312. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate VI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull blue.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37313. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·008.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dull dark blue.

TECHNIQUE: modelling fair, cutting very coarse.

PRESERVATION: perfect.

- 37314. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue-green.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

42

- 37315. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION: Inscribed on the base with the prenom of Thothmes III, and a crowned uræus to the left. *Back*, rounded prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: dark blue, of good quality.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37316. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with a cross and concentric circles within the arms. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: light sky-blue.

TECHNIQUE: fair, no legs indicated.

PRESERVATION: perfect.

- 37317. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '004.—Plate XVI.

DESCRIPTION: Inscribed on the base with a *dend*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37318. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '004. Width, 0 m '006. Height, 0 m '003.—Plate XII.

DESCRIPTION: Inscribed on the base with three flower buds. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, of fine quality.

TECHNIQUE: modelling good, cutting fine.

PRESERVATION: perfect.

- 37319. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·008. Width, 0 m ·006. Height, 0 m ·004.—Plate VIII.

DESCRIPTION: Inscribed with a figure of a flying hawk, with a *ra*-sign in front of it. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: good.

- 37320. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: modelling very good, cutting fair.

PRESERVATION: perfect.

- 37321. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a flying hawk [holding in its talons] before it a seal. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 37322. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·009. Height, 0 m ·006.—Plate XII.

DESCRIPTION: Inscribed on the base with an ornamental device. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark green, going brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37323. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.—Plate XIII.

DESCRIPTION: Inscribed on the base with an ornamental design. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of fine quality.

TECHNIQUE: modelling fine, cutting fair.

PRESERVATION: good.

- 37324. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked (see Plate XXI).

DATE: Early Eighteenth Dynasty.

GLAZE: medium blue, of fine quality.

TECHNIQUE: very good.

PRESERVATION: perfect.

- 37325. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '006.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dull dark blue.

TECHNIQUE: good.

PRESERVATION: perfect.

- 37326. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: medium bluish-green, of very good quality.

TECHNIQUE: good, no legs indicated.

PRESERVATION: perfect.

- 37327. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .011. Width, 0 m .007. Height, 0 m .005.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty.

GLAZE: dull dark greeny-blue.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37328. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .012. Width, 0 m .008. Height, 0 m .006.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, Shesha type.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: dark blue.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 37329. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .012. Width, 0 m .008. Height, 0 m .005.—Plate VIII.

DESCRIPTION: Inscribed with an *r*- and *men*-sign. *Back*, prothorax indicated as No. 36826.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue, of fine quality.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37330. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m .012. Width, 0 m .008. Height, 0 m .006.—Plate XVI.

DESCRIPTION: Inscribed on the base with the signs *nefer* and *ankh*. *Back*, prothorax indicated as No. 37132.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: light blue.

TECHNIQUE: very good.

PRESERVATION: perfect.



- 37331. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width 0 m ·009. Height, 0 m ·007.—Plate XVI.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, similar to No. 37330.

DATE: Early Eighteenth Dynasty (Hatshepsut).

GLAZE: blue, of very good quality.

TECHNIQUE: modelling very good, cutting coarse.

PRESERVATION: perfect.

- 37332. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate VIII.

DESCRIPTION: Inscribed with a *men*-sign between two *neb*-signs. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green, of fine quality.

TECHNIQUE: modelling fine, cutting coarse.

PRESERVATION: good.

- 37333. Scarab-shaped Seal.**—Paste.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

PASTE: pale dull pea-green.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37334. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium green, going brown.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37335. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·009. Height, 0 m ·006.—Plate XIII.

DESCRIPTION: Inscribed on the base with four cobras symmetrically arranged.

*Back*, with prothorax slightly indicated but no elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: medium green, going brown.

TECHNIQUE: coarse.

PRESERVATION: perfect.

- 37336. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·012. Width, 0 m ·008. Height, 0 m ·006.—Plate IX.

DESCRIPTION: Inscribed on the base with a figure of Ra standing before a *nefer*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: blue.

TECHNIQUE: modelling fair, cutting coarse.

PRESERVATION: perfect.

- 37337. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·007.—Plate VII.

DESCRIPTION: Inscribed on the base with a hawk-headed divinity and an uraeus.

*Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: pale pea-green.

TECHNIQUE: rough.

PRESERVATION: perfect.

- 37338. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·012. Width, 0 m ·009. Height, 0 m ·007.—Plate V.

DESCRIPTION: Inscribed on the base with the name *Men-kheper* between two feathers. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: green, going iridescent.

TECHNIQUE: very coarse.

PRESERVATION: fair.

- 37339. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION : Inscribed on the base with the prenomen of Thothmes III within an oval, with *uza*-eyes above and below. *Back*, rounded prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

GLAZE : fine grey-blue.

TECHNIQUE : excellent.

PRESERVATION : perfect.

- 37340. Scarab-shaped Seal.**—Black steatite.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate IV.

DESCRIPTION : Inscribed on the base with the prenomen of Thothmes III between horizontal lines. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

TECHNIQUE : very coarse.

PRESERVATION : slightly chipped.

- 37341. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate VIII.

DESCRIPTION : Inscribed with the name of Shu, son of Ra. *Back*, see Plate XXII.

DATE : Nineteenth Dynasty (?).

GLAZE : pale grey blue-green.

TECHNIQUE : very good.

PRESERVATION : perfect.

- 37342. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '007.—Plate VIII.

DESCRIPTION : Inscribed with the name Shu, son of Ra. *Back*, see Plate XXII.

DATE : Nineteenth Dynasty (?).

GLAZE : pale green, going brown.

TECHNIQUE : very delicate.

PRESERVATION : perfect.

- 37343. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate VIII.

DESCRIPTION: Inscribed with the name of Shu, son of Ra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone whity-grey.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37344. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '004.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated, but no elytra marked.

DATE: Eighteenth Dynasty.

GLAZE: pale bluey-green.

TECHNIQUE: poor.

PRESERVATION: perfect.

- 37345. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate IV.

DESCRIPTION: Inscribed on the base with the name Men-kheper between two *nub*-signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

GLAZE: dark green.

TECHNIQUE: rough.

PRESERVATION: back chipped.

- 37346. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '009. Width, 0 m '006. Height, 0 m '004.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: dark blue-green.

TECHNIQUE: coarse.

PRESERVATION: perfect.

*Catal. du Musée*, n. 36001.

43

**37347. Scarab-shaped Seal.**—Paste.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '005.—Plate X

DESCRIPTION: Inscribed on the base with hieroglyphics reading Ra-neb-ha (*cf.* Nos. 36498, 37081, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: violet.

TECHNIQUE: fair.

PRESERVATION: perfect.

**37348. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '009. Width, 0 m '007. Height, 0 m '004.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax indicated but no elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone dark grey.

TECHNIQUE: fair.

PRESERVATION: back much worn.

**37349. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '005.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with human-headed handle from which two uraei are suspended (*cf.* Nos. 36993, 37073). *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone greyish white.

TECHNIQUE: very good.

PRESERVATION: perfect.

**37350. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate IX.

DESCRIPTION: Inscribed on the base with a seated figure of the god Amen (?) wearing the double feathers, and holding in his hand an *uas*-sceptre. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty (?).

GLAZE: pale green, going white.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

- 37351. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '004.—Plate IX.

DESCRIPTION: Inscribed on the base with a squatting figure of Maat. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale dull pea-green.

TECHNIQUE: very good.

PRESERVATION: head chipped.

- 37352. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '005.—Plate X.

DESCRIPTION: Inscribed on the base with a figure of a sistrum with uraei on either side and a *neb*-sign below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

GLAZE: dull pea-green.

TECHNIQUE: modelling very good, cutting good.

PRESERVATION: perfect.

- 37353. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: pale green, going brown.

TECHNIQUE: coarse.

PRESERVATION: good.

- 37354. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.—Plate X.

DESCRIPTION: Inscribed on the back with a legend of doubtful meaning. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty or later.

GLAZE: dark indigo-blue.

TECHNIQUE: good.

PRESERVATION: chipped.

**37355. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '005.—Plate X.

DESCRIPTION: Inscribed on the base with hieroglyphs reading *Ra-ha-neb* (cf. Nos. 36496, 36497, etc.). *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: sky-blue, of fine quality.

TECHNIQUE: good.

PRESERVATION: perfect.

**37356. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a flying vulture and a beetle with outspread wings. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue, gone grey-white.

TECHNIQUE: modelling fine, cutting good.

PRESERVATION: perfect.

**37357. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '00(?)—Plate XV.

DESCRIPTION: Inscribed on the base with hieroglyphic signs (cf. Nos. 36923, 37095). *Back*, cut away.

DATE: Nineteenth Dynasty.

GLAZE: blue-green, gone brown, nacreous and crackled.

TECHNIQUE: fair.

PRESERVATION: back cut away.

**37358. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '015. Width, 0 m '012. Height, 0 m '006.—Plate VIII.

DESCRIPTION: Inscribed on the base with a figure of a hawk and uræus upon a *neb*-sign, above is a flying scarabæus beetle. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

GLAZE: green, gone a pale yellow.

TECHNIQUE: modelling good, back fair.

PRESERVATION: perfect.

- 37359. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·012. Height, 0 m ·006.—Plate XV.

DESCRIPTION: Inscribed on the base with a *hes*-sign between two urai, while surrounding the whole is a rope-pattern border (*cf.* No. 37128). *Back*, see Plate XXII.

DATE: Nineteenth Dynasty or later.

GLAZE: pale olive green, going brown.

TECHNIQUE: fair.

PRESERVATION: edge chipped.

- 37360. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·014. Width, 0 m ·011. Height, 0 m ·007.—Plate XIV.

DESCRIPTION: Inscribed on the base with the figure of a horse. *Back*, rounded and prothorax marked.

DATE: Nineteenth Dynasty.

GLAZE: dark blue, gone dark yellow-green.

TECHNIQUE: very poor.

PRESERVATION: perfect.

- 37361. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.—Plate X.

DESCRIPTION: Inscribed on the base with a legend of doubtful meaning. *Back*, rounded prothorax and elytra marked, no legs indicated.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale blue, going white.

TECHNIQUE: modelling fair, cutting medium.

PRESERVATION: perfect.

- 37362. Scarab-shaped Seal.**—Black steatite.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate VIII.

DESCRIPTION: Inscribed with the name of Ptah with a *neb*-sign below. *Back*, as No. 37131, see Plate XIX.

DATE: Nineteenth Dynasty (?).

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: much worn.



- 37363. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XV.

DESCRIPTION: Inscribed on the base with figures of three urai with feathers upon their heads. *Back*, with prothorax slightly indicated but no elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: pale blue, gone brown in places.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

- 37364. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '009.—Plate XVII.

DESCRIPTION: Inscribed with the name of the chancellor, Per-em-uah, between vertical lines. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: modelling good, cutting fair.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 36872.

- 37365. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '008.—Plate XVII.

DESCRIPTION: Coil patterns ending in flowers. *Back*, Shesha type.

DATE: Hyksos Period.

GLAZE: green, turned brown.

TECHNIQUE: modelling coarsish, cutting good.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 36872.

- 37366. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '01.—Plate XVII.

DESCRIPTION: Inscribed with the name and titles of an official. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

GLAZE: blue (?).

TECHNIQUE: fair.

PRESERVATION: broken into three pieces and worn.

BIBL: *Journal d'entrée du Musée*, No. 3682 . . . .

- 37367. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·007.—Plate XVII.

DESCRIPTION: Inscribed with legend reading *mery Amen-ra*. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone light brown.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 335 . . . .

- 37368. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·016. Width, 0 m ·011. Height, 0 m ·008.—Plate XVI.—Naucratis (1899).

DESCRIPTION: Inscribed on the base with a figure of Bes between two cobras. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone grey.

TECHNIQUE: medium.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, F.

- 37369. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·031. Width, 0 m ·021. Height, 0 m ·013.—Plate XVII.—Naucratis (1899).

DESCRIPTION: A *heper*-sign between two *ta*-signs; above, a *hes*-vase between two cobras, and below, a *neb*-sign. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone grey.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, B.

- 37370. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·009.—Plate XVII.—Naucratis (1899).

DESCRIPTION: A sphinx with hieroglyphic signs above and below. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green.

TECHNIQUE: fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, G.

- 37371. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '009.—Plate XVII.—Naucratis (1899).

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; on either side, a feather and *ra*-sign, and below, a canoe. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, D.

- 37372. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '013. Height, 0 m '009.—Plate XVII.

DESCRIPTION: Inscribed with the prenomen of Thothmes III within a cartouche; before it, a *nefer*-sign and cobra, and on either side, hieroglyphics. *Back*, without prothorax or elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark blue, going white.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 33593, E.

- 37373. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '015. Height, 0 m '01.—Plate XVII.—Naucratis (1899).

DESCRIPTION: Standing figure of Ptah, holding *uas*-scepter; before him two *ded*-signs with hawks above. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593.

- 37374. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '016. Height, 0 m '009.—Plate XVII.—Naucratis (1899).

DESCRIPTION: An obelisk with cynocephali on either side; above, a *ra*-sign and crescent; below, a *neb*-sign. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: dark blue, gone whitish.

TECHNIQUE: medium.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, C.

- 37375. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XVII.—Naucratis (1899).

DESCRIPTION: Inscribed on the base with a standing figure of the god Harpocrates, with hieroglyphs in the field. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: blue, turned white.

TECHNIQUE: very good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, J.

- 37376. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '033. Width, 0 m '025. Height, 0 m '015.—Plate XVII.—Naucratis (1899).

DESCRIPTION: Inscribed with the prenomen of Thothmes III. *Back*, rounded prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: very rough.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 33593, A.

- 37377. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XVII.—Naucratis.

DESCRIPTION: Inscribed with the prenomen of Thothmes III with legend *scp-ca-ra* below. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Nineteenth Dynasty.

GLAZE: green, gone white.

TECHNIQUE: coarsish.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 33593, I.

- 37378. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '021. Width, 0 m '016. Height, 0 m '008.—Plate XVII.

DESCRIPTION: A *kheper*-sign between two cobras; below, a *nub*-sign. *Back*, see Plate XVII. Mounted in a gold fundu.

DATE: Nineteenth Dynasty.

GLAZE: dark green, going white.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 25181. Given by M. CAREY, 1882. MASPERO, *Slip. Cat.*, No. 1697. PETRIE, *Hist. Scarabs*, No. 162.

*Catal. du Musée*, n. 36001.

44

- 37379. Scarab-shaped Seal.**—Paste, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XII.

DESCRIPTION: Inscribed on the base with a series of *nefer*-signs, arranged in three rows, with horizontal lines between each row. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

PASTE: pale blue-green.

TECHNIQUE: cutting coarsish, modelling good.

PRESERVATION: slightly chipped.

- 37380. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the name and title of Queen Nefret-ari. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair cutting and modelling.

PRESERVATION: good.

- 37381. Scarab-shaped Seal.**—Paste.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '006.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a hawk-headed lion; below is a *neb*-sign. *Back*, prothorax and elytra marked.

DATE: Early Eighteenth Dynasy.

PASTE: pale pea-green.

TECHNIQUE: cutting good, modelling poor.

PRESERVATION: perfect.

- 37382. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '005.—Plate XII.

DESCRIPTION: Inscribed on the base with the figure of a cobra standing on a *neb*-sign; on either side an *ankh*-sign. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: fair cutting and modelling.

PRESERVATION: back chipped.

- 37383. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·015. Width, 0 m ·011. Height, 0 m ·007.—Plate XII.

DESCRIPTION: Inscribed on the base with the titles of a king within an oval; around are hieroglyphic signs. *Back*, prothorax indicated but no elytra marked.

DATE: Early Eighteenth Dynasty (Amenhetep).

GLAZE: blue-green, gone greyish.

TECHNIQUE: good cutting and modelling.

PRESERVATION: perfect.

- 37384. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·007.—Plate XII.

DESCRIPTION: Inscribed on the base with the name of Amen-Ra, with an *uab*-sign above and a *neb*-sign below. *Back*, without prothorax or elytra marked.

DATE: Late Eighteenth Dynasty.

GLAZE: green, going brown.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: fair.

- 37385. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with the name of Amen-Ra. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: pale green.

TECHNIQUE: cutting poor, modelling delicate.

PRESERVATION: perfect.

- 37386. Scarab-shaped Seal.**—Dark grey stone.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·005.—Plate XII.

DESCRIPTION: Inscribed on the base with the name of Amen; a *neb*-sign below. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: cutting scratchy, modelling good.

PRESERVATION: perfect.

**37387. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '009.—Plate XVII.

DESCRIPTION: Inscribed on the base with the figure of a king between the gods Horus and Anubis; above is a seated sphinx with a *men*-sign over its back. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: gone grey.

TECHNIQUE: fine modelling, cutting good.

PRESERVATION: back slightly flaked.

**37388. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '011.—Plate XVII.

DESCRIPTION: Inscribed on the base with the figure of a king seated with two deities standing behind him; above is a winged disc. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

GLAZE: blue, gone grey.

TECHNIQUE: coarsish cutting, modelling coarse.

PRESERVATION: badly chipped on sides and edges.

**37389. Scarab.**—Steatite, glazed.—Length, 0 m '076. Width, 0 m '052. Height, 0 m '03.—Plate XVII.

DESCRIPTION: Inscribed with the text of Amenhetep III's lion hunt. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Eighteenth Dynasty.

GLAZE: dark green-blue, of poor quality and badly burnt.

TECHNIQUE: modelling coarse, cutting fair.

PRESERVATION: edges much chipped.

**37390. Scarab.**—Steatite.—Length, 0 m '06. Width, 0 m '045. Height, 0 m '025.—Abydos.

DESCRIPTION: Inscribed with the text recording Amenhetep III's lion hunt. *Back*, prothorax and elytra marked, with a V on either wing-case. The prenomen of Amenhetep III is inscribed on the legs on both sides.

DATE: Eighteenth Dynasty.

GLAZE: green, gone grey.

TECHNIQUE: modelling fair, cutting good.

PRESERVATION: edges worn and chipped.

BIBL: On label, "Abydos."

- 37391. Scarab.**—Steatite, glazed.—Length, 0 m .085. Width, 0 m .055.  
Height, 0 m .025.

DESCRIPTION: Inscribed with the text of Amenhetep III's lion hunt. *Back*, flaked away.

DATE: Late Eighteenth Dynasty.

GLAZE: blue, gone white.

TECHNIQUE: fair.

PRESERVATION: back flaked away and badly damaged by salt.

- 37392. Scarab.**—Steatite, glazed.—Length, 0 m .045. Width, 0 m .055.  
Height, 0 m .03.—Mitraheny.

DESCRIPTION: Lower half of a scarab inscribed with the text of Amenhetep III's lion hunt. Four and a half lines of text. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Eighteenth Dynasty.

GLAZE: dark blue-green.

TECHNIQUE: fair.

PRESERVATION: back flaked.

BIBL: On label, "Mitraheny."

- 37393. Scarab.**—Steatite, glazed.—Length, 0 m .098. Width, 0 m .065.  
Height, 0 m .036.—Plate XVII.

DESCRIPTION: Inscribed with the text naming Queen Thÿi's parents and recording the limits of Amenhetep III's empire. *Back*, prothorax and elytra marked, with a **V** on either wing-case.

DATE: Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: slightly chipped.

BIBL: *Journal d'entr e du Mus e*, No. 25848. Bought.

- 37394. Scarab.**—Steatite, glazed.—Length, 0 m .067. Width, 0 m .048.  
Height, 0 m .025.

DESCRIPTION: Inscribed with similar text to that on No. 37393. *Back*, flaked off.

DATE: Late Eighteenth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair.

PRESERVATION: back flaked off and badly chipped.



- 37395. Fragment of a Scarab.**—Steatite, glazed.—Length, 0 m '065.  
Width, 0 m '04. Height, 0 m '014.—Mitrahény (1904).

DESCRIPTION : Inscribed with similar text to No. 37393.

DATE : Late Eighteenth Dynasty.

GLAZE : green.

TECHNIQUE : fair.

PRESERVATION : only a fragment remains.

- 37396. Fragment of a Scarab-shaped Seal.**—Pottery, glazed.—Length,  
0 m '05. Width, 0 m '05. Height, 0 m '03.—Plate XVII.

DESCRIPTION : Inscribed with the names and titles of Rameses II. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Nineteenth Dynasty.

GLAZE : blue (?), gone white.

TECHNIQUE : fair.

PRESERVATION : upper half only remains. Badly chipped and rubbed.

- 37397. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '051. Width,  
0 m '034. Height, 0 m '018.—Plate XVII.—Memphis.

DESCRIPTION : Inscribed with the name of Sha-ba-ka within a cartouche ; on either side a cynocephalus seated upon a *neb*-sign with a feather in front and an *uaz*-eye above. On the back is the cartouche of Nefer-ka-ra surmounted by double feathers with uræi on either side, and a lotus flower below.

DATE : Twenty-sixth Dynasty.

GLAZE : dark greeny-brown.

TECHNIQUE : very good.

PRESERVATION : slightly chipped on surface.

BIBL : MASPERO, *Stip Cat.*, No. 3786. PETRIE, *Hist. Scarabs*, No. 1886.

- 37398. Scarab-shaped Seal.**—Paste.—Length, 0 m '04. Width, 0 m '028.  
Height, 0 m '022.—Plate XVII.

DESCRIPTION : Inscribed with the prenom and nomen of Aahmes II with titles above. *Back*, modelled with the legs of a beetle with a ram's head, and on the back a Hathor head with uræi on either side, and a lotus flower below.

DATE : Twenty-sixth Dynasty.

PASTE : blue-green.

TECHNIQUE : well modelled and fine cutting.

PRESERVATION : worn on surface.

- 37399. Scarab.**—Dark green basalt.—Length, 0 m '063. Width, 0 m '041. Height, 0 m '028.—Plate XVII.

DESCRIPTION: Inscribed with an historical text of Nekau. In the division above is a standing figure of the king attended by Neith and Hathor. Below are prisoners with arms tied behind. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Twenty-sixth Dynasty.

TECHNIQUE: fine modelling and cutting.

PRESERVATION: perfect.

BIBL.: MAR. *Album photographique de Musée du Boulaq*, Plate XXXVI. MAR. *Mon. Divers*, Plate XLVIII c.

- 37400. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Sat-Hather *nebt amakh*. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: green, gone a yellowy-white.

TECHNIQUE: very delicate.

PRESERVATION: slightly chipped on edge.

BIBL.: *Journal d'entrée du Musée*, No. 30873. DE MORGAN, *Dahchour*, I, fig. 133.

- 37401. Scarab-shaped Seal.**—Amethyst and gold.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the gold plate with the prenom of Senusret III, with continuous loop pattern on either side. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very delicate.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30870. DE MORGAN, *Dahchour*, Plate XVI, 19 and fig. 132.

- 37402. Scarab-shaped Seal.**—Amethyst and gold.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the gold plate with two *sam*-signs being tied by figures of the Nile god. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very delicate.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, Plate XVI, 19, and fig. 134.

**37403. Scarab-shaped Seal.**—Turquoise.—Length, 0 m ·014. Width, 0 m ·009. Height, 0 m ·006.—Plate XVIII.

DESCRIPTION: No inscription or design. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very delicate.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, p. 62, No. 22.

**37404. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·004.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Merÿt. A silver wire in the piercing. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very fine, legs deeply cut.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, fig. 147.

**37405. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·017. Width, 0 m ·012. Height, 0 m ·007.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Merÿt. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very fine.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, fig. 152.

**37406. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m ·016. Width, 0 m ·01. Height, 0 m ·007.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Mererÿt. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entr e du Mus e*, No. 30913. Not in DE MORGAN's publication.

- 37407. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m .01. Width, 0 m .007. Height, 0 m .005.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Mererÿt, *neb amakh*.  
*Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fine, legs pierced through width.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, fig. 150.

- 37408. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .011. Width, 0 m .007. Height, 0 m .005.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the name of the Princess Mererÿt, *neb amakh*. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: very fine, legs pierced through width.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, fig. 153.

- 37409. Scarab-shaped Seal.**—Gold and turquoise.—Length, 0 m .015. Width, 0 m .009. Height, 0 m .006.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the base with double *sem*-signs and papyrus and lotus flowers. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: a gold base and frame inlaid with small pieces of turquoise. Fine work.

PRESERVATION: one piece of leg wanting.

BIBL.: DE MORGAN, *Dahchour*, Plate XIX, fig. 35.

- 37410. Scarab-shaped Seal.**—Gold, lapis lazuli, and beryl.—Length, 0 m .014. Width, 0 m .01. Height, 0 m .008.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the titles of a queen. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: base of lapis lazuli, head of lapis lazuli, thorax and wings of beryl, with lapis lazuli between, gold plate on base, splendid workmanship.

PRESERVATION: piece of head wanting, otherwise perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30916. DE MORGAN, *Dahchour*, I, Plate XIX, fig. 37.

*Catal. du Musée*, n. 36001.

45

**37411. Scarab-shaped Seal.**—Lapis lazuli and gold.—Length, 0 m '018. Width, 0 m '012. Height, 0 m '008.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the gold plate with the prenomen and titles of Amenemhat III. A gold wire through piercing and twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine, pierced transversely with three holes.

PRESERVATION: legs wanting.

BIBL.: *Journal d'entrée du Musée*, No. 30891. DE MORGAN, *Dahchour*, I, fig. 148.

**37412. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the titles of a queen. A gold wire through piercing, twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine, lapis lazuli base, with a green stone body inlaid with lapis lazuli wings and thorax.

PRESERVATION: thorax inlay wanting, otherwise perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30902. DE MORGAN, *Dahchour*, I, Plate XX, fig. 48 b.

**37413. Scarab-shaped Seal.**—Beryl.—Length, 0 m '009. Width, 0 m '005. Height, 0 m '004.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the prenomen of Amenemhat III. Mounted on a gold wire twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: very brilliant cutting and highly polished.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30898. DE MORGAN, *Dahchour*, I, fig. 149.

**37414. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '005.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed with the titles of a queen. Mounted on a gold wire twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

GLAZE: blue (?), gone yellow.

TECHNIQUE: very fine.

PRESERVATION: perfect.

BIBL.: *Journal d'entrée du Musée*, No. 30904. DE MORGAN, *Dahchour*, I, fig. 151.

- 37415. Scarab-shaped Seal.**—Lapis lazuli and gold.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '007.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the gold plate with the title of Queen of the King of Lower Egypt. Mounted on a gold wire twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: fine work.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, fig. 146.

- 37416. Scarab-shaped Seal.**—Gold, lapis lazuli, and turquoise.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.—Plate XVIII.—Dahchour.

DESCRIPTION: Inscribed on the gold plate with the titles of a queen. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: the base is a solid gold plate, the edges of which are inlaid with alternate rectangles of lapis and turquoise. The wings are of lapis.

PRESERVATION: thorax inlay wanting, otherwise perfect.

BIBL.: *Journal d'entr e du Mus e*, No. 30907. DE MORGAN, *Dahchour*, I, Plate XX, fig. 52.

- 37417. Scarab-shaped Seal.**—Gold and lapis lazuli.—Length, 0 m '012. Width, 0 m '008. Height, 0 m '005.—Plate XVIII.—Dahchour.

DESCRIPTION: Uninscribed. Mounted on a gold wire twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: the lapis lazuli body and wings is fixed on a solid gold base. Very fine modelling and brilliant polish.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, p. 70, No. 52.

- 37418. Scarab-shaped Seal.**—Turquoise.—Length, 0 m '013. Width, 0 m '008. Height, 0 m '005.—Dahchour.

DESCRIPTION: Uninscribed. Mounted on a gold wire twisted behind to form a ring. *Back*, similar to No. 37417.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine modelling and brilliant polish.

PRESERVATION: perfect.

BIBL.: DE MORGAN, *Dahchour*, I, p. 62, No. 22, Plate XVI.

- 37419. Scarab-shaped Seal.**—Gold, beryl, and lapis lazuli.—Length, 0 m ·015  
Width, 0 m ·01. Height, 0 m ·006.—Plate XVIII.—Dahchour.

DESCRIPTION: Uninscribed. Mounted on a gold wire twisted behind to form a ring. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: splendid workmanship. Gold plate base, with legs of lapis and emerald stone, and back inlaid on gold with head of emerald stone, thorax of carnelian, and wing-cases of lapis and emerald stone.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I, Plate XX, fig. 35.

- 37420. Scarab-shaped Seal.**—Amethyst.—Length, 0 m ·011. Width, 0 m ·007.  
Height, 0 m ·006.—Plate XVIII.—Dahchour.

DESCRIPTION: Uninscribed. Mounted on a gold wire twisted behind to form a ring. A gold base. *Back*, see Plate XVIII.

DATE: Twelfth Dynasty.

TECHNIQUE: splendid modelling and brilliant polish.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I, p. 70, No. 54.

- 37421. Scarab-shaped Seal.**—Amethyst.—Length, 0 m ·016. Width, 0 m ·011.  
Height, 0 m ·008.—Dahchour.

DESCRIPTION: Uninscribed. Mounted on a gold plate. *Back*, see Plate XXI.

DATE: Twelfth Dynasty.

TECHNIQUE: splendid modelling.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I, p. 70, No. 48.

- 37422. Scarab-shaped Seal.**—Amethyst.—Length, 0 m ·018. Width, 0 m ·012.  
Height, 0 m ·008.—Dahchour.

DESCRIPTION: Uninscribed. *Back*, similar to No. 37401.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine modelling.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I.

- 37423. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '007.—Dahchour.

DESCRIPTION: Uninscribed. *Back*, similar to No. 37401.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine modelling.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I, p. 70, No. 50.

- 37424. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '016. Width, 0 m '011. Height, 0 m '008.—Dahchour.

DESCRIPTION: Uninscribed. *Back*, similar to No. 37401.

DATE: Twelfth Dynasty.

TECHNIQUE: very fine modelling.

PRESERVATION: perfect.

BIBL: DE MORGAN, *Dahchour*, I, p. 70, No. 51.

- 37425. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '008.—Plate XVIII.

DESCRIPTION: Inscribed on the base with the prenomen of Thothmes III within a cartouche, with hieroglyphic signs on either side. *Back*, see Plate XVIII. Set as a swivel in a bronze hoop ring with wire coils.

DATE: Middle Eighteenth Dynasty.

GLAZE: gone white.

TECHNIQUE: fine cutting and modelling.

PRESERVATION: perfect. Bronze hoop slightly corroded.

- 37426. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '02. Width, 0 m '015. Height, 0 m '009.—Plate XVIII.

DESCRIPTION: Inscribed on the base with the prenomen of Piankhy and the nomen of Queen Isit-em-kheb. *Back*, prothorax and elytra marked. Mounted in an ivory funda with gold ends for swivel.

DATE: Twenty-fourth Dynasty.

GLAZE: green, gone brown.

TECHNIQUE: fair cutting and modelling coarsish.

PRESERVATION: good.



**37427. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '019. Width, 0 m '014. Height, 0 m '01.—Plate XVII.

DESCRIPTION: Inscribed on the base with the nomen of Rameses mery-amen and a hieroglyphic legend. *Back*, prothorax and elytra marked.

DATE: Nineteenth or Twentieth Dynasty.

GLAZE: blue green.

TECHNIQUE: fair.

PRESERVATION: good.

**37428. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked. Mounted in a gold fundu ornamented with granulated gold work.

DATE: Eighteenth Dynasty.

TECHNIQUE: modelling coarsish.

PRESERVATION: fair.

**37429. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '006.—Plate XVIII.

DESCRIPTION: Inscribed on the base with a series of three double coils. *Back*, see Plate XVIII. Set in a gold fundu with a thin gold hoop ring, the maximum diameter of which is 0 m '002.

DATE: Hyksos Period.

GLAZE: gone grey.

TECHNIQUE: fair.

PRESERVATION: back much worn.

**37430. Scarab-shaped Seal.**—Bronze.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.—Plate XVIII.

DESCRIPTION: Inscribed on the base with the name of Amen-ra and a hieroglyphic legend. *Back*, see Plate XVIII. Set as a swivel in a bronze hoop to which it is attached by a bronze pin.

DATE: Eighteenth or Nineteenth Dynasty.

TECHNIQUE: well cut and modelled.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cut.*, No. 4198.

- 37431. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.—Plate XVIII.

DESCRIPTION: Inscribed on the base with a figure of Tauris standing and holding a knife. *Back*, see Plate XVIII. Set as a swivel to a silver ornamented hoop by means of a silver wire.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: very good cutting and modelling.

PRESERVATION: perfect.

- 37432. Scarab-shaped Seal.**—Steatite, glazed. Length, 0 m '012. Width, 0 m '008. Height, 0 m '006.—Plate XVIII.

DESCRIPTION: Engraved on the base with hieroglyphic (?) signs. *Back*, see Plate XVIII. Mounted in a gold fundu and set so as to form the swivel to a silver ring. The threading wire is coiled several times round the hoop.

DATE: Eighteenth Dynasty (?).

GLAZE: gone white.

TECHNIQUE: well cut and modelled.

PRESERVATION: seal well preserved, but silver ring much corroded.

- 37433. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.—Plate XVIII.

DESCRIPTION: Inscribed on the base with the titles of a king and the name *Nefer-ah*. *Back*, see Plate XVIII. Set so as to form the swivel to a silver ring.

DATE: Twenty-sixth Dynasty (?).

GLAZE: green.

TECHNIQUE: cutting poor, but modelling fair.

PRESERVATION: back chipped.

- 37434. Scarab-shaped Seal.**—Dark blue, opaque glass.—Length, 0 m '02. Width, 0 m '014. Height, 0 m '01.—Plate XVIII.

DESCRIPTION: Inscribed on the base with figures of Ptah and Sekhmet. *Back*, see Plate XVIII. Set so as to form the swivel to a bronze ring.

DATE: Eighteenth Dynasty (Amenhetep III ?).

TECHNIQUE: back finely modelled, cutting poor.

PRESERVATION: excellent.

BIBL.: *Journal d'entrée du Musée*, No. 30419.

- 37435. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '012. Height, 0 m '007.—Plate XVIII.

DESCRIPTION: Inscribed on the base with a figure of Tahuti as a cynocephalus, and the legend *neb khemenu*. For the ornamented back see Plate XVIII. Set so as to form the swivel to a bronze ring.

DATE: Nineteenth Dynasty (?).

TECHNIQUE: modelling fine, cutting fair.

PRESERVATION: chipped on base, bronze slightly corroded.

- 37436. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.—Plate XVII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs, arranged in two vertical columns with a line between. *Back*, Shesha type. Set in a gold fundu.

DATE: Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: coarse.

PRESERVATION: head badly chipped.

- 37437. Scarab-shaped Seal.**—Paste.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '008.—Plate XVII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs. *Back*, inscribed with hieroglyphic signs (see Plate XVII).

DATE: Nineteenth Dynasty or later.

PASTE: dull pea-green, turning brown.

TECHNIQUE: fair.

PRESERVATION: good.

- 37438. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '019. Width, 0 m '013. Height, 0 m '01.—Plate XVII.

DESCRIPTION: Inscribed on the base with hieroglyphic signs, and two double scrolls in ovals on either side. *Back*, prothorax slightly indicated, no elytra marked

DATE: Twelfth Dynasty or Hyksos Period.

GLAZE: green, gone brown.

TECHNIQUE: fine cutting.

PRESERVATION: good.

- 37439. Scarab-shaped Seal.**—Gold.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, with a V on either wing-case. Mounted as a swivel ring with gold hoop and gold wire coils.

DATE: Eighteenth Dynasty (?).

TECHNIQUE: coarsish modelling.

PRESERVATION: perfect.

- 37440. Scarab-shaped Seal.**—Green serpentine.—Length, 0 m '02. Width, 0 m '013. Height, 0 m '008.

DESCRIPTION: Inscribed on the base with the title *uwm* and name Neferhetep. *Back*, prothorax and elytra marked. Mounted in a gold funda ornamented with a herring-bone around the edge of wire-work, and set in a narrow gold hoop-ring.

DATE: Thirteenth—Seventeenth Dynasty.

TECHNIQUE: excellent modelling, cutting medium.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 29405.

- 37441. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '007. Width, 0 m '004. Height, 0 m '003.

DESCRIPTION: Inscribed on the base with the name of the god Amen. *Back*, prothorax and elytra marked. Mounted in a gold funda, and set as a swivel ring with gold hoop and gold wire coils.

DATE: Eighteenth Dynasty (?).

GLAZE: green.

TECHNIQUE: excellent.

PRESERVATION: perfect.

BIBL: *Journal d'entrée du Musée*, No. 29837.

- 37442. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION: Inscribed on the base with the signs Ra-ankh . . . . *Back*, prothorax and elytra marked. Mounted in a gold funda, and set as a swivel-ring with gold hoop and gold wire coils.

DATE: Twelfth Dynasty or Intermediate Period.

TECHNIQUE: excellent.

PRESERVATION: a sign after the *ankh* is destroyed, otherwise perfect.

*Catal. du Musée*, n. 36001.

46

- 37443. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '014. Width, 0 m '011. Height, 0 m '007.

DESCRIPTION: Inscribed on the base with a *nefer*-sign between two *neb*-signs. *Back*, prothorax and elytra marked. Mounted as a swivel ring with gold hoop and gold wire coils.

DATE: Eighteenth Dynasty.

TECHNIQUE: excellent.

PRESERVATION: good.

- 37444. Scarab-shaped Seal.**—Steatite.—Length, 0 m '015. Width, 0 m '011. Height, 0 m '007.

DESCRIPTION: Inscribed on the base with three *uaz*-signs above a *nub*-sign; on either side are *ankhs*. *Back*, Shesha type. Mounted in a gold funda, and set as a swivel ring with gold hoop and gold wire coils.

DATE: Hyksos Period.

TECHNIQUE: excellent.

PRESERVATION: good.

- 37445. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '016. Width, 0 m '013. Height, 0 m '01.

DESCRIPTION: Inscribed on the base with a double coil, with *nefer*-signs on either side. *Back*, prothorax and elytra marked. Set as a swivel ring with gold hoop and gold wire coils.

DATE: Early Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: coarsish.

PRESERVATION: back slightly flaked.

- 37446. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION: Inscribed on the base with a figure of Maat, a *nefer*-sign, and a feather; below is a *neb*-sign, and above a winged disk. *Back*, prothorax and elytra marked. Set as a swivel ring with gold hoop and gold wire coils.

DATE: Eighteenth Dynasty.

GLAZE: green.

TECHNIQUE: fair.

PRESERVATION: perfect.

- 37447. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION: Inscribed on the base with a *shen*-ring above a *nub*-sign, and an *ankh* on either side. *Back*, without prothorax or elytra marked. Mounted in a heavy broad gold funda.

DATE: Hyksos Period.

GLAZE: blue.

TECHNIQUE: good.

PRESERVATION: excellent.

- 37448. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '017. Width, 0 m '012. Height, 0 m '007.

DESCRIPTION: Inscribed on the base with a series of interwoven coils. *Back* covered with a gold plate. Mounted in a gold funda.

DATE: Hyksos Period or Seventeenth Dynasty.

GLAZE: green.

TECHNIQUE: good.

PRESERVATION: excellent.

- 37449. Scarab-shaped Seal.**—Hæmatite.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.

DESCRIPTION: Inscribed on the base with the legend *De Bast nefer*. *Back* prothorax and elytra marked. Mounted in a gold funda ornamented with granulated gold work.

DATE: Nineteenth Dynasty.

TECHNIQUE: very good.

PRESERVATION: excellent.

- 37450. Scarab-shaped Seal.**—Limestone (?), glazed.—Length, 0 m '083. Width, 0 m '06. Height, 0 m '025.

DESCRIPTION: Inscribed on the base with the figure of a hawk, with a disk and uræus above its back and a *mer*-sign below. *Back*, prothorax and elytra marked.

DATE: Twentieth Dynasty or later.

GLAZE: green.

TECHNIQUE: coarsish.

PRESERVATION: good.

BIBL.: *Journal d'entrée du Musée*, No. 26409.

- 37451. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '016. Width, 0 m '012.  
Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.  
DATE: Probably Hyksos Period.  
TECHNIQUE: Lumpy modelling.  
PRESERVATION: good.  
BIBL.: MASPERO, *Slip Cat.*, No. 4567.

- 37452. Scarab-shaped Seal.**—Limestone.—Length, 0 m '022. Width, 0 m '016.  
Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, originally inlaid.  
DATE: Early Eighteenth Dynasty.  
TECHNIQUE: medium.  
PRESERVATION: inlay of back lost.  
BIBL.: MASPERO, *Slip Cat.*, No. 4566.

- 37453. Scarab-shaped Seal.**—Green jasper.—Length, 0 m '017. Width,  
0 m '014. Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, not pierced.  
DATE: Nineteenth Dynasty.  
TECHNIQUE: coarse modelling.  
PRESERVATION: good.  
BIBL.: MASPERO, *Slip Cat.*, No. 4566.

- 37454. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '015. Width, 0 m '01.  
Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra.  
DATE: Hyksos Period.  
TECHNIQUE: lumpy modelling.  
PRESERVATION: good.  
BIBL.: MASPERO, *Slip Cat.*, No. 4575 B.

- 37455. Scarab-shaped Seal.**—Black obsidian.—Length, 0 m '021. Width, 0 m '015. Height, 0 m '001.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

TECHNIQUE: fair modelling.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4575 B.

- 37456. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '009.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Thothmes III.

TECHNIQUE: fine modelling.

PRESERVATION: head chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 4575 B.

- 37457. Scarab-shaped Seal.**—White quartz.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: lumpy modelling.

PRESERVATION: chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 4575 B.

- 37458. Scarab-shaped Seal.**—White quartz.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '007.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period (?).

TECHNIQUE: poor.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4575 B.



- 37459. Scarab-shaped Seal.**—Amethyst.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·009.

DESCRIPTION: Inscribed on the base with a figure of Tahuti as a cynocephalus and the legend *neb khemenu*. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Amenhetep III.

TECHNIQUE: fair modelling, cutting coarse.

PRESERVATION: perfect.

BIBL: MASPERO, *Slip Cat.*, No. 4575 B.

- 37460. Scarab-shaped Seal.**—Hæmatite.—Length, 0 m ·015. Width, 0 m ·01. Height, 0 m ·006.

DESCRIPTION: Inscribed on the base with the name of Amen. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: coarse cutting and modelling.

PRESERVATION: edges chipped.

BIBL: MASPERO, *Slip Cat.*, No. 4575 B.

- 37461. Scarab-shaped Seal.**—Green serpentine.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: coarse modelling.

PRESERVATION: good.

BIBL: MASPERO, *Slip Cat.*, No. 4575.

- 37462. Scarab-shaped Seal.**—Amethyst.—Length, 0 m ·014. Width, 0 m ·01. Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: Hyksos Period.

TECHNIQUE: fair modelling.

PRESERVATION: head chipped.

BIBL: MASPERO, *Slip Cat.*, No. 4568.

- 37463. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '007.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

GLAZE : pale blue-green.

TECHNIQUE : finely modelled.

PRESERVATION : good.

BIBL : MASPERO, *Slip Cat.*, No. 4568.

- 37464. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '014. Width, 0 m '01. Height, 0 m '007.

DESCRIPTION : Uninscribed. *Back*, Shesha type.

DATE : Hyksos Period.

TECHNIQUE : fair.

PRESERVATION : perfect.

BIBL : MASPERO, *Slip Cat.*, No. 4568.

- 37465. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '001. Width, 0 m '007. Height, 0 m '005.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

TECHNIQUE : fair modelling.

PRESERVATION : perfect.

BIBL : MASPERO, *Slip Cat.*, No. 4568.

- 37466. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '013. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

TECHNIQUE : coarse modelling, not pierced.

PRESERVATION : fair.

BIBL : MASPERO, *Slip Cat.*, No. 4568.

- 37467. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m ·014. Width, 0 m ·009. Height, 0 m ·007.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

GLAZE : green, turned brown.

TECHNIQUE : modelling fair.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4568.

- 37468. Scarab-shaped Seal.**—Mother of Pearl.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

TECHNIQUE : modelling fair.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4568.

- 37469. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·011. Width, 0 m ·008. Height, 0 m ·006.

DESCRIPTION : Inscribed on the base with three crossed lines. *Back*, rounded prothorax and elytra marked.

DATE : Early Eighteenth Dynasty.

TECHNIQUE : fair modelling.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37470. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·01. Width, 0 m ·007. Height, 0 m ·005.

DESCRIPTION : Uninscribed. *Back*, without prothorax or elytra marked.

DATE : Early Eighteenth Dynasty.

TECHNIQUE : coarse modelling.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37471. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '01. Width, 0 m '007. Height, 0 m '004.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: coarsish modelling.

PRESERVATION: fair.

BIBL: MASPERO, *Slip Cat.*, No. 4569.

- 37472. Scarab-shaped Seal.**—Pottery, glazed.—Length, 0 m '011. Width, 0 m '007. Height, 0 m '005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Middle Eighteenth Dynasty.

GLAZE: blue.

TECHNIQUE: coarsely modelled.

PRESERVATION: good.

BIBL: MASPERO, *Slip Cat.*, No. 4569.

- 37473. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

TECHNIQUE: poor and coarse.

PRESERVATION: fair.

BIBL: MASPERO, *Slip Cat.*, No. 4569.

- 37474. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Late Eighteenth Dynasty.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL: MASPERO, *Slip Cat.*, No. 4569.

*Catal. du Musée*, n. 36001.

47

- 37475. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m ·011. Width, 0 m ·007. Height, 0 m ·005.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Middle Eighteenth Dynasty.

TECHNIQUE : medium.

PRESERVATION : fair.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37476. Scarab-shaped Seal.**—Brown jasper (?).—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.

DESCRIPTION : Uninscribed. *Back*, without prothorax or elytra marked.

DATE : Nineteenth Dynasty.

TECHNIQUE : medium.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37477. Scarab-shaped Seal.**—Brown jasper (?).—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Nineteenth Dynasty.

TECHNIQUE : fair.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37478. Scarab-shaped Seal.**—Brown jasper (?).—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·006.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Nineteenth Dynasty.

TECHNIQUE : fair.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4569.

- 37479. Scarab-shaped Seal.**—Stone (?), pale grey-green.—Length, 0 m '015.  
Width, 0 m '011. Height, 0 m '007.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37480. Scarab-shaped Seal.**—Black agate (?).—Length, 0 m '015. Width,  
0 m '011. Height, 0 m '007.

DESCRIPTION: Uninscribed. *Back*, Shesha type.

DATE: Hyksos Period.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4566.

- 37481. Scarab-shaped Seal.**—Dark green serpentine.—Length, 0 m '02.  
Width, 0 m '013. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, Shesha type.

DATE: Hyksos Period.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4566.

- 37482. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '02. Width, 0 m '013.  
Height, 0 m '009.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty.

TECHNIQUE: fine cutting.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4566.

- 37483. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '021. Width, 0 m '014.  
Height, 0 m '012.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: chipped.

BIBL.: MASPERO, *Stip Cat.*, No. 4566.

- 37484. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '02. Width, 0 m '015.  
Height, 0 m '011.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Stip Cat.*, No. 4566.

- 37485. Scarab-shaped Seal.**—Black serpentine.—Length, 0 m '017. Width,  
0 m '012. Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Stip Cat.*, No. 4566.

- 37486. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '02. Width, 0 m '013.  
Height, 0 m '01.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Thirteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Stip Cat.*, No. 4566.

- 37487. Scarab-shaped Seal.**—Green beryl.—Length, 0 m '018. Width, 0 m '013. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: good.

BIBL.: MASPERO, *Ship Cat.*, No. 4566.

- 37488. Scarab-shaped Seal.**—Amethyst.—Length, 0 m '015. Width, 0 m '01. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: Twelfth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Ship Cat.*, No. 4566.

- 37489. Scarab-shaped Seal.**—Rock crystal.—Length, 0 m '014. Width, 0 m '009. Height, 0 m '006.

DESCRIPTION: On the base a figure of a hawk. *Back*, prothorax and elytra marked.

DATE: Eighteenth Dynasty.

TECHNIQUE: medium.

PRESERVATION: good.

BIBL.: MASPERO, *Ship Cat.*, No. 4567.

- 37490. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '013. Width, 0 m '01. Height, 0 m '009.

DESCRIPTION: Uninscribed. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: good.

BIBL.: MASPERO, *Ship Cat.*, No. 4567.



- 37491. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '016. Width, 0 m '013.  
Height, 0 m '009.

DESCRIPTION : On the base a double coil. *Back*, Shesha type.

DATE : Hyksos Period.

TECHNIQUE : fair.

PRESERVATION : good.

BIBL. : MASPERO, *Slip Cat.*, No. 4567.

- 37492. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '019. Width, 0 m '012.  
Height, 0 m '009.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE : Late Eighteenth Dynasty.

TECHNIQUE : fair.

PRESERVATION : good.

BIBL. : MASP., *Slip Cat.*, No. 4567.

- 37493. Scarab-shaped Seal.**—Dark green serpentine.—Length, 0 m '018.  
Width, 0 m '011.—Height, 0 m '009.

DESCRIPTION : Uninscribed. *Back*, prothorax and elytra marked.

DATE : Eighteenth Dynasty.

TECHNIQUE : good.

PRESERVATION : fair.

BIBL. : MASPERO, *Slip Cat.*, No. 4567.

- 37494. Scarab-shaped Seal.**—Pale blue glass.—Length, 0 m '019. Width,  
0 m '014. Height, 0 m '01.

DESCRIPTION : On the base hieroglyphic signs with rope-pattern border. *Back*, rounded prothorax and elytra marked.

DATE : Early Eighteenth Dynasty.

TECHNIQUE : fair.

PRESERVATION : broken across middle.

BIBL. : MASPERO, *Slip Cat.*, No. 4567.

- 37495. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '018. Width, 0 m '012.  
Height, 0 m '009.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

- 37496. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '017. Width, 0 m '011.  
Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, rounded prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

- 37497. Scarab-shaped Seal.**—Green serpentine.—Length, 0 m '015. Width,  
0 m '01. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Twelfth Dynasty.

TECHNIQUE: good.

PRESERVATION: chipped on head.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

- 37498. Scarab-shaped Seal.**—Carnelian.—Length, 0 m '01. Width, 0 m '008.  
Height, 0 m '006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

**37499. Scarab-shaped Seal.**—Black obsidian.—Length, 0 m ·013. Width, 0 m ·01. Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

TECHNIQUE: good.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

**37500. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·013. Width, 0 m ·009. Height, 0 m ·007.

DESCRIPTION: Uninscribed. *Back*, without prothorax and elytra marked.

DATE: Early Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4567.

**37501. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·008. Width, 0 m ·006. Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

**37502. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·009. Width, 0 m ·006. Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37503. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '008.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Nineteenth Dynasty (?).

TECHNIQUE: coarse.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37504. Scarab-shaped Seal.**—Green jasper.—Length, 0 m '011. Width, 0 m '008. Height, 0 m '005.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: End of Twelfth Dynasty or Hyksos Period.

TECHNIQUE: good.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37505. Scarab-shaped Seal.**—Steatite, unglazed.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.

DESCRIPTION: Uninscribed. *Back*, Shesha type.

DATE: Hyksos Period.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37506. Scarab-shaped Seal.**—Green jasper.—Length, 0 m '012. Width, 0 m '009. Height, 0 m '005.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked.

DATE: Eighteenth Dynasty (?).

TECHNIQUE: good.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

*Catal. du Musée*, n. 36001.

48

- 37507. Scarab-shaped Seal.**—Pale blue glass (transparent).—Length, 0 m ·013.  
Width, 0 m ·009. Height, 0 m ·007.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: edges chipped.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37508. Scarab-shaped Seal.**—Violet blue glass.—Length, 0 m ·011. Width,  
0 m ·009. Height, 0 m ·006.

DESCRIPTION: Inscribed on the base with the signs *heg maa* and an oval. *Back*, prothorax and elytra marked, with a V on either wing-case.

DATE: Late Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: chipped on base.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37509. Scarab-shaped Seal.**—Agate (?).—Length, 0 m ·011. Width, 0 m ·008.  
Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, worn.

PRESERVATION: badly worn.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37510. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·01. Width, 0 m ·007.  
Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37511. Scarab-shaped Seal.**—Lapis lazuli.—Length, 0 m .009. Width, 0 m .007. Height, 0 m .006.

DESCRIPTION: Inscribed on the base with a hawk above three flower signs. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4571.

- 37512. Scarab-shaped Seal.**—Carnelian.—Length, 0 m .012. Width, 0 m .009. Height, 0 m .006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37513. Scarab-shaped Seal.**—Steatite, glazed.—Length, 0 m .012. Width, 0 m .008. Height, 0 m .007.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked, the latter with vertical lines down wing-cases.

DATE: Twenty-sixth Dynasty (?).

GLAZE: pale pea-green.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37514. Scarab-shaped Seal.**—Red jasper.—Length, 0 m .01. Width, 0 m .006. Height, 0 m .004.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37515. Scarab-shaped Seal.**—Hæmatite.—Length, 0 m ·011. Width, 0 m ·008.  
Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: good.

PRESERVATION: perfect.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37516. Scarab-shaped Seal.**—Carnelian.—Length, 0 m ·012. Width, 0 m ·009.  
Height, 0 m ·007.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: chipped on base.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37517. Scarab-shaped Seal.**—Hæmatite.—Length, 0 m ·012. Width, 0 m ·008.  
Height, 0 m ·007.

DESCRIPTION: Uninscribed. *Back*, as 37479.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37518. Scarab-shaped Seal.**—Black obsidian.—Length, 0 m ·012. Width,  
0 m ·008. Height, 0 m ·006.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty (?).

TECHNIQUE: coarse.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37519. Scarab-shaped Seal.**—Dark blue glass (transparent).—Length, 0 m ·01.  
Width, 0 m ·006. Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, without prothorax or elytra marked. Set in a silver fundus.

DATE: Eighteenth Dynasty (?).

TECHNIQUE: fair.

PRESERVATION: good.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37520. Scarab-shaped Seal.** Haematite.—Length, 0 m ·011. Width, 0 m ·008.  
Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: coarse.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.

- 37521. Scarab-shaped Seal.** Haematite.—Length, 0 m ·01. Width, 0 m ·005.  
Height, 0 m ·005.

DESCRIPTION: Uninscribed. *Back*, prothorax and elytra marked.

DATE: Middle Eighteenth Dynasty.

TECHNIQUE: coarse.

PRESERVATION: fair.

BIBL.: MASPERO, *Slip Cat.*, No. 4570.





## INDEX TO ROYAL NAMES.

- Aahmes I, 36071, 36072.  
 Aahmes II, 37398.  
 Aahmes-nefret-ari, Queen of Aahmes I, 36073-5.  
 Aa-kheper-ka-Ra, *see* Thothmes I.  
 Aa-kheperu-Ra, *see* Amenhetep II.  
 Aa-mu, 36040.  
 Akhen-aten, 36235-36237.  
 Amenardes, 36293, 36295, 36296.  
 Amenemhat III, 37411, 37413, 37515.  
 Amenhetep I, 36076-36085.  
 Amenhetep II, 36201-4, 36309.  
 Amenhetep III, 36208-36232, 37389-37393.  
 Amenhetep IV, *see* Akhenaten.  
 Anket-aba, mother of Sekhem-se-naz-tau-Ra, 36012.  
 Aÿ, 36021-36024.  
  
 Ded-ka-Ra, *see* Shabataka.  
  
 Ha-ankh-ef, father of Kha-seshes-Ra, 36013.  
 Ha-ankh-ef, father of Kha-nefer-Ra, 36017, 36018.  
 Hatshepsut, 36095-7.  
 Heq-maat-Ra, *see* Rameses IV.  
 Horem-heb, 36238.  
  
 Isit-em-kheb, Queen, 37426.  
 Iua, father of Queen Týi, 37393.  
  
 Kashita, 36293, 36296.  
 Kema, mother of Sebekhetep, 36019.  
 Kha-hetep-Ra, 36020.  
 Kha-ka-Ra, 36009, 36025.  
 Kha-kau-Ra, 37401.  
 Kha-kheper-Ra, 36008.  
 Kha-mu, 36042.  
 Kha-nefer-Ra, 36014-36018.  
  
 Kha-seshes-Ra, 36013.  
 Kha-user-Ra, 36041.  
 Khnem-ab-Ra, 37398.  
 Khufu, 36001.  
 Khÿan (*Heq Khasket*), 36027.  
  
 Maa-ab-Ra, 36030-36035.  
 Maat-ka-Ra, *see* Hatshepsut.  
 Men-ka-Ra, 36003-36005.  
 Men-kheper-Ra (Thothmes III), 36098-36200, 37371, 37372, 37376, 37377.  
 Men-kheper-Ra-ka (Thothmes III), 37425.  
 Men-kheper-Ra, 37426.  
 Men-kheperu-Ra, *see* Thothmes IV.  
 Men-pehti-Ra, *see* Setÿ I.  
 Mentu-hetep, father of Sebekhetep, 36011.  
 Mereryt (Princess), 37404-37408.  
 Mer-nefer-Ra (Aÿ), 36021-36024.  
  
 Neb-maa-Ra, *see* Amenhetep III.  
 Neb-pehti-Ra, *see* Aahmes I.  
 Nefer-ab (?), 37433.  
 Nefer-ka-Ra, 36002.  
 Nefer-ka-Ra Shabaka, 37397.  
 Nefret-ari, 37380.  
 Nefret-ari-mer-en-Mut, 36290.  
 Nefer-kheperu-Ra, *see* Amenhetep IV.  
 Nekho, 37399.  
 Ne-maat-Ra, *see* Amenemhat III.  
 Nub-ka-Ra (?), 36241.  
 Nub-maat-Ra, 36346.  
  
 Osorkon II, 36289.  
  
 Psamtek I, 36299, 36302-36305, 36308.  
  
 Qar (?), 36043.

- Rameses I, 36239.  
 Rameses II, 36255-36279, 36287, 36306, 37396.  
 Rameses III, 36283.  
 Rameses IV, 36286.
- Sa-hathor, Prince, 36026.  
 Sa-mentu, 36288.  
 Sat-hathor, Princess, 37400.  
 Sat-aah (?), Queen of Thothmes III, 36513.  
 Sebekhetep, 36012, 36015, 36016, 36019, 36020.  
 Sekhem-se-uaz-taui-Ra, 36011, 36012.  
 Senusret, 36010.  
 Sety I, 36240, 36250-36254.  
 Sety II, 36284, 36285.  
 Shabaka, 37397.  
 Shabataka, 36300.  
 Shesha, 36036-36039.  
 Sheshanq, 36292, 36294, 36297.
- Ta-harqa, 36291, 36301.  
 Thyï, Queen, 36233, 36234, 37389, 37393.  
 Thothmes I, 36086-36093.  
 Thothmes II, 36094.  
 Thothmes III, *see* Men-kheper-Ra.  
 Thothmes IV, 36205-36207.
- Uah-ab-Ra, 36302.  
 Uazed, 36029.  
 Uhem-ab-Ra (Nekho), 37399.  
 Unas, 36006, 36007.  
 User-maat-ra, *see* Rameses II.  
 User-kheper-ra, 36285.
- Yabekher, 36028.
- Zeser-kheper-ka, *see* Amenhetep I.  
 Zeser-kheperu-Ra, *see* Hor-em-heb.

PLATE I.






PLATE II.





PLATE III.



Generated for eijk6c (University of Virginia) on 2017-02-09 06:36 GMT / http://hdl.handle.net/2027/mdp.39015013775245  
Public Domain in the United States; Google-digitized / http://www.hathitrust.org/access\_use#pd-us-google









PLATE V.





PLATE VI.





PLATE VII.







PLATE VIII.






PLATE IX.





PLATE IX.





PLATE X








PLATE XI.





PLATE XII.






PLATE XIII.






PLATE XIV.



Generated for eijk6c (University of Virginia) on 2017-02-09 06:36 GMT / http://hdl.handle.net/2027/mdp.39015013775245  
Public Domain in the United States; Google-digitized / http://www.hathitrust.org/access\_use#pd-us-google





PLATE XV.






PLATE XVI.








PLATE XVII



37398




37397



37396



37389




37393




37390



PLATE XVIII.



37439




37443




37432




37426




37430




37435




37438



37431



37434



37425




37404



37401



37402



37409




37416



37410



37408




37411



37405



37407



37404



37409



37410




37412



37403



37414



37413



37415



37420




37417







PLATE XIX.



Types of Backs without the Prothorax or Elytra marked.



The SHESHA TYPE.



Types of Backs with the Prothorax slightly indicated but no Elytra marked.






PLATE XX



Types of Backs with the Prothorax slightly indicated but no Elytra marked








Types of Backs with Prothorax marked but no Elytra shown



Miscellaneous Examples




PLATE XXI.



Types of Backs with the Prothorax and Elytra marked and with Rounded Prothorax and Elytra marked.



PLATE XXII



Types of Backs with Prothorax and Elytra marked with a V-shaped cutting on either wing-case.









